

1.1.1 Band II EIRP

Band II									
ENV	Mode		Frequency (MHz)	Conducted Power (dBm)	Gain (dBi)	EIRP (dBm)		Verdict	
	Network	Subset				Result	Limit		
NTNV	RMC	12.2kbps RMC	1852.4	23.89	2.79	26.68	<=33.01	Pass	
			1880	24.09	2.79	26.88	<=33.01	Pass	
			1907.6	23.79	2.79	26.58	<=33.01	Pass	
	HSDPA	Subtest 1	1852.4	22.04	2.79	24.83	<=33.01	Pass	
		Subtest 2	1852.4	21.99	2.79	24.78	<=33.01	Pass	
		Subtest 3	1852.4	21.94	2.79	24.73	<=33.01	Pass	
		Subtest 4	1852.4	22.06	2.79	24.85	<=33.01	Pass	
		Subtest 1	1880	22.08	2.79	24.87	<=33.01	Pass	
		Subtest 2	1880	22.19	2.79	24.98	<=33.01	Pass	
		Subtest 3	1880	22.12	2.79	24.91	<=33.01	Pass	
		Subtest 4	1880	22.22	2.79	25.01	<=33.01	Pass	
		Subtest 1	1907.6	21.84	2.79	24.63	<=33.01	Pass	
		Subtest 2	1907.6	21.94	2.79	24.73	<=33.01	Pass	
		Subtest 3	1907.6	21.88	2.79	24.67	<=33.01	Pass	
		Subtest 4	1907.6	21.86	2.79	24.65	<=33.01	Pass	
		HSUPA	Subtest 1	1852.4	20.73	2.79	23.52	<=33.01	Pass
			Subtest 2	1852.4	20.74	2.79	23.53	<=33.01	Pass
	Subtest 3		1852.4	20.74	2.79	23.53	<=33.01	Pass	
	Subtest 4		1852.4	20.74	2.79	23.53	<=33.01	Pass	
	Subtest 1		1880	20.80	2.79	23.59	<=33.01	Pass	
	Subtest 2		1880	20.70	2.79	23.49	<=33.01	Pass	
	Subtest 3		1880	20.44	2.79	23.23	<=33.01	Pass	
	Subtest 4		1880	20.47	2.79	23.26	<=33.01	Pass	
	Subtest 5		1880	20.70	2.79	23.49	<=33.01	Pass	
	Subtest 1		1907.6	20.46	2.79	23.25	<=33.01	Pass	
	Subtest 2		1907.6	20.03	2.79	22.82	<=33.01	Pass	
	Subtest 3		1907.6	20.14	2.79	22.93	<=33.01	Pass	
Subtest 4	1907.6		20.46	2.79	23.25	<=33.01	Pass		
Subtest 5	1907.6	20.46	2.79	23.25	<=33.01	Pass			

Note1: EIRP=Conducted Power+Antenna Gain