



Shenzhen Certification Technology Service Co., Ltd
2F, Building B, East Area of Nanchang Second Industrial Zone,
Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China

TEST REPORT

FCC ID: LU7-TS100

Applicant : Shenzhen YIDONG Technology Co., Ltd.
Address : Floor 1-5,Building B, Area B, Yuanfen Industrial Zone, Dalang,
Bao'an District, Shenzhen, China

Equipment under Test (EUT):

Name : Flat Computer

Model : TS100, EMR3074

Standards : FCC PART 15, Subpart B (Class B): 2012

Report No. : CST-TCB131217003-1

Date of Test : December 18-31, 2013

Date of Issue : January 4, 2014

Test Result :	PASS *
----------------------	---------------

* In the configuration tested, the EUT complied with the standards specified above

Authorized Signature

(Mark Zhu)
General Manager

The manufacture should ensure that all the products in series production are in conformity with the product sample detailed in this report.

If the product in this report is used in any configuration other than that detailed in the report, the manufacturer must ensure the new system complies with all relevant standards. Any mention of Shenzhen Certification Technology Service Co., Ltd. Or test done by Shenzhen Certification Technology Service Co., Ltd. Approvals in connection with, distribution or use of the product described in this report must be approved by Shenzhen Certification Technology Service Co., Ltd. Approvals in writing.

TABLE OF CONTENTS

<u>Description</u>	<u>Page</u>
Test Report Declaration	3
1. Summary of standards and results.....	4
1.1. Description of Standards and Results.....	4
2. GENERAL INFORMATION.....	5
2.1. Description of Device (EUT)	5
2.2. Tested Supporting System Details	6
2.3. Block Diagram of connection between EUT and simulators	6
2.4. Test Facility.....	7
2.5. Measurement Uncertainty	7
3. POWER LINE CONDUCTED Emission test	8
3.1. Test Equipment.....	8
3.2. Block Diagram of Test Setup	8
3.3. Power Line Conducted Emission Test Limits	8
3.4. Configuration of EUT on Test.....	9
3.5. Operating Condition of EUT	9
3.6. Test Procedure	9
3.7. Conducted Disturbance at Mains Terminals Test Results.....	9
4. Radiated emission Test.....	18
4.1. Test Equipment.....	18
4.2. Block Diagram of Test Setup	18
4.3. Radiated Emission Limit	19
4.4. EUT Configuration on Test.....	19
4.5. Operating Condition of EUT	20
4.6. Test Procedure	20
4.7. Radiated Disturbance Test Results.....	20
5. Photograph	37
5.1. Photos of Power Line Conducted Emission Test	37
5.2. Photos of Radiated Emission Test (In Anechoic Chamber).....	38
6. Photos of the EUT	40

TEST REPORT VERIFICATION

Applicant : Shenzhen YIDONG Technology Co., Ltd.
Manufacturer : Shenzhen YIDONG Technology Co., Ltd.
EUT Description : Flat Computer
(A) Model No. : TS100, EMR3074
(B) Trademark : N/A
(C) DIFF : Only different in Model No, the other the same.
The test model: TS100
(C) Power Supply : DC 5V From Adapter
(D) Test Voltage : DC 5V From Adapter AC 120V/60Hz

Measurement Standard Used:
FCC PART 15, Subpart B (Class B): 2012

The device described above is tested by Shenzhen Certification Technology Service Co., Ltd. to determine the maximum emission levels emanating from the device. The maximum emission levels are compared to the FCC Part 15 Subpart B Class B limits both conducted and radiated emissions. The test results are contained in this test report and Shenzhen Certification Technology Service Co., Ltd. is assumed of full responsibility for the accuracy and completeness of these tests.

After the test, our opinion is that EUT compliance with the requirement of the above standards.

This report applies to above tested sample only. This report shall not be reproduced in parts without written approval of Shenzhen Certification Technology Service Co., Ltd.

1. SUMMARY OF STANDARDS AND RESULTS

1.1. Description of Standards and Results

The EUT have been tested according to the applicable standards as referenced below.

EMISSION			
Description of Test Item	Standard	Limits	Results
Power Line Conducted Emission Test	FCC Part 15: 2012 ANSI C63.4: 2003	Class B	PASS
Radiated Emission Test	FCC Part 15: 2012 ANSI C63.4: 2003	Class B	PASS

2. GENERAL INFORMATION

2.1. Description of Device (EUT)

Description : Flat Computer

Model Number : TS100

Trademark : N/A

Power Supply : DC 5V From Adapter

Adapter 1 : Information: Switching power adapter

Model: WRP2U-050200C

Input: AC 100-240V, 50/60Hz 0.3A

Output: DC 5V, 1.5A

Adapter 2 : Information: Switching power adapter

Model: SCT-A520B-D

Input: AC 100-240V, 50/60Hz 0.4A max

Output: DC 5V, 1.5A

Applicant : Shenzhen YIDONG Technology Co.,Ltd.

Floor 1-5,Building B, Area B, Yuanfen Industrial Zone, Dalang,

Bao'an District, Shenzhen, China

Manufacturer : Shenzhen YIDONG Technology Co.,Ltd.

Floor 1-5,Building B, Area B, Yuanfen Industrial Zone, Dalang,

Bao'an District, Shenzhen, China


Date of Test : December 18-31, 2013

Sample Type : Series production

2.2. Tested Supporting System Details

No.	Description	Manufacturer	Model	Serial Number
1.	Personal Computer	ACER	ASPIRE M1830	PTSF90C00305005CAC3000
2.	Monitor	ACER	G205HV	SNID:10306738385
3.	USB Keyboard	ACER	SK-9625	KBUSB1580500037E0100
4.	USB Mouse	ACER	MS.11200.014	M-UAY-ACR2
5.	Printer	HP	HP1020	CNCJ410726
Note: These equipment has FCC DOC certificate.				

2.3. Block Diagram of connection between EUT and simulators



※ EUT: Flat Computer

2.4. Test Facility

JAN 13, 2012 File on Federal Communication Commission
Registration Number: 197647

October 11, 2011 Certificated by IC
Registration Number: 8528B

2.5. Measurement Uncertainty

(95% confidence levels, k=2)


Test Item	Uncertainty
Uncertainty for Conduction emission test	2.50dB
Uncertainty for Radiation Emission test	3.04 dB (Distance: 3m Polarize: V)
	3.02 dB (Distance: 3m Polarize: H)
Uncertainty for Radiation Emission test (1GHz-18GHz)	3.56 dB (Distance: 3m Polarize: V)
	3.84 dB (Distance: 3m Polarize: H)
Uncertainty for test site temperature and humidity	0.6°C
	3%

3. POWER LINE CONDUCTED EMISSION TEST

3.1. Test Equipment

Item	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
1.	Test Receiver	Rohde&Schwarz	ESCI	1166.5950K03-1011	Oct. 30, 13	1 Year
2.	L.I.S.N.	Schwarzbeck	NSLK8126	8126466	Oct. 30, 13	1 Year
3.	L.I.S.N.-2	Kyoritsu	KNW-407	8-1628-5	Oct. 30, 13	1 Year
4.	Terminator	Hubersuhner	50Ω	No. 1	Oct. 30, 13	1 Year
5.	RF Cable	Schwarzbeck	9111505/200	5995-12-161-6890#	Oct. 30, 13	1Year
6.	Coaxial Switch	Schwarzbeck	CX-210	N/A	Oct. 30, 13	1 Year
7.	Pulse Limiter	Schwarzbeck	VTSD9516F	9618	Oct. 30, 13	1 Year

3.2. Block Diagram of Test Setup



3.3. Power Line Conducted Emission Test Limits

Frequency	Maximum RF Line Voltage	
	Quasi-Peak Level dB(μV)	Average Level dB(μV)
150kHz ~ 500kHz	66 ~ 56*	56 ~ 46*
500kHz ~ 5MHz	56	46
5MHz ~ 30MHz	60	50

Notes: 1. Emission level=Read level+ LISN factor-Preamp factor+ Cable loss

2* Decreasing linearly with logarithm of frequency.

3. The lower limit shall apply at the transition frequencies.

3.4. Configuration of EUT on Test

The following equipment are installed on Power Line Conducted Emission Test to meet the commission requirement and operating regulations in a manner which tends to maximize its emission characteristics in a normal application.

Support Equipments : As Tested Supporting System Detail, in Section 2.2.

3.5. Operating Condition of EUT

3.5.1. Setup the EUT and simulator as shown as Section 3.2.

3.5.2. Turn on the power of all equipment.

3.5.3. Let the EUT work in test mode (ON) and measure it.

3.6. Test Procedure

The EUT was placed on a non-metallic table, 80cm above the ground plane. The EUT Power connected to the power mains through a line impedance stabilization network (L.I.S.N. 1#). The other peripheral devices power cord connected to the power mains through a line impedance stabilization network (L.I.S.N. #2), this provided a 50-ohm coupling impedance for the EUT (Please refer to the block diagram of the test setup and photographs). Both sides of power line were checked for maximum conducted interference. In order to find the maximum emission, the relative positions of equipments and all of the interface cables were changed according to ANSI C63.4-2003 on conducted Emission test.

The bandwidth of test receiver (R&S TEST RECEIVER ESCI) is set at 10kHz.

The frequency range from 150KHz to 30MHz is checked. The test result are reported on Section 3.7.

3.7. Conducted Disturbance at Mains Terminals Test Results

PASS. (All emissions not reported below are too low against the prescribed limits.)

The EUT with the following test mode was tested and read Q.P values and average values, the test results are listed in next pages.

Temperature: 24°C Humidity: 56%


The details of test mode is as follows :

NO.	Test Mode
1.	Charge And Data Transmitting for adapter 1
2.	Charge And Play Video for adapter 1
3.	Charge And Data Transmitting for adapter 2
4.	Charge And Play Video for adapter 2



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 27 File: E:\TEST REPORT\WuXian\YiDong\Conduction CN-1.EM6 (42) Date: 2013-12-24 Time: 13:56:12



Condition : FCC PART 15 B QP POL: NEUTRAL Temp: 20 °C Hum: 53 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging and Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : WRP2U-050200C


Item	Freq MHz	Read dBuV	LISN Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	0.190	50.12	0.03	-9.72	0.10	59.97	64.02	-4.05	QP
2	0.190	37.12	0.03	-9.72	0.10	46.97	54.02	-7.05	Average
3	0.317	43.90	0.03	-9.72	0.10	53.75	59.80	-6.05	QP
4	0.317	28.90	0.03	-9.72	0.10	38.75	49.80	-11.05	Average
5	0.444	40.30	0.03	-9.72	0.10	50.15	56.98	-6.83	QP
6	0.444	24.30	0.03	-9.72	0.10	34.15	46.98	-12.83	Average
7	0.567	38.22	0.03	-9.72	0.10	48.07	56.00	-7.93	QP
8	0.567	22.22	0.03	-9.72	0.10	32.07	46.00	-13.93	Average
9	2.900	26.93	0.07	-9.70	0.12	36.82	56.00	-19.18	QP
10	2.900	10.93	0.07	-9.70	0.12	20.82	46.00	-25.18	Average
11	10.905	27.36	0.23	-9.49	0.22	37.30	60.00	-22.70	QP
12	10.905	12.36	0.23	-9.49	0.22	22.30	50.00	-27.70	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 29 File: E:\TEST REPORT\WuXian\YiDong\Conduction CN-1.EM6 (42) Date: 2013-12-24 Time: 13:58:19




Condition : FCC PART 15 B QP POL: LINE Temp: 20 °C Hum: 53 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging and Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : WRP2U-050200C

Item	Freq MHz	Read dBuV	LISN Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	0.190	47.61	0.03	-9.72	0.10	57.46	64.02	-6.56	QP
2	0.190	36.61	0.03	-9.72	0.10	46.46	54.02	-7.56	Average
3	0.317	39.20	0.03	-9.72	0.10	49.05	59.80	-10.75	QP
4	0.317	25.20	0.03	-9.72	0.10	35.05	49.80	-14.75	Average
5	0.567	34.36	0.03	-9.72	0.10	44.21	56.00	-11.79	QP
6	0.567	23.36	0.03	-9.72	0.10	33.21	46.00	-12.79	Average
7	1.585	25.78	0.05	-9.71	0.10	35.64	56.00	-20.36	QP
8	1.585	16.78	0.05	-9.71	0.10	26.64	46.00	-19.36	Average
9	2.839	21.44	0.07	-9.70	0.12	31.33	56.00	-24.67	QP
10	2.839	12.44	0.07	-9.70	0.12	22.33	46.00	-23.67	Average
11	7.852	20.65	0.14	-9.49	0.16	30.44	60.00	-29.56	QP
12	7.852	7.65	0.14	-9.49	0.16	17.44	50.00	-32.56	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com



Condition : FCC PART 15 B QP POL: LINE Temp: 24 °C Hum: 56 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : WRP2U-050200C

Item	Freq MHz	Read dBUV	LISN Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBUV	Limit dBUV	Margin dBUV	Remark
1	0.182	49.62	0.03	-9.72	0.10	59.47	64.42	-4.95	QP
2	0.182	31.62	0.03	-9.72	0.10	41.47	54.42	-12.95	Average
3	0.242	45.60	0.03	-9.72	0.10	55.45	62.04	-6.59	QP
4	0.242	32.60	0.03	-9.72	0.10	42.45	52.04	-9.59	Average
5	0.541	38.28	0.03	-9.72	0.10	48.13	56.00	-7.87	QP
6	0.541	21.28	0.03	-9.72	0.10	31.13	46.00	-14.87	Average
7	0.963	35.90	0.04	-9.71	0.10	45.75	56.00	-10.25	QP
8	0.963	22.90	0.04	-9.71	0.10	32.75	46.00	-13.25	Average
9	2.707	38.44	0.07	-9.70	0.11	48.32	56.00	-7.68	QP
10	2.707	19.44	0.07	-9.70	0.11	29.32	46.00	-16.68	Average
11	6.557	29.97	0.12	-9.57	0.15	39.81	60.00	-20.19	QP
12	6.557	14.97	0.12	-9.57	0.15	24.81	50.00	-25.19	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss




Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 39

File: E:\TEST REPORT\WuXianYiDong\Conduction CN-1.EM6 (42)

Date: 2013-12-22 Time: 10:12:29



Condition : FCC PART 15 B QP POL: NEUTRAL Temp:24 °C Hum:56 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charge And Data transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : WRP2U-050200C


Item	Freq MHz	Read dBuV	LISN Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	0.182	48.46	0.03	-9.72	0.10	58.31	64.42	-6.11	QP
2	0.182	31.46	0.03	-9.72	0.10	41.31	54.42	-13.11	Average
3	0.844	36.91	0.04	-9.71	0.10	46.76	56.00	-9.24	QP
4	0.844	15.91	0.04	-9.71	0.10	25.76	46.00	-20.24	Average
5	2.707	31.14	0.07	-9.70	0.11	41.02	56.00	-14.98	QP
6	2.707	15.14	0.07	-9.70	0.11	25.02	46.00	-20.98	Average
7	3.901	31.79	0.08	-9.69	0.12	41.68	56.00	-14.32	QP
8	3.901	12.79	0.08	-9.69	0.12	22.68	46.00	-23.32	Average
9	5.594	32.21	0.10	-9.64	0.13	42.08	60.00	-17.92	QP
10	5.594	17.21	0.10	-9.64	0.13	27.08	50.00	-22.92	Average
11	15.226	23.81	0.24	-9.38	0.24	33.67	60.00	-26.33	QP
12	15.226	8.81	0.24	-9.38	0.24	18.67	50.00	-31.33	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 41 File: E:\TEST REPORT\WuXianYiDong\Conduction CN-1.EM6 (48) Date: 2013-12-23 Time: 16:07:57



Condition : FCC PART 15 B QP POL: NEUTRAL Temp:24 °C Hum:56 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging and Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : STC-A520B-D


Item	Freq MHz	Read dBuV	LISN Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	0.188	45.29	0.03	-9.72	0.10	55.14	64.11	-8.97	QP
2	0.188	29.29	0.03	-9.72	0.10	39.14	54.11	-14.97	Average
3	0.313	37.61	0.03	-9.72	0.10	47.46	59.88	-12.42	QP
4	0.313	20.61	0.03	-9.72	0.10	30.46	49.88	-19.42	Average
5	0.567	35.40	0.03	-9.72	0.10	45.25	56.00	-10.75	QP
6	0.567	16.40	0.03	-9.72	0.10	26.25	46.00	-19.75	Average
7	1.568	30.41	0.05	-9.71	0.10	40.27	56.00	-15.73	QP
8	1.568	12.41	0.05	-9.71	0.10	22.27	46.00	-23.73	Average
9	2.809	25.90	0.07	-9.70	0.12	35.79	56.00	-20.21	QP
10	2.809	10.90	0.07	-9.70	0.12	20.79	46.00	-25.21	Average
11	7.977	23.10	0.14	-9.48	0.16	32.88	60.00	-27.12	QP
12	7.977	1.10	0.14	-9.48	0.16	10.88	50.00	-39.12	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 43 File: E:\TEST REPORT\WuXianYiDong\Conduction CN-1.EM6 (48) Date: 2013-12-23 Time: 16:14:32



Condition : FCC PART 15 B QP POL: LINE Temp: 24 °C Hum: 56 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging and Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : STC-A520B-D


Item	Freq MHz	Read dBuV	LISN Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	0.186	45.25	0.03	-9.72	0.10	55.10	64.20	-9.10	QP
2	0.186	29.25	0.03	-9.72	0.10	39.10	54.20	-15.10	Average
3	0.375	37.21	0.03	-9.72	0.10	47.06	58.39	-11.33	QP
4	0.375	24.21	0.03	-9.72	0.10	34.06	48.39	-14.33	Average
5	0.989	28.81	0.04	-9.71	0.10	38.66	56.00	-17.34	QP
6	0.989	18.81	0.04	-9.71	0.10	28.66	46.00	-17.34	Average
7	1.610	28.09	0.05	-9.71	0.10	37.95	56.00	-18.05	QP
8	1.610	20.09	0.05	-9.71	0.10	29.95	46.00	-16.05	Average
9	3.547	22.02	0.08	-9.69	0.12	31.91	56.00	-24.09	QP
10	3.547	4.02	0.08	-9.69	0.12	13.91	46.00	-32.09	Average
11	7.935	18.73	0.14	-9.48	0.16	28.51	60.00	-31.49	QP
12	7.935	2.73	0.14	-9.48	0.16	12.51	50.00	-37.49	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 45 File: E:\TEST REPORT\WuXianYiDong\Conduction CN-1.EM6 (48) Date: 2013-12-23 Time: 16:17:48



Condition : FCC PART 15 B QP POL: LINE Temp: 24 °C Hum: 56 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging and Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : STC-A520B-D


Item	Freq MHz	Read dBuV	LISN Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	0.192	45.33	0.03	-9.72	0.10	55.18	63.93	-8.75	QP
2	0.192	32.33	0.03	-9.72	0.10	42.18	53.93	-11.75	Average
3	0.385	32.62	0.03	-9.72	0.10	42.47	58.17	-15.70	QP
4	0.385	19.62	0.03	-9.72	0.10	29.47	48.17	-18.70	Average
5	1.480	24.02	0.05	-9.71	0.10	33.88	56.00	-22.12	QP
6	1.480	14.02	0.05	-9.71	0.10	23.88	46.00	-22.12	Average
7	2.622	21.51	0.06	-9.70	0.11	31.38	56.00	-24.62	QP
8	2.622	13.51	0.06	-9.70	0.11	23.38	46.00	-22.62	Average
9	4.874	17.25	0.10	-9.68	0.12	27.15	56.00	-28.85	QP
10	4.874	8.25	0.10	-9.68	0.12	18.15	46.00	-27.85	Average
11	7.606	18.49	0.14	-9.50	0.16	28.29	60.00	-31.71	QP
12	7.606	5.49	0.14	-9.50	0.16	15.29	50.00	-34.71	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 Fax: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 47 File: E:\TEST REPORT\WuXianYiDong\Conduction CN-1.EM6 (48) Date: 2013-12-23 Time: 16:19:19



Condition : FCC PART 15 B QP POL: NEUTRAL Temp:24 °C Hum:56 %
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging and Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer: Store
 Remark : STC-A520B-D

Item	Freq MHz	Read dBuV	LISN Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	0.192	47.45	0.03	-9.72	0.10	57.30	63.93	-6.63	QP
2	0.192	31.45	0.03	-9.72	0.10	41.30	53.93	-12.63	Average
3	0.256	42.32	0.03	-9.72	0.10	52.17	61.56	-9.39	QP
4	0.256	27.32	0.03	-9.72	0.10	37.17	51.56	-14.39	Average
5	0.447	35.85	0.03	-9.72	0.10	45.70	56.93	-11.23	QP
6	0.447	21.85	0.03	-9.72	0.10	31.70	46.93	-15.23	Average
7	1.535	26.75	0.05	-9.71	0.10	36.61	56.00	-19.39	QP
8	1.535	15.75	0.05	-9.71	0.10	25.61	46.00	-20.39	Average
9	2.809	22.78	0.07	-9.70	0.12	32.67	56.00	-23.33	QP
10	2.809	11.78	0.07	-9.70	0.12	21.67	46.00	-24.33	Average
11	7.606	22.53	0.14	-9.50	0.16	32.33	60.00	-27.67	QP
12	7.606	7.53	0.14	-9.50	0.16	17.33	50.00	-32.67	Average

Remarks: Level = Read + LISN Factor - Preamp Factor + Cable loss

4. RADIATED EMISSION TEST

4.1. Test Equipment


Item	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
1	Test Receiver	Rohde&Schwarz	ESCI	1166.5950K06-1012	Oct. 30, 13	1 Year
2	Amplifier	Schwarzbeck	BBV9743	9743-019	Oct. 30, 13	1 Year
3	Bilog Antenna	Schwarzbeck	VULB 9168	VULB9168-438	Mar.12, 13	1 Year
4	RF Cable	Schwarzbeck	AK9515E	95891-2m	Oct. 30, 13	1 Year
5	RF Cable	Schwarzbeck	AK9515E	95891-11m	Oct. 30, 13	1 Year
6	RF Cable	Schwarzbeck	AK9515E	95891-0.5m	Oct. 30, 13	

For frequency range 1GHz~5GHz (At Semi Anechoic Chamber)


Item	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
1	Spectrum Analyzer	Agilent	E4446A	US44300459	Oct. 30, 13	1 Year
2	Horn Antenna	EMCO	BBV9743	9743-019	Mar.12, 13	1 Year
3	Amplifier	Schwarzbeck	SCHWARZBECK	N/A	Oct. 30, 13	1 Year
4	RF Cable	Hubersuhner	SUCOFLEX102	28620/2	Oct. 30, 13	1 Year
5	RF Cable	Hubersuhner	SUCOFLEX102	271471/4	Oct. 30, 13	1 Year
6	RF Cable	Hubersuhner	SUCOFLEX102	29086/2	Oct. 30, 13	1 Year

4.2. Block Diagram of Test Setup

4.2.1. In Semi Anechoic Chamber (3m) Test Setup Diagram for 30MHz~1000MHz



4.2.2. In Semi Anechoic Chamber (3m) Test Setup Diagram for 1-5GHz



4.3. Radiated Emission Limit

Frequency MHz	Distance (Meters)	Field Strengths Limits dB(μ V)/m
30 ~ 88	3	40.0
88 ~ 216	3	43.5
216 ~ 960	3	46.0
960 ~ 1000	3	54.0
1000 ~ 6000	3	74(Peak) 54(Average)

Remark: (1) Emission level = Read level + Antenna Factor - Preamp Factor + Cable Loss

(2) The smaller limit shall apply at the cross point between two frequency bands.

(3) Distance is the distance in meters between the measuring instrument, antenna and the closest point of any part of the device or system.

4.4. EUT Configuration on Test

The following equipment are installed on Radiated Emission Test to meet the commission requirements and operating regulations in a manner that tends to maximize its emission characteristics in normal application.

4.4.1. Support Equipments : As Tested Supporting System Detail, in Section 2.2.

4.5. Operating Condition of EUT

- 4.5.1. Setup the EUT as shown in Section 4.2.
- 4.5.2. Turn on the power of all equipment.
- 4.5.3. Let the EUT work in test mode (ON) and test it.

4.6. Test Procedure

The EUT was placed on a non-metallic table, 80 cm above the ground plane inside a semi-anechoic chamber. An antenna was located 3m from the EUT on an adjustable mast. A pre-scan was first performed in order to find prominent radiated emissions. For final emissions measurements at each frequency of interest, the EUT were rotated and the antenna height was varied between 1m and 4m in order to maximize the emission. Measurements in both horizontal and vertical polarities were made and the data was recorded. In order to find the maximum emission, the relative positions of equipments and all of the interface cables were changed according to ANSI C63.4-2003 on Radiated Emission test.

The bandwidth setting on the test receiver (ROHDE&SCHWARZ TEST RECEIVER ESCI) is 120 kHz.

The resolution bandwidth of the Agilent Spectrum Analyzer E4446A was set at 1MHz. (For above 1GHz)

The frequency range from 30MHz to 1000MHz was pre-scanned with a peak detector and all final readings of measurement from Test Receiver are Quasi-Peak values.

The frequency range from 1GHz to 5GHz was checked with peak and average detector, measurement distance is 3m in 3m chamber.

Finally, selected operating situations at Anechoic Chamber measurement, all the test results are listed in section 4.7.

4.7. Radiated Disturbance Test Results

PASS. (All emissions not reported below are too low against the prescribed limits.)

For frequency range 30MHz~6000MHz

The EUT with the following test mode was tested and read Q.P values, all the test results listed in next pages.

Temperature: 25.2°C Humidity: 56%

The details of test mode is as follows :

NO.	Test Mode
1.	Charge And Data Transmitting for adapter 1
2.	Charge And Play Video for adapter 1
3.	Charge And Data Transmitting for adapter 2
4.	Charge And Play Video for adapter 2




Shenzhen Certification Technology Service Co., Ltd.
2F, Building B, East Area of Nanchang Second Industrial Zone,
Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
Tel: 400



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 2




Condition : FCC PART 15 B 3m POL: VERTICAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : WRP2U-050200C
 Temp : 24.2℃
 Hum : 50%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	41.57	37.62	13.93	27.81	0.19	23.93	40.00	-16.07	QP
2	58.00	37.76	12.91	27.86	0.23	23.04	40.00	-16.96	QP
3	122.40	49.61	12.35	26.88	0.43	35.51	43.50	-7.99	QP
4	239.99	44.80	11.45	27.09	0.53	29.69	46.00	-16.31	QP
5	510.04	36.51	16.68	27.64	0.68	26.23	46.00	-19.77	QP
6	721.73	41.45	19.92	27.73	1.26	34.90	46.00	-11.10	QP

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com




Condition : FCC PART 15_18G PEAK 3m POL: VERTICAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : WRP2U-050200C
 Temp : 24.2°C
 Hum : 50%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	1195.00	55.47	24.32	34.90	2.31	47.20	54.00	-6.80	Average
2	1195.00	68.47	24.32	34.90	2.31	60.20	74.00	-13.80	Peak
3	1780.00	58.89	24.92	34.83	3.38	52.36	74.00	-21.64	Peak
4	2375.00	50.94	27.65	34.97	3.91	47.53	54.00	-6.47	Average
5	2375.00	58.94	27.65	34.97	3.91	55.53	74.00	-18.47	Peak
6	2770.00	55.19	27.89	34.98	4.23	52.33	74.00	-21.67	Peak
7	3475.00	50.76	28.40	34.91	4.83	49.08	54.00	-4.92	Average
8	3475.00	55.76	28.40	34.91	4.83	54.08	74.00	-19.92	Peak
9	4335.00	48.05	30.23	34.53	5.39	49.14	74.00	-24.86	Peak

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com




Condition : FCC PART 15_18G PEAK 3m POL: HORIZONTAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : WRP2U-050200C
 Temp : 24.2°C
 Hum : 50%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	1190.00	56.49	24.32	34.90	2.31	48.22	54.00	-5.78	Average
2	1190.00	62.49	24.32	34.90	2.31	54.22	74.00	-19.78	Peak
3	1865.00	56.91	25.22	34.87	3.50	50.76	74.00	-23.24	Peak
4	2375.00	57.13	27.65	34.97	3.91	53.72	74.00	-20.28	Peak
5	2640.00	50.00	27.79	34.98	4.13	46.94	54.00	-7.06	Average
6	2640.00	59.00	27.79	34.98	4.13	55.94	74.00	-18.06	Peak
7	3405.00	55.38	27.89	34.92	4.77	53.12	74.00	-20.88	Peak
8	4200.00	49.60	29.99	34.60	5.31	50.30	74.00	-23.70	Peak

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com




Condition : FCC PART 15 B 3m POL: VERTICAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : WRP2U-050200C
 Temp : 21.2°C
 Hum : 45%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	32.98	36.67	13.33	27.58	0.11	22.53	40.00	-17.47	QP
2	71.83	42.98	10.51	26.77	0.19	26.91	40.00	-13.09	QP
3	157.56	48.62	14.15	26.91	0.39	36.25	43.50	-7.25	QP
4	299.32	43.61	12.80	27.19	0.69	29.91	46.00	-16.09	QP
5	601.43	44.81	18.36	27.82	1.07	36.42	46.00	-9.58	QP
6	958.79	40.37	22.16	27.61	1.97	36.89	46.00	-9.11	QP

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com



Condition : FCC PART 15 B 3m POL: HORIZONTAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : WRP2U-050200C
 Temp : 21.2°C
 Hum : 45%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	98.83	46.98	10.15	26.84	0.38	30.67	43.50	-12.83	QP
2	131.76	46.89	12.79	26.89	0.57	33.36	43.50	-10.14	QP
3	150.01	45.07	14.16	26.91	0.39	32.71	43.50	-10.79	QP
4	299.32	51.26	12.80	27.19	0.69	37.56	46.00	-8.44	QP
5	451.14	43.71	15.99	27.49	1.08	33.29	46.00	-12.71	QP
6	760.70	42.63	20.38	27.67	1.45	36.79	46.00	-9.21	QP

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss




Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com





Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com



Condition : FCC PART 15_18G PEAK 3m POL: HORIZONTAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : WRP2U-050200C
 Temp : 24.2°C
 Hum : 50%


Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	1190.00	56.49	24.32	34.90	2.31	48.22	54.00	-5.78	Average
2	1190.00	64.49	24.32	34.90	2.31	56.22	74.00	-17.78	Peak
3	1720.00	51.82	24.74	34.80	3.28	45.04	74.00	-28.96	Peak
4	1980.00	54.19	25.80	34.93	3.60	48.66	74.00	-25.34	Peak
5	2770.00	48.90	27.89	34.98	4.23	46.04	54.00	-7.96	Average
6	2770.00	60.90	27.89	34.98	4.23	58.04	74.00	-15.96	Peak
7	3165.00	50.28	28.28	34.96	4.56	48.16	74.00	-25.84	Peak

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 7 File: E:\REPORT DATA\WuXian\YiDong\RE 12.24-D.EM6 (10) Date: 2014-01-07 Time: 09:01:17



Condition : FCC PART 15 B 3m POL: HORIZONTAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-AS20B-D
 Temp : 21.2°C
 Hum : 45%


Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	71.83	38.51	10.51	26.77	0.19	22.44	40.00	-17.56	QP
2	143.83	44.87	13.77	26.90	0.38	32.12	43.50	-11.38	QP
3	216.02	45.75	10.41	27.05	0.55	29.66	46.00	-16.34	QP
4	397.63	45.99	14.71	27.42	0.71	33.99	46.00	-12.01	QP
5	560.69	45.67	17.56	27.73	1.05	36.55	46.00	-9.45	QP
6	890.73	40.73	21.53	27.65	1.28	35.89	46.00	-10.11	QP

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 8 File: E:\REPORT DATA\WuXian\YiDong\RE 12.24-D.EM6 (10) Date: 2014-01-07 Time: 09:02:50




Condition : FCC PART 15 B 3m POL: VERTICAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-AS20B-D
 Temp : 21.2°C
 Hum : 45%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	53.88	43.96	13.22	27.84	0.21	29.55	40.00	-10.45	QP
2	71.83	47.36	10.51	26.77	0.19	31.29	40.00	-8.71	QP
3	143.83	38.40	13.77	26.90	0.38	25.65	43.50	-17.85	QP
4	396.24	43.08	14.68	27.42	0.75	31.09	46.00	-14.91	QP
5	627.27	45.63	18.82	27.82	0.98	37.61	46.00	-8.39	QP
6	760.70	42.19	20.38	27.67	1.45	36.35	46.00	-9.65	QP

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com




Condition : FCC PART 15_18G PEAK 3m POL: VERTICAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-AS20B-D
 Temp : 24.2°C
 Hum : 50%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	1185.00	56.46	24.32	34.90	2.28	48.16	54.00	-5.84	Average
2	1185.00	65.46	24.32	34.90	2.28	57.16	74.00	-16.84	Peak
3	1780.00	54.89	24.92	34.83	3.38	48.36	54.00	-5.64	Average
4	1780.00	59.89	24.92	34.83	3.38	53.36	74.00	-20.64	Peak
5	2885.00	55.25	28.00	34.98	4.34	52.61	74.00	-21.39	Peak
6	3475.00	49.76	28.40	34.91	4.83	48.08	54.00	-5.92	Average
7	3475.00	56.76	28.40	34.91	4.83	55.08	74.00	-18.92	Peak
8	3720.00	50.95	28.93	34.83	5.00	50.05	74.00	-23.95	Peak
9	4335.00	48.05	30.23	34.53	5.39	49.14	74.00	-24.86	Peak

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com



Condition : FCC PART 15_18G PEAK 3m POL: HORIZONTAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Playing Video
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-AS20B-D
 Temp : 24.2°C
 Hum : 50%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	1190.00	54.49	24.32	34.90	2.31	46.22	54.00	-7.78	Average
2	1190.00	65.49	24.32	34.90	2.31	57.22	74.00	-16.78	Peak
3	1980.00	58.19	25.80	34.93	3.60	52.66	74.00	-21.34	Peak
4	2375.00	55.13	27.65	34.97	3.91	51.72	74.00	-22.28	Peak
5	2770.00	50.90	27.89	34.98	4.23	48.04	54.00	-5.96	Average
6	2770.00	57.90	27.89	34.98	4.23	55.04	74.00	-18.96	Peak
7	3405.00	50.38	27.89	34.92	4.77	48.12	54.00	-5.88	Average
8	3405.00	56.38	27.89	34.92	4.77	54.12	74.00	-19.88	Peak
9	4320.00	49.35	30.20	34.54	5.39	50.40	74.00	-23.60	Peak

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss




Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 9

File: E:\REPORT DATA\WuXian\YiDong\RE 12.24-D.EM6 (10)

Date: 2014-01-07 Time: 09:01:17



Condition : FCC PART 15 B 3m POL: HORIZONTAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-AS20B-D
 Temp : 21.2°C
 Hum : 45%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	41.71	36.04	13.93	27.81	0.19	22.35	40.00	-17.65	QP
2	143.83	41.87	13.77	26.90	0.38	29.12	43.50	-14.38	QP
3	287.99	48.92	12.54	27.17	0.66	34.95	46.00	-11.05	QP
4	397.63	50.99	14.71	27.42	0.71	38.99	46.00	-7.01	QP
5	560.69	47.67	17.56	27.73	1.05	38.55	46.00	-7.45	QP
6	890.73	43.73	21.53	27.65	1.28	38.89	46.00	-7.11	QP

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss




Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com

Data: 10

File: E:\REPORT DATA\WuXian\YiDong\RE 12.24-D.EM6 (10)

Date: 2014-01-07 Time: 09:02:50




Condition : FCC PART 15 B 3m POL: VERTICAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-AS20B-D
 Temp : 21.2°C
 Hum : 45%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamplifier Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	32.98	40.10	13.33	27.58	0.11	25.96	40.00	-14.04	QP
2	67.20	47.82	11.21	26.98	0.28	32.33	40.00	-7.67	QP
3	143.83	48.40	13.77	26.90	0.38	35.65	43.50	-7.85	QP
4	287.99	43.87	12.54	27.17	0.66	29.90	46.00	-16.10	QP
5	396.24	46.08	14.68	27.42	0.75	34.09	46.00	-11.91	QP
6	627.27	45.63	18.82	27.82	0.98	37.61	46.00	-8.39	QP

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com




Condition : FCC PART 15_18G PEAK 3m POL: VERTICAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-A520B-D
 Temp : 24.2°C
 Hum : 50%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	1185.00	57.46	24.32	34.90	2.28	49.16	54.00	-4.84	Average
2	1185.00	65.46	24.32	34.90	2.28	57.16	74.00	-16.84	Peak
3	1980.00	52.52	25.80	34.93	3.60	46.99	54.00	-7.01	Average
4	1980.00	62.52	25.80	34.93	3.60	56.99	74.00	-17.01	Peak
5	2780.00	50.18	27.90	34.98	4.25	47.35	54.00	-6.65	Average
6	2780.00	58.18	27.90	34.98	4.25	55.35	74.00	-18.65	Peak
7	3565.00	50.86	28.69	34.90	4.90	49.55	74.00	-24.45	Peak
8	4105.00	47.38	29.86	34.65	5.25	47.84	74.00	-26.16	Peak
9	4755.00	43.86	31.18	34.25	5.67	46.46	74.00	-27.54	Peak

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss



Shenzhen Certification Technology Service Co., Ltd.
 2F, Building B, East Area of Nanchang Second Industrial Zone,
 Gushu 2nd Road, Bao'an District, Shenzhen 518126, P.R. China
 Tel: 4006786199 FAX: +86-755-26736857
 Website: <http://www.cessz.com> Email: Service@cessz.com



Condition : FCC PART 15_18G PEAK 3m POL: HORIZONTAL
 EUT : Flat Computer
 Model No : TS100
 Test Mode : Charging And Data Transmitting
 Power : DC 5V From Adapter AC 120V/60Hz
 Test Engineer : Store
 Remark : STC-AS20B-D
 Temp : 24.2°C
 Hum : 50%

Item	Freq MHz	Read Level dBuV	Antenna Factor dB	Preamp Factor dB	Cable Loss dB	Level dBuV	Limit dBuV	Margin dBuV	Remark
1	1190.00	57.49	24.32	34.90	2.31	49.22	54.00	-4.78	Average
2	1190.00	68.49	24.32	34.90	2.31	60.22	74.00	-13.78	Peak
3	1585.00	59.44	24.87	34.75	3.05	52.61	74.00	-21.39	Peak
4	1980.00	56.19	25.80	34.93	3.60	50.66	54.00	-3.34	Average
5	1980.00	61.19	25.80	34.93	3.60	55.66	74.00	-18.34	Peak
6	2375.00	52.13	27.65	34.97	3.91	48.72	54.00	-5.28	Average
7	2375.00	59.13	27.65	34.97	3.91	55.72	74.00	-18.28	Peak
8	2770.00	50.90	27.89	34.98	4.23	48.04	54.00	-5.96	Average
9	2770.00	63.90	27.89	34.98	4.23	61.04	74.00	-12.96	Peak
10	3165.00	55.28	28.28	34.96	4.56	53.16	74.00	-20.84	Peak

Remark: Level = Read Level + Antenna Factor - Preamp Factor + Cable Loss

5. PHOTOGRAPH

5.1.Photos of Power Line Conducted Emission Test




Adapter 1



Adapter 2


5.2.Photos of Radiated Emission Test (In Anechoic Chamber)



Adapter 1



Adapter 1



Adapter 2



Adapter 2

6. PHOTOS OF THE EUT



**Full View
(SCT-A520B-D)**




**Full View
(WRP2U-050200C)**



Front View



Rear View



Top View



Bottom View



Left View




Right View




Inside View



Inside View




Inside View




Inside View



Inside View



Inside View



Inside View

-----THE END OF REPORT-----