

TEST RESULT SUMMARY

FCC PART 15 SUBPART C**Section 15.231 (Transmitter)****FCC PART 15 SUBPART B****Class B (Receiver/Beacon Post)**

MANUFACTURER'S NAME	Dane Industries Inc
NAME OF EQUIPMENT	418 MHz Transmitter & Receiver/Beacon Post
MODEL NUMBER	100-030 (Transmitter) 100-027, 100-031, 100-072 (Receiver/Beacon Post)
MANUFACTURER'S ADDRESS	9855 13th Avenue N Plymouth MN 55441
TEST REPORT NUMBER	W9121
TEST DATE	22 February 1999

According to testing performed at TÜV Product Service Inc, the above-mentioned unit is in compliance with the electromagnetic compatibility requirements defined in FCC Part 15.

It is the manufacturer's responsibility to assure that additional production units of this model are manufactured with identical electrical and mechanical characteristics. Any modifications necessary for compliance made during testing on the above mentioned date(s) must be implemented in all production units for compliance to be maintained.

TÜV Product Service Inc, as an independent testing laboratory, declares that the equipment tested as specified above conforms to the requirements of FCC Part 15.

Date: 03 May 1999

Location: Taylors Falls MN
USA

J. C. Sausen
J. C. Sausen
Test Engineer

Joel T. Schneider
J. T. Schneider
NVLAP Signatory

EMC EMISSION - TEST REPORT

Test Report File No. : WC1G912101 Date of issue: 03 May 1999

Model / Serial No. : 100-030 (Transmitter)
100-027, 100-031, 100-072 (Receiver/Beacon Post)

Product Type : 418 MHz Transmitter & Receiver/Beacon Post

Applicant : Dane Industries Inc

Manufacturer : Dane Industries Inc

License holder : Dane Industries Inc

Address : 9855 13th Avenue N
Plymouth MN 55441

Test Result : Positive Negative

Test Project Number
 Reference(s) : W9121

Total pages including
 Appendices : 27

TÜV Product Service Inc is a subcontractor to TÜV Product Service, GmbH according to the principles outlined in ISO/IEC Guide 25 and EN 45001.

TÜV Product Service Inc reports apply only to the specific samples tested under stated test conditions. It is the manufacturer's responsibility to assure that additional production units of this model are manufactured with identical electrical and mechanical components. TÜV Product Service Inc shall have no liability for any deductions, inferences or generalizations drawn by the client or others from TÜV Product Service Inc issued reports.

This report is the confidential property of the client. As a mutual protection to our clients, the public and ourselves, extracts from the test report shall not be reproduced except in full without our written approval. This report shall not be used by the client to claim product endorsement by NVLAP or any agency of the US government.

TÜV Product Service Inc and its professional staff hold government and professional organization certifications and are members of AAMI, ACIL, AEA, ANSI, IEEE, NVLAP, and VCCI

DIRECTORY - EMISSIONS

	Page(s)
A) Documentation	
Test report	1 - 10
Directory	2
Test Regulations	3
Deviation from standard / Summary	10
Test-setups (Photos)	11 - 12
Test-setup (drawing)	<u>Appendix A</u>
B) Test data	
Conducted emissions	10/150 kHz - 30 MHz
Radiated emissions	10 kHz - 30 MHz
Radiated emissions	30 MHz - 1000 MHz
Interference power	30 MHz - 300 MHz
Equivalent Radiated emissions	1 GHz - 18 GHz
C) Appendix A	
Test Data Sheets and Test Setup Drawing(s)	<u>A2 - A8</u>
D) Appendix B	
Constructional Data Form	<u>B2</u>
Product Information Form(s)	<u>B3 - B5</u>
E) Appendix C	
Measurement Protocol	<u>C1 - C2</u>

EMISSIONS TEST REGULATIONS :

The emissions tests were performed according to following regulations:

<input type="checkbox"/> - EN 50081-1 / 1991	<input type="checkbox"/> - Group 1	<input type="checkbox"/> - Group 2
<input type="checkbox"/> - EN 55011 / 1991	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B
<input type="checkbox"/> - EN 55013 / 1990	<input type="checkbox"/> - Household appliances and similar	
<input type="checkbox"/> - EN 55014 / 1987	<input type="checkbox"/> - Portable tools	
<input type="checkbox"/> - EN 55014 / A2:1990	<input type="checkbox"/> - Semiconductor devices	
<input type="checkbox"/> - EN 55014 / 1993	<input type="checkbox"/> - Household appliances and similar	
<input type="checkbox"/> - EN 55015 / 1987	<input type="checkbox"/> - Portable tools	
<input type="checkbox"/> - EN 55015 / A1:1990	<input type="checkbox"/> - Semiconductor devices	
<input type="checkbox"/> - EN 55015 / 1993	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B
<input type="checkbox"/> - EN 55022 / 1987	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B
<input type="checkbox"/> - EN 55022 / 1994	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B
<input type="checkbox"/> - BS	<input type="checkbox"/> - Class B	
<input type="checkbox"/> - VCCI	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B
<input checked="" type="checkbox"/> - FCC Part 15 Subpart C Section 15.231	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B
<input checked="" type="checkbox"/> - FCC Part 15 Subpart B	<input type="checkbox"/> - Class A	<input checked="" type="checkbox"/> - Class B
<input type="checkbox"/> - CISPR 11 (1990)	<input type="checkbox"/> - Group 1	<input type="checkbox"/> - Group 2
<input type="checkbox"/> - CISPR 22 (1993)	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B
	<input type="checkbox"/> - Class A	<input type="checkbox"/> - Class B

Environmental conditions in the lab:

	<u>Actual</u>
Temperature	: 22 °C
Relative Humidity	: 19 %
Atmospheric pressure	: 97.8 kPa
Power supply system	: 9 VDC battery for transmitter, 12 VDC battery for receiver/beacon post

Sign Explanations:

- not applicable
 - applicable

Emissions Test Conditions: CONDUCTED EMISSIONS (Interference Voltage)

The CONDUCTED EMISSIONS (INTERFERENCE VOLTAGE) measurements were performed at the following test location:

- Test not applicable

- Wild River Lab Large Test Site (Open Area Test Site)
- Wild River Lab Small Test Site (Open Area Test Site)
- Oakwood Lab (Open Area Test Site)
- Wild River Lab Screen Room
- New Brighton Lab Shielded Room

Test equipment used :

Model Number	Manufacturer	Description	Serial Number	Cal Date
--------------	--------------	-------------	---------------	----------

Use of the calibrated equipment on this list ensures traceability to national and international standards.

Emissions Test Conditions: RADIATED EMISSIONS (Magnetic Field)

The RADIATED EMISSIONS (MAGNETIC FIELD) measurements were performed at the following test location:

- Wild River Lab Large Test Site (Open Area Test Site)
- Wild River Lab Small Test Site (Open Area Test Site)
- Oakwood Lab (Open Area Test Site)

at a test distance of :

- 3 meters
- 30 meters

- Test not applicable

Test equipment used :

Model Number	Manufacturer	Description	Serial Number	Cal Date
--------------	--------------	-------------	---------------	----------

Emissions Test Conditions: RADIATED EMISSIONS (Electric Field)

The **RADIATED EMISSIONS (ELECTRIC FIELD)** measurements, in the frequency range of 30 MHz-1000 MHz, were tested in a horizontal and vertical polarization at the following test location :

- Test not applicable

- Wild River Lab Large Test Site (Open Area Test Site)
- Wild River Lab Small Test Site (Open Area Test Site)
- Oakwood Lab (Open Area Test Site)

at a test distance of :

- 3 meters
- 10 meters
- 30 meters

Test equipment used :

Model Number	Manufacturer	Description	Serial Number	Cal Date
■ - 3146	Electro-Mechanics (EMCO)	Log Periodic Antenna	9103-3075	11-98
■ - 3108	Electro-Mechanics (EMCO)	Biconical Antenna	2429	6-98
■ - 8566B	Hewlett-Packard	Spectrum Analyzer	2221A01596	4-98
■ - 85662A	Hewlett-Packard	Analyzer Display	2152A03640	4-98
■ - 85650A	Hewlett-Packard	Quasi-Peak Adapter	2811A01127	4-98
■ - ZHL-1042J	Mini-Circuits	Preamplifier	H072294-11	4-98

Use of the calibrated equipment on this list ensures traceability to national and international standards.

Emissions Test Conditions: INTERFERENCE POWER

The **INTERFERENCE POWER** measurements were performed by using the absorbing clamp on the mains and interface cables in the frequency range 30 MHz - 300 MHz at the following test location :

- Test not applicable

- Wild River Lab Large Test Site (Open Area Test Site)
- Wild River Lab Small Test Site (Open Area Test Site)
- Oakwood Lab (Open Area Test Site)
- Wild River Lab Screen Room
- New Brighton Lab Shielded Room

Test equipment used :

Model Number	Manufacturer	Description	Serial Number	Cal Date

Emissions Test Conditions: RADIATED EMISSIONS (Electric Field)

The **EQUIVALENT RADIATED EMISSIONS** measurements in the frequency range 1 GHz - 4.2 GHz were performed in a horizontal and vertical polarization at the following test location :

- - Wild River Lab Large Test Site (Open Area Test Site)
- - Wild River Lab Small Test Site (Open Area Test Site)
- - Oakwood Lab (Open Area Test Site)
- - Wild River Lab Screen Room

at a test distance of:

- - 1 meters
- - 3 meters
- - 10 meters

- Test not applicable

Test equipment used :

Model Number	Manufacturer	Description	Serial Number	Cal Date
■ - 3115	Electro-Mechanics (EMCO)	Horn Antenna	9001-3275	9-98
■ - 8566B	Hewlett-Packard	Spectrum Analyzer	2221A01596	4-98
■ - 85662A	Hewlett-Packard	Analyzer Display	2152A03640	4-98
■ - 85650A	Hewlett-Packard	Quasi-Peak Adapter	2811A01127	4-98
■ - ZHL-1042J	Mini-Circuits	Preamplifier	H072294-11	4-98
■ - AFT-8434	Avantek	Preamplifier	9112 Z221	4-98

Use of the calibrated equipment on this list ensures traceability to national and international standards.

Equipment Under Test (EUT) Test Operation Mode - Emission tests :

The device under test was operated under the following conditions during emissions testing:

- Standby
- Test program (H - Pattern)
- Test program (color bar)
- Test program (customer specific)
- Practice operation
- Normal Operating Mode
- Transmitter on.

Configuration of the device under test:

- - See Constructional Data Form in Appendix B - Page B2
- - See Product Information Form in Appendix B - beginning on Page B3

The following peripheral devices and interface cables were connected during the measurement:

Emission Test Results:**Conducted emissions 10/150 kHz - 30 MHz**

The requirements are

 - MET - NOT MET

Minimum limit margin

_____ dB

at _____ MHz

Maximum limit exceeding

_____ dB

at _____ MHz

Remarks: _____

Radiated emissions (magnetic field) 10 kHz - 30 MHz

The requirements are

 - MET - NOT MET

Minimum limit margin

_____ dB

at _____ MHz

Maximum limit exceeding

_____ dB

at _____ MHz

Remarks: _____

Radiated emissions (electric field) 30 MHz - 1000 MHz

The requirements are

 - MET - NOT MET

Minimum limit margin for xmtr fundamental

7 dB

at 418.0 MHz

Minimum limit margin for xmtr spurious

0.2 dB

at 836.0 MHz

Minimum limit margin for receiver

0.6 dB

at 407.3 MHz

Remarks: The fundamental was measured to be 92.3 dBuV/m in peak mode, minus 20 dB (based on 10% duty cycle) to get average measurement, or 72.3 dBuV/m (4121 uV/m) compared to a limit of 80.3 dBuV/m (10333 uV/m). The second harmonic was measured to be 80.1 dBuV/m in peak mode, minus 20 dB (based on 10% duty cycle) to get average measurement, or 60.1 dBuV/m (1011 uV/m) compared to a limit of 60.3 dBuV/m (1035 uV/m).

Interference Power at the mains and interface cables 30 MHz - 300 MHz

The requirements are

 - MET - NOT MET

Minimum limit margin

_____ dB

at _____ MHz

Maximum limit exceeding

_____ dB

at _____ MHz

Remarks: _____

Equivalent Radiated emissions 1 GHz - 4.2 GHz

The requirements are

 - MET - NOT MET

Minimum limit margin for transmitter

0.7 dB

at 1672 MHz

Minimum limit margin for receiver

>10 dB

at _____ MHz

Remarks: Peak analyzer reading of 73.3 dBuV/m, minus 20 dB (based on 10% duty cycle) to get average measurement, or 53.3 dBuV/m (462 uV/m) compared to a limit of 54 dBuV/m (501 uV/m).

DEVIATIONS FROM STANDARD:

None.

GENERAL REMARKS:

The bandwidth of the fundamental must be less than 0.25% of the center frequency, or 1.045 MHz. Page A5 of A5 shows the bandwidth to be less than 50 kHz.

SUMMARY:

The requirements according to the technical regulations are

- met
- not met.

The device under test does

- fulfill the general approval requirements mentioned on page 3.
- not fulfill the general approval requirements mentioned on page 3.

Testing Start Date: 22 February 1999

Testing End Date: 22 February 1999

- TÜV PRODUCT SERVICE INC -

Joel T. Schneider
J. T. Schneider
NVLAP Signatory

J. C. Sausen
Tested By:
J. C. Sausen

FCC ID: N2N 600-023

Test-setup photo(s):

Conducted emission 10/150 kHz - 30 MHz

Not Applicable

Appendix A


Test Data Sheets

and

Test Setup Drawing(s)

TEST SETUP FOR EMISSIONS TESTING**WILD RIVER LAB**
Large Test Site**Notes:**

1. Items shown in dotted lines are located on the floor below the test area. It is 5 meters vertically from the ground floor to the test area.
2. 50 Hz, 60 Hz, and 400 Hz are power panels for alternating current.
3. The antenna may be positioned horizontally 3, 10 or 30 meters from the center of the turntable.
4. The circle is a 6.7 meter diameter turntable.
5. A ground plane is in the plane of this sheet.
6. The test sample is shown in the azimuthal position representing zero degrees.



T U V P R O D U C T S E R V I C E

RADIATED EMISSIONS

Large Test Site
3 Meter Antenna Distance
Equipment Under Test:
DANE INDUSTRIES
TRANSMITTER

Report W9121 Run 1
Date 02-22-99 Page 1
Engineer
Tech: JCS 
Requester

Notes: CONTINUOUS TRX MODE FOR TESTING. 20 DB RELAXATION WITH 10 % DUTY CYC

Frequency MHz	Level dBuV	Factor dB	Cable dB	Peak dBuV/m	Polar\ Height	Duty Cycle	Average dBuV/m	Limit 15.231(b)
418	74.2	16.4	1.8	92.4	H --	-20	72.4	80.3
418	66.95	16.4	1.8	85.2	V --	-20	65.2	80.3
836.01	50.85	21.8	2.6	75.3	V --	-20	55.3	60.3
836.01	55.65	21.8	2.6	80.1	H --	-20	60.1	60.3
1254.0	40.45	25.6	3.3	69.4	H --	-20	49.4	60.3
1254.0	32.1	25.6	3.3	61	V --	-20	41	60.3
1672.0	32.4	27.6	3.9	63.9	V --	-20	43.9	54
1672.0	41.8	27.6	3.9	73.3	H --	-20	53.3	54
2090.0	35.3	29.5	8	72.8	H --	-20	52.8	60.3
2090.0	24.25	29.5	8	61.8	V --	-20	41.8	60.3
2508.0	34.1	30.1	8.4	72.7	V --	-20	52.7	60.3
2508.0	40.8	30.1	8.4	79.4	H --	-20	59.4	60.3
2926.0	37.95	31	5.4	74.4	H --	-20	54.4	60.3
2926.0	26.95	31	5.4	63.4	V --	-20	43.4	60.3
3344.0	18	33	5.5	56.5	V --	-20	36.5	60.3
3344.0	25.6	33	5.5	64.1	H --	-20	44.1	60.3
3762.0	28.8	33.9	6.1	68.8	H --	-20	48.8	54
3762.0	20.5	33.9	6.1	60.5	V --	-20	40.5	54
3762.0	29.4	33.9	6.1	69.4	H --	-20	49.4	54
4180.0	19.55	33.7	6.3	59.6	H --	-20	39.6	54
4180.0	20.8	33.7	6.3	60.8	V --	-20	40.8	54

T U V P R O D U C T S E R V I C E

RADIATED EMISSIONS

Large Test Site
 3 Meter Antenna Distance
 Equipment Under Test:
 DANE INDUSTRIES
 TRANSMITTER
 Notes: CONTINUOUS TRX MODE FOR TESTING. 20 DB RELAXATION WITH 10 % DUTY CYC

Figure _____

Report W9121 Run 1
 Date 02-22-99 Page 2
 Engineer _____
 Tech: JCS *[Signature]*
 Requester _____

Measurement Summary

Frequency MHz	----- Final ----- dBuV/m	Azimuth uV/m	Polar\ deg	Delta Height	Delta 15.231(b)
418	72.4	4168.6	--	H --	-7.9
836.01	60.1	1011.5	--	H --	-0.2
1254.0	49.4	295.12	--	H --	-10.9
1672.0	53.3	462.38	--	H --	-0.7
2090.0	52.8	436.51	--	H --	-7.5
2508.0	59.4	933.25	--	H --	-0.9
2926.0	54.4	524.80	--	H --	-5.9
3344.0	44.1	160.32	--	H --	-16.2
3762.0	49.4	295.12	--	H --	-4.6
4180.0	40.8	109.64	--	V --	-13.2

File W9121 Run 1


File No. WC1G912101, Page A4 of A8

FCC ID: N2N 600-023

REPORT #W9121
RUN 2

TÜV PRODUCT SERVICE
RADIATED EMISSIONS AT 3 METERS
DANE INDUSTRIES RECEIVER BEACON POST

02-22-99



File No. WC1G912101, Page A5 of A8

T U V P R O D U C T S E R V I C E

RADIATED EMISSIONS

Large Test Site
 3 Meter Antenna Distance
 Equipment Under Test:
 DANE INDUSTRIES
 RECEIVER BEACON POST
 Notes:

Report W9121 Run 2
 Date 02-22-99 Page 1
 Engineer _____
 Tech: JCS JCS
 Requester _____

Frequency	Level	Factor	Cable	Final	Az	Polar\ Height	Delta	Delta
MHz	dBuV	dB	dB	dBuV/m	deg		FCC B	
407.26	17.26	17.1	1.8	36.1	--	V --	-9.9	
407.26	26.56	17.1	1.8	45.4	--	H --	-.6	
814.52	4.7	21.6	2.6	28.9	--	H --	-17.1	
814.52	2.48	21.6	2.6	26.7	--	V --	-19.3	
1629.0	5.84	27.4	3.9	37.1	--	H --	-16.9	
1629.0	2.66	27.4	3.9	33.9	--	V --	-20.1	

NO FURTHER EUT EMISSIONS DETECTED ABOVE NOISE FLOOR UP TO 4.07 GHZ.

NOISE FLOOR MEASUREMENTS:

2036.3	1.1	29.5	6.6	37.1	--	V --	-16.9
2443.5	1.2	30	10.1	41.3	--	V --	-12.7
2850.8	1.65	30.9	5.5	38	--	V --	-16
3258.0	1	32.5	5.4	39	--	V --	-15
3665.3	1	33.8	5.9	40.7	--	V --	-13.3
4072.6	1.3	33.8	6.3	41.4	--	V --	-12.6

END OF SCAN DATA.

T U V P R O D U C T S E R V I C E

RADIATED EMISSIONS

Large Test Site
 3 Meter Antenna Distance
 Equipment Under Test:
 DANE INDUSTRIES
 RECEIVER BEACON POST
 Notes:

Figure _____

Report W9121 Run 2
 Date 02-22-99 Page 2
 Engineer _____
 Tech: JCS *JCS*
 Requester _____

Measurement Summary

Frequency MHz	----- Final ----- dBuV/m	Azimuth uV/m	Polar\ deg	Height	Delta FCC B	Delta
407.26	45.4	186.20	--	H	--	-.6
814.52	28.9	27.861	--	H	--	-17.1
1629.0	37.1	71.614	--	H	--	-16.9
2036.3	37.1	71.614	--	V	--	-16.9
2443.5	41.3	116.14	--	V	--	-12.7
2850.8	38	79.432	--	V	--	-16
3258.0	39	89.125	--	V	--	-15
3665.3	40.7	108.39	--	V	--	-13.3
4072.6	41.4	117.48	--	V	--	-12.6

Minimum Passing Margin for FCC B is .6 dB at 407.26 MHz

File W9121 Run 2

File No. WC1G912101, Page A7 of A8

FCC ID: N2N 600-023

Appendix B

Constructional Data Form

and

Product Information Form(s)

FCC ID: N2N 600-023



Constructional Data Form

Not Applicable

File No. WC1G912101, Page B2 of B5

PRODUCT INFORMATION FORM

NOTE: It is required to complete both 1) a Product Information Form for each unit under test and 2) a Constructional Data Form for each system tested as outlined in the enclosed instructions.

*** Please show the exact spelling [including spacing, capitalization, etc] as you want shown on the After Test Documentation.**

***Company Name** Dane Industries Inc

***Company Address** 9855 13th Avenue N

Plymouth MN 55441

Customer Representatives

***Equipment Description** 418 MHz Transmitter

***Model Number** 100-030 ***Serial Number**

Type of Test

- Development
- Initial Design Verification
- Design Change (Please describe exact changes below)
- Production Sample (Audit Test)
- Final Product Verification

Changes Made

Oscillator Frequencies

Power Interface n/a	Power Supply
Frequency	Description
Voltage	Manufacturer
# of Phases	Model Number
Current	Switching Freq

Power Cable n/a

<input type="checkbox"/> Hardwired	<input type="checkbox"/> Flexible
<input type="checkbox"/> Shielded	<input type="checkbox"/> Unshielded
<input type="checkbox"/> Attached	<input type="checkbox"/> Removable

Power Line Filter n/a

Manufacturer	Model Number
--------------	--------------

PRODUCT INFORMATION FORM

NOTE: It is required to complete both 1) a Product Information Form for each unit under test and 2) a Constructional Data Form for each system tested as outlined in the enclosed instructions.

*** Please show the exact spelling [including spacing, capitalization, etc] as you want shown on the After Test Documentation.**

***Company Name** Dane Industries Inc

***Company Address**
9855 13th Avenue N
Plymouth MN 55441

Customer Representatives

***Equipment Description** 418 MHz Receiver/Beacon Post

***Model Number** 100-027, 100-031, 100-072 ***Serial Number**

Type of Test

- Development
- Initial Design Verification
- Design Change (Please describe exact changes below)
- Production Sample (Audit Test)
- Final Product Verification

Changes Made

Oscillator Frequencies

Power Interface n/a	Power Supply
Frequency	Description
Voltage	Manufacturer
# of Phases	Model Number
Current	Switching Freq

Power Cable n/a	Power Supply
------------------------	---------------------

<input type="checkbox"/> Hardwired	<input type="checkbox"/> Flexible
<input type="checkbox"/> Shielded	<input type="checkbox"/> Unshielded
<input type="checkbox"/> Attached	<input type="checkbox"/> Removable

Power Line Filter n/a	Power Supply
------------------------------	---------------------

Manufacturer	Model Number
--------------	--------------

Cabinet Shielding Provision


Software and/or Operating Modes

Interfacing Equipment or Simulators

I/O Cables

Function	Length (meters)	Shielded	Analog/Digital	Active During Test
"Low" when activated by xmtr (X4)	1 m	N	D	N
+12 V	1 m	N		Y
GND	1 m	N		Y

Block Diagram



Appendix C

MEASUREMENT PROTOCOL

GENERAL INFORMATION

Measurement Uncertainty

The test system for conducted emissions is defined as the LISN, tuned receiver or spectrum analyzer, and coaxial cable. The test system for radiated emissions is defined as the antenna, the pre-amplifier, the spectrum analyzer and the coaxial cable. These test systems have a measurement uncertainty of ± 4.5 dB. The equipment comprising the test systems are calibrated on an annual basis.

Justification

The Equipment Under Test (EUT) is configured in a typical user arrangement in accordance with the manufacturer's instructions. A cable is connected to each available port and either terminated with a peripheral into its characteristic impedance or left unterminated. When appropriate, the cables are manually manipulated with respect to each other to obtain maximum emissions from the unit.

CONDUCTED EMISSIONS

The final level, expressed in dB μ V, is arrived at by taking the reading directly from the EMI receiver. This level is compared directly to the FCC limit.

To convert between dB μ V and μ V, the following conversions apply:

$$\text{dB}\mu\text{V} = 20(\log \mu\text{V})$$

$$\mu\text{V} = \text{Inverse log}(\text{dB}\mu\text{V}/20)$$

RADIATED EMISSIONS

The final level, expressed in dB μ V/m, is arrived at by taking the reading from the spectrum analyzer (Level dB μ V) and adding the antenna correction factor and cable loss factor (Factor dB) to it. This result then has the FCC limit subtracted from it to provide the Delta which gives the tabular data as shown in the data sheets in Attachment B. The amplifier gain is automatically accounted for by using an analyzer offset.

Example:

Frequency (MHz)	Level (dB μ V)	+	Factor & Cable (dB)	=	Final (dB μ V/m)	-	FCC B (dB μ V/m)	=	Delta (dB)
32.21	13.9	+	16.3	=	30.2	-	40.0	=	-9.8

DETAILS OF TEST PROCEDURES**General Standard Information**

The test methods used comply with ANSI C63.4-1992 - "Methods of Measurement of Radio-Noise Emissions from Low-Voltage Electrical and Electronic Equipment in the Range of 9 kHz to 40 GHz."

Conducted Emissions

Conducted emissions on the 60 Hz power interface of the EUT are measured in the frequency range of 450 kHz to 30 MHz. The measurements are performed using a receiver, which has CISPR characteristic bandwidth and quasi-peak detection, and a Line Impedance Stabilization Network (LISN), with $50\ \Omega/50\ \mu\text{H}$ (CISPR 16) characteristics. Table top equipment is placed on a non-conducting table 80 centimeters above the floor and is positioned 40 centimeters from the vertical ground plane (wall) of the screen room. In some cases, a pre-scan using a spectrum analyzer is initially performed on the units comprising the system under test to locate the highest emissions. If the minimum passing margin appears to be less than 20 dB with a peak mode measurement, the emissions are re-measured using a tuned receiver or spectrum analyzer with quasi-peak and average detection and recorded on the data sheets.

Radiated Emissions

Radiated emissions from the EUT are measured in the frequency range of 30 to 1000 MHz using a spectrum analyzer and appropriate broadband linearly polarized antennas. Measurements between 30 MHz and 1000 MHz are made with 120 kHz/6 dB bandwidth and quasi-peak (or peak) detection and measurements above 1000 MHz are made with a 1 MHz/6 dB bandwidth and peak detection. Table top equipment is placed on a 1.0 X 1.5 meter non-conducting table 80 centimeters above the ground plane. Floor standing equipment is placed directly on the turntable/ground plane. Interface cables that are closer than 40 centimeters to the ground plane are bundled in the center in a serpentine fashion so they are at least 40 centimeters from the ground plane. Cables to simulators/testers (if used in this test) are routed through the center of the table and to a screen room located outside the test area. The antenna is positioned 3 meters horizontally from the EUT. To locate maximum emissions from the test sample the antenna is varied in height from 1 to 4 meters, measurement scans are made with both horizontal and vertical antenna polarizations and the EUT are rotated 360 degrees. Intentional radiators are rotated through three orthogonal axes to determine the attitude that maximizes the emissions.