



AS4000

Wireless Local Loop System

**Demand Assignment
Access Concentrator
Installation and Commissioning**

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | Preface |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | Preface |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

Notice

1. This manual is subject to revision.
2. All rights reserved.
3. Right of modification reserved.
4. This manual is supplied without liability for errors or omissions.
5. No part of this manual may be reproduced or used except as authorised by contract or other written permission.
6. This equipment is conditioned by the requirement that no modifications will be made to the equipment unless the changes or modifications are expressly approved by ACC Communications.
7. Prerequisite skills: Personnel installing, commissioning, and maintaining the Airspan products must have a basic knowledge of telephony and radio communications, and have experience in installing, commissioning and maintaining telecommunications products. ACC provides a range of comprehensive training courses specifically aimed at providing operators/users of AS4000 products with the prerequisite skills to install, commission and or maintain the product. The courses can be tailored to provide the level of training required by the operator/user.
8. Airspan™ and Sitespan™ are Registered Trademarks of Airspan Communications Corporation.

For additional information on Airspan Systems, please call your ACC Representative, or contact ACC at:

Cambridge House
Oxford Road
Uxbridge
Middlesex
UB8 1UN

Call (44) 1784 886700

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | Preface |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | Preface |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

Safety Instructions - Warnings and Cautions



SAFETY

1. Read and follow all warning notices and instructions marked on the product or included in this manual
2. Do not allow anything to rest on any power cord and do not locate the product where persons could step or walk on a power cord.
3. When installed in the final configuration, the product must comply with the applicable Safety Standards and regulatory requirements of the country in which it is installed. If necessary, consult with the appropriate regulatory agencies and inspection authorities to ensure compliance.
4. No hazardous RF radiation is emitted from the equipment. Measured at the surface of the CRU radome, when transmitting, the maximum total power radiated from the CRU is 0.01% of the UK National Radiological Protection Board basic restriction per kg. of body part.



WARNING - HAZARDOUS VOLTAGES

On AC installations, hazardous voltages exist. Use caution when verifying or working with AC power. Remove metal jewellery that could come into contact with AC power.

On DC sections, short circuiting the low voltage, low impedance circuits can cause severe arcing that may result in burns or eye damage. Remove rings, watches etc. to avoid shorting DC circuits.



Electro-Static Discharge ESD

Electro-Static Discharge. Many circuits contain devices that are susceptible to damage from high impedance voltage sources. To avoid such risks always follow anti-static procedures where marked.


| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | Preface |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |



NOTE

AS4000 products do not contain hazardous substances (as defined in UK ‘Control of Substances Hazardous to Health Regulations 1989’, and the ‘Dangerous Substances Regulations 1990’). At the end of any Airspan product’s life cycle, the customer should consult with Airspan to ensure that the product is disposed of in conformance with the relevant regulatory requirements



The  Symbol on an Airspan product signifies that it has been certified according to the EMC directive 89/336/EEC. The product fulfils the requirements according to the following standards:

- EN50082-1 Immunity.
- EN55022 Group 1 Class A for the Central Terminal Emissions.
- EN55022 Group 1 Class B for the Subscriber Terminal Emissions.



NOTE

The Subscriber Terminal equipment has been tested and found to comply with the limits for a Class B digital device, pursuant to part 15 of the FCC Rules.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | Preface |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

User Response Form

Mail: Airspan Communications Limited
Cambridge House
Oxford Road
Uxbridge
Middlesex
UB8 1UN

Fax: (44) 01895-467182

| Document Rating | Excellent | Good | Average | Below Average | Poor |
|-------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|
| Accuracy / Completeness | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Clarity / Organisation | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Figures | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Table of Contents/Index | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

The nature of this response is Addition ☐ Deletion ☐ Correction ☐

Please enter details of response below (include precise reference to Section, Page, Paragraph)

Please complete the following for acknowledgement/response:

| | | | |
|------------|-------|---------|-------|
| Name: | | Address | |
| Company | | | |
| Job Title | | | |
| Department | | | |
| Telephone | | | |

Thank you for your co-operation and assistance.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | Preface |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank



AS4000 Access Concentrator
Installation and Commissioning

605-0000-453

Issue 1.2dr Date 7/02/00

ICL 001

ISSUE CONTROL LIST

| Title | Issue | Date | Issue Details |
|--------------|--------------|-------------|----------------------|
| Title Page | 1.2 | August 2000 | |
| ICL-001 | 1.2 | August 2000 | |
| IXL-001 | 1.2 | August 2000 | |
| GSI-001 | 1.2 | August 2000 | |
| GSI-002 | 1.2 | August 2000 | |
| GSI-003 | 1.2 | August 2000 | |
| DLP-001 | 1.2 | August 2000 | |
| DLP-002 | 1.2 | August 2000 | |
| DLP-003 | 1.2 | August 2000 | |
| DLP-004 | 1.2 | August 2000 | |
| DLP-005 | 1.2 | August 2000 | |
| DLP-006 | 1.2 | August 2000 | |
| DLP-007 | 1.2 | August 2000 | |
| DLP-008 | 1.2 | August 2000 | |
| DLP-009 | 1.2 | August 2000 | |
| DLP-010 | 1.2 | August 2000 | |
| DLP-011 | 1.2 | August 2000 | |
| Appendix 1 | 1.2 | April 2000 | |
| Appendix 2 | 1.2 | April 2000 | |
| Appendix 3 | 1.2 | April 2000 | |
| Appendix 4 | 1.2 | April 2000 | |
| | | | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | ICL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| CHANGE TYPE/DATE | PURPOSE | PAGES AFFECTED |
|--------------------------------------|---------|----------------|
| Draft Issue #, Month Year | | |
| | | |



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

INDEX TASK LIST

PREFACE:

Safety Instructions Warnings and Cautions

User Response Form

ACCESS: ICL, IXL

Issue Control List ICL-001

Index Task List IXL-001

GENERAL SYSTEM INFORMATION: GSI

Introduction. GSI-001

- 1. Purpose of Document..... 1
- 2. Prerequisite skills..... 1

Overview. GSI-002

- 1. Installation Tasks 1
- 2. Safety 1
 - 2.1. Hazardous Voltages 1
 - 2.2. ESD 2

Technical Specifications. GSI-003

- 1. Access Concentrator 1

Preparatory Tasks..... DLP-001

- 1. Installation Tools and Equipment..... 1
 - 1.1. Required Tools..... 1
 - 1.2. Required Equipment 2
- 2. Site Readiness..... 2
 - 2.1. Power Availability 2
 - 2.2. Site Earth 3
 - 2.3. Flooring 3
 - 2.4. Cable Trays..... 3
 - 2.5. Delivery Inspection..... 3
 - 2.6. Unpacking Inspection..... 4

Rack Installation. DLP-002

- 1. Positioning and Securing Racks 1
 - 1.1. Installing Rack in a Suite..... 1
 - 1.2. Securing Rack Base 2

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| | |
|---|----------------|
| 1.3. Securing the rack using overhead Ironwork..... | 3 |
| 1.4. Securing a Rack to a Wall | 4 |
| Access Concentrator Rack Cabling. | DLP-003 |
| 1. DC Power..... | 1 |
| 2. Rack Earthing | 3 |
| 3. Alarm Unit (Type 55B) External Connections..... | 3 |
| 4. Access Concentrator Interface Panel..... | 4 |
| 5. 2Mbit/s Cabling (CT Link)..... | 6 |
| 6. 2Mbit/s Cabling (Switch Link)..... | 7 |
| Card Installation | DLP-004 |
| 1. Preliminary | 1 |
| 2. Card Insertion | 2 |
| System Configuration for testing | DLP-005 |
| 1. General..... | 1 |
| 2. Card Provision for New Installation | 1 |
| 2.1. PSU Voltage AC Shelves: (Test 2a) | 2 |
| 3. Commissioning rack | 2 |
| Turn -Up and DC measurements | DLP-006 |
| 1. Rack Turn-Up and Measuring Input Voltage(Test 1a) | 1 |
| 2. Switching on the rack. (Test 1b)..... | 1 |
| 3. PSU Voltage AC Shelves: (Test 2a)..... | 2 |
| Setting Up system Using Sitespan | DLP-007 |
| 1. Setting up Site Configuration on Sitespan | 1 |
| 2. Setting up CT Rack and Shelf configuration on Sitespan..... | 4 |
| 3. Assign Central terminal Card Slots | 6 |
| 3.1. DTU Card | 6 |
| 4. Setting up AC Rack and Shelf configuration on Sitespan | 8 |
| 5. Assign Access Concentrator Card Slots..... | 11 |
| 6. Configure AC Cards | 12 |
| 6.1. CTU..... | 12 |
| 6.2. CAS..... | 12 |
| 6.3. DATA..... | 13 |
| 6.4. V5.1..... | 14 |
| Shelf Controller Software Downloads | DLP-008 |
| Configuring the Acces Concentrator | DLP-009 |
| 1. Configure the Access Concentrator..... | 1 |
| 2. Alarm and Status Indications (Test 3) | 3 |
| 3. Self Test (Test 4) | 4 |
| Commissioning Test Results | DLP-010 |
| 1. Commissioning Test Results | 1 |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| | |
|---|-------------------|
| 1.1. Test Equipment Calibration..... | 1 |
| Site Acceptance | DLP-011 |
| 1. Site Inspection | 1 |
| 2. Site Acceptance Forms..... | 1 |
| BNC Terminations to Coax | Appendix 1 |
| Procedure in case of card boot-up failure..... | Appendix 2 |
| Procedure in case of card boot-up failure | 1 |
| LAT Settings | Appendix 3 |
| 1. LAT connected to SC..... | 1 |
| Sitespan Database Translation V2.5 to V3.4 | Appendix 4 |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

List of Figures

| Figures | Page |
|---|-------------|
| DLP-001 | |
| Figure 1. Packaging for AC Site | 3 |
| DLP-002 | |
| Figure 2. Access Concentrator Rack. | 1 |
| Figure 3. Securing Rack Base | 2 |
| Figure 4. Typical Overhead Ironwork Support | 3 |
| Figure 5. Securing Rack To Wall | 4 |
| DLP-003 | |
| Figure 6. DC Termination on Combiner Shelf. | 2 |
| Figure 7. Rack Earthing | 3 |
| Figure 8. AS4000 Alarm Unit Connections | 4 |
| Figure 9. Access Concentrator Interface Panel (1010 Board) | 5 |
| Figure 10. Access Concentrator Interface Panel (1026 Board) | 5 |
| DLP-004 | |
| Figure 11. Access Concentrator Rack Fuse and Alarm Panel | 1 |
| Figure 12. Typical Card set for V5.1 | 2 |
| Figure 13. Typical card set for V5.2 | 3 |
| DLP-005 | |
| Figure 14. AC Shelf PSU | 2 |
| DLP-006 | |
| Figure 15. Test Voltage (Expansion Rack) | 1 |
| Figure 16. Access Concentrator Shelf PSU | 2 |
| DLP-008 | |
| Figure 17. Access Concentrator Shelf Backplane | 1 |
| DLP-009 | |
| Figure 18. Access Concentrator Shelf Backplane | 1 |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

List of Tables

| Table | Page |
|--|-------------|
| GSI-003 | |
| Table 1. Physical Characteristics. | 1 |
| Table 2. Environmental Specifications. | 1 |
| Table 3. Power Requirements. | 2 |
| DLP-001 | |
| Table 4. Required Test Equipment. | 2 |
| DLP-003 | |
| Table 5. DC Power Cables. | 1 |
| DLP-005 | |
| Table 6. . PSU Voltage Test | 2 |
| DLP-006 | |
| Table 7. Access Concentrator Shelf PSU Voltages. | 2 |
| DLP-009 | |
| Table 8. Access Concentrator Shelf Card LED Indications. | 4 |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

Abbreviations

| | |
|-------|--|
| AC | Alternating Current |
| AGC | Automatic Gain Control |
| AU | Analogue Unit |
| A/D | Analogue/Digital |
| CPE | Customer Premises Equipment |
| CRU | Customer Radio Unit |
| CT | Central Terminal |
| CTU | Concentrated Tributary Unit (Access Terminal Shelves) |
| CU | Compression Unit |
| DA | Demand Assignment |
| DC | Direct Current |
| DMM | Digital Multi Meter |
| DRS | Digital Radio System |
| DTU | Demand Assignment Tributary Unit |
| FA | Fixed Assignment |
| ISDN | Integrated Services Digital Network |
| ITU-T | International Telecommunications Union -Telecommunications |
| LD | Loop Disconnect |
| LED | Light Emitting Diode |
| MF | Multi-Frequency |
| MSTP | Modem Shelf Termination Panel |
| MU | Modem Unit |
| NTU | Network Termination Unit |
| PC | Power Control |
| PSU | Power Supply Unit |
| RF | Radio Frequency |
| SC | Shelf Controller |
| SPU | Signalling Processing Unit |
| ST | Subscriber Terminal |
| Rx | Receive |
| Tx | Transmit |
| TU8 | Tributary Unit Eight E1 ports |
| VDU | Video Display Unit |
| VF | Voice Frequency |
| XTU | Exchange Tributary Unit (E1 protocol: CAS, V5.1, V5.2) |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

Related Documentation

| | |
|--------------|--|
| 605-0000-450 | System Overview |
| 605-0000-451 | System Operations and Maintenance Manual |
| 605-0000-452 | Central Terminal - Installation & Commissioning |
| 605-0000-433 | Central Terminal - Antenna/Feeder Installation & Commissioning |
| 605-0000-454 | Subscriber Terminal - Installation & Commissioning |
| 605-0000-437 | D128 Terminal Converter |
| 605-0000-435 | Material Return and Repair |
| 605-0000-427 | Sitespan |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | IXL 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | GSI 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

INTRODUCTION

1. Purpose of Document

This document describes the installation and commissioning of the ACC AS4000 Access Concentrator (AC) Rack and associated shelves to Release 5.0 specifications.

2. Prerequisite skills

Personnel installing and commissioning the AS4000 products must have a basic knowledge of telephony and radio communications, and have experience in installing telecommunications products. ACC provides a range of comprehensive training courses specifically aimed at providing operators/users of AS4000 products with the prerequisite skills to install, commission and or maintain the product. The courses can be tailored to provide the level of training required by the operator/user.

This manual is intended for use by persons familiar with the AS4000 product having attended the ACC Access Concentrator Installation and Commissioning training course prior to performing the procedures in this practice.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | GSI 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank



OVERVIEW

1. Installation Tasks

The installation procedures are arranged as a series of tasks and are generalised to cover the majority of applications and configurations. If your particular system application is not covered, call the ACC Help Desk, for assistance at the following number: TELEPHONE: +44 (0) 1527 402800

It is recommended that the tasks be completed in the sequence listed below:

- Task 1 — Verify Site facilities
- Task 2 — Unpack and Inspect Equipment
- Task 3 — AC Rack Installation
- Task 4 — System Interface Cabling
- Task 5 — Module/Card insertion
- Task 6 — System Test
- Task 7 — Test Results
- Task 8 — Connection to management system.
- Task 9 — Work Area Inspection and Cleaning
- Task 10 — Acceptance Procedure

2. Safety



Personnel installing the ACC AS4000 System should follow ACC safety procedures W090 0001 001 Issue 01 April 96

2.1. Hazardous Voltages



There are hazardous voltages present in the shelves of this equipment. Do not touch components or track on the cards while they are in operation.

On AC installations, hazardous voltages exist. Use caution when verifying or working with AC power. Remove metal jewellery that could come into contact with AC power.

On DC sections, short circuiting the low-voltage, low-impedance circuits can cause severe arcing that may result in burns or eye damage. Remove rings, watches, etc. to avoid shorting DC circuits. Do not install power modules in the shelf until the shelf and rack are properly mounted and secured.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | GSI 002 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

2.2. ESD



Electro-Static Discharge. Many circuits contain devices that are susceptible to damage from high impedance voltage sources. To avoid such risks always follow anti-static procedures.



TECHNICAL SPECIFICATIONS

1. Access Concentrator

The following tables provide technical specifications for the AS4000 Access Concentrator.

| Physical Characteristics | |
|---|--------|
| AC Rack Dimensions, (without brackets): | |
| Width | 600mm |
| Height | 2175mm |
| Depth | 300mm |
| Shipping Weight: | |
| Rack Frame | 60 kg |
| AC Shelf | |
| Card Set | |
| | |

Table 1. Physical Characteristics.

| Environmental | | |
|-----------------------------------|----------------|---------|
| | Minimum | Maximum |
| Operating Temperature | -5° C | +45° C |
| Relative Humidity, non-condensing | 0% | 95% |
| Storage Temperature | -40° C | 85° C |
| Storage Humidity, non-condensing | Less than 100% | |
| Air Pressure | 70 kPa | 106 kPa |

Table 2. Environmental Specifications.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | GSI 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| POWER REQUIREMENTS | |
|---|---|
| DC Input Voltage Operating Range. (N.B. This supply to be a guaranteed SELV from an EN60950 approved source.) | Maximum Range, -21.8V DC to -60.aV DC @ 540W |
| DC Input Current (Fully populated AC Rack) | 25 Amps max. @ -21V DC 11.5 Amps max. @ -48V DC 9 Amps max. @ -60V DC |
| Recommended Power Distribution Fusing (With a readily accessible disconnect device which will isolate all poles.) | -21. 8V DC to -60V DC 30Amps High Inrush |
| Power Distribution CT Fusing | -21.8V DC to -60V DC 30Amps each feed |

Table 3. Power Requirements.



Warning. The maximum DC input should not exceed 60 Volts. Voltages in excess of this are considered hazardous.



PREPARATORY TASKS

1. Installation Tools and Equipment

The following lists of tools and equipment are required to successfully install and test the AS4000 Access Concentrator Racks.

1.1. Required Tools

- Combination Spanners: 8 mm, 13 mm, 17 mm, & 19 mm.
- Spirit Level: 18 inch.
- Pozidrive: No 1 x 75 mm.
- No 2 x 100 mm
- No 3 x 150 mm.
- Screwdriver, flat blade: 3 mm x 100 mm.
- Screwdriver, flat blade: 5.5 mm x 100 mm.
- Screwdriver, flat blade: 8 mm x 150 mm.
- Hammer, Ball Pein: 1lb.
- Drill Bits, Masonry: 11 mm, 12 mm, 13 mm.
- Ratchet Crimp Tool for red, blue and yellow insulated crimps.
- Crimp Tool type 6A with VQ dies for co-ax connectors.
- Cordless Drill/Driver.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

1.2. Required Equipment

| Item | Description | Recommended Model | Quantity |
|------|--------------------|---------------------|----------|
| 1 | Digital Multimeter | Fluke 77 or similar | 1 |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| | | | |

Table 4. Required Test Equipment.

2. Site Readiness

Verify that the site is ready for the installation of the AC Rack.

This preparation will have been covered by a site survey conducted by ACC or by a survey form completed by the customer. The survey will include a site plan of the facility identifying the floor layout, power outlets, distribution boxes, and cabling runways. A sketch showing the rack support arrangements showing the exact positions of the mounting points on the rack with dimensions, and typical overhead ironwork provision should be included.

Inspect the site, and particularly the equipment room, before unloading or unpacking the equipment to ensure the following:

- Adequate grounding is provided.
- Access to the equipment room will be adequate for normal handling and movement.
- Adequate lighting is available for carrying out the installation.

Any non compliance with acceptable standards should be brought to the customers attention and resolved before proceeding with the installation.

2.1. Power Availability

From the site survey, confirm the location of the two fuse positions for the negative battery supply and the return point. Also locate the fuse position for the alarm unit 55B power supply.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

2.2. Site Earth

Confirm the position of the grounding point using the site survey.

2.3. Flooring

Ensure that flooring is substantial enough to support the rack and can provide a secure fixing.

2.4. Cable Trays

Verify that cable trays are installed to provide routing to the proper destinations and are of adequate strength

2.5. Delivery Inspection

Upon taking delivery of the equipment consignment, check that the consignment agrees in all particulars with the consignment delivery documentation (number of boxes, descriptions, and the contents of boxes, etc.). Any discrepancy or damage must be reported immediately to ACC for further instructions. In case of severe damage, do not accept the consignment from the carrier. See Material Return and Repair document 605-0000-427 for further details. The equipment is normally shipped as shown in. Figure 1.




Figure 1. Packaging for AC Site

If subsequent to the initial shipment incremental upgrades are made to the system the equipment will be delivered in packaging of size and type suitable for that shipment.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 001 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

2.6. Unpacking Inspection

The contents of each box must be checked against the relevant part lists provided with the box, for the correct part numbers and quantities, and for damage. Any shortage or damaged items must be reported immediately to ACC for further instructions at the address given in section 0 of this manual or:

TELEPHONE: +44 (0) 1527 402800

FAX: +44 (0) 1527 550956

E-Mail: support@airspan.com

Dispose of all unnecessary packaging in a safe manner according to the customer's requirements.

Note: It is recommended that one package carton of each type be retained should it be required to return any faulty or damaged items for repair.



RACK INSTALLATION

1. Positioning and Securing Racks

1.1. Installing Rack in a Suite

From the site survey, confirm the position of the AC Racks. If the racks are to be positioned in a suite, metalwork will be required to secure it to the overhead structure. Either a proprietary system or fabricated steelwork will be required - see site survey.

Manoeuvre the racks into position.





Figure 2. Access Concentrator Rack.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 002 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

1.2. Securing Rack Base

Using the base of the rack as a template, mark the floor locating positions through the cut-outs in the Rack Frame. Using a 13mm diameter drill bit, drill four holes to a depth of approximately 25mm. Position the rack over the four holes and screw the four (supplied) M12 screws through washers to secure the rack base.



Rack Base

Figure 3. Securing Rack Base

Warning: These screws are provided as locating pins only and must be used in conjunction with the overhead steelwork and not as an alternative method for securing the rack.

Temporarily secure the rack to adjacent racks or steelwork until the overhead support is in place.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 002 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

1.3. Securing the rack using overhead Ironwork

Assemble the overhead steelwork as required and secure the rack to the overhead structure using suitable fixings in compliance with local requirements. Remove all burrs and sharp edges.




Figure 4. Typical Overhead Ironwork Support

Note: In installations where threaded droprods in excess of 500mm are employed it may be necessary to provide additional support bars to ensure rigidity of the support structure.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 002 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

1.4. Securing a Rack to a Wall

If the rack is to be positioned against a wall, attach the two right-angled wall brackets (these brackets are part on the packaging) to the top of the rack and finger tighten with the provided M12 screws.

Manoeuvre the racks into position against the wall. Join the racks together with 12mm nuts and bolts placed through the holes at the top and bottom of the side panels and mark the wall through the holes in the top brackets.




Figure 5. Securing Rack To Wall

Using an 11mm. drill bit, drill holes in the wall to a depth of 75mm and fit masonry plugs. Fix the hex head screws through the brackets and finger tighten. Check that the rack is in the correct position and tighten all fixings.

Attention should be paid to the fabric of the wall. Where possible, drill directly into the brick and not into mortar. With panelled or partitioned walls, instruction should be taken locally as to how the rack is to be secured. See site survey.

Follow the procedure for the rack base as described in paragraph 1.2.



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

ACCESS CONCENTRATOR RACK CABLING

1. DC Power

The cables for the negative DC battery feeds, the 0V returns and the Rack Ground are detailed in Table 2. Should local requirements specify otherwise, it is acceptable for cables of other colours to be used, however, under no circumstances should the cable sizes be less than that specified in Table 2. The length of the cable supplied will be detailed in the site survey. Separate DC sources are desirable for maximum protection.

| Function | Colour | Min. Cable Size |
|--------------------------|--------------|----------------------------|
| Negative Battery Feed | Blue | 10 AWG; 6.0mm ² |
| Zero Volt Battery Return | Black | 10 AWG; 6.0mm ² |
| Rack Ground | Green/Yellow | 8AWG; 10.amm ² |

Table 5. DC Power Cables.



Warning.

The maximum DC input should not exceed 60 Volts. Voltages in excess of this are considered hazardous.

From the site survey confirm the location of the isolator for the negative battery feed points; then ensure that the supply is isolated. If the location is remote from the AC, take appropriate action to ensure that the supply is not inadvertently reconnected. This may include locking OFF an isolator, by taking its unique handle with you or ensuring that replacement fuses are not easily installed. Provide a label at the AC to indicate the location of the isolator or fuse positions mentioned above.


Run and tie in the two negative battery feeds and the two zero volt returns to the AC rack installed. These should be rated at 30A. Power cables must be run and tied separate from signal cables.

Note: Do not insert fuses until instructed to do so in the commissioning stage of installation.

Run the DC cables through the top right hand side of the rack, into the fuse and alarm panel.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

2. Rack Earthing

Using the site survey, locate the building central [safety] grounding point. Run an earth cable rated at 30A to each rack and connect it to the centre earth stud located at the top or bottom (not both) of the rack. See Figure 7. These points are labelled with the IEC Earth symbol. .




Figure 7. Rack Earthing



Warning: Other external safety earth connections must not be made to the rack. The two studs located towards the sides at the top of the rack are used for earth bonding the side and rear panels to the rack and must be left untouched to maintain the systems safety earthing integrity.

Terminate the battery feed and return cables at the isolator/fuse positions, and ensure that the AC rack is isolated until the commencement of commissioning tests.

3. Alarm Unit (Type 55B) External Connections

Run alarm cables from the station alarm scheme to the AU55B in the Fuse and Alarm Panel in the AC Rack. Terminate on the 25 way D-Type connector as shown in Figure 8 and to the station alarm scheme. Connect the -48V/24V alarm supply to the alarm supply fuse box using 1.0mm cable and terminate on the D-type connector.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

If a visual indication at the rack is all that is required, connect the alarm unit from the D-type connector on the AU55B to P9 in the Fuse and Alarm Panel.




Figure 8. AS4000 Alarm Unit Connections

The 10 way alarm ribbon from the AU55B should be connected to P7 on the alarm panel.

4. Access Concentrator Interface Panel

All cabling to the access concentrator connects to the interface panel. Slots 4,5 and 6 can be used for 75Ω and 120Ω connections. Slots 7-14 are used for 120Ω connections. Each slot will support up to 8 E1 connections.




Figure 9. Access Concentrator Interface Panel (1010 Board)




Figure 10. Access Concentrator Interface Panel (1026 Board)

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |




Figure 11. 120ohm connections to AC shelf

5. 120 Cabling Specification

The cable with the following characteristics to be used for interconnection between the AC shelf and switch/channel bank: Double screened, 120Ohm, 8 twisted pairs. The overall screen should be screened with a foil AND a 90% coverage tinned copper braid.

6. 2Mbit/s Cabling (CT Link)

From the site survey, confirm the location of the Digital Distribution Frame (DDF) if a DDF is to be used or the CT link if the 2Mbit/s feeds are fed direct to the equipment. The length of 2Mbit/s feeds should not exceed 250 metres.

Note: This must be a SELV port of an EN 60950 approved product.

Run the 2Mbit/s cables from the AC shelf to the allocated positions on the DDF. (Two cables per shelf in normal working, four cables per shelf in protected mode).

In partial equipped installations it may be appropriate to run enough cables to cater for a complete rack of equipment. This reduces the need to disturb original installation when adding additional equipment.

Feed the 2Mbit/s cables through the top hole on the most convenient side of the rack, and down the front of the rack.

Identify and label each cable at both ends as well as the DDF/Backhaul positions.

Terminate all cables with BNC co-axial connectors.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

7. 2Mbit/s Cabling (Switch Link)

From the site survey, confirm the location of the Digital Distribution Frame (DDF) if a DDF is to be used or the Switch if the 2Mbit/s feeds are fed direct to the equipment. The length of 2Mbit/s feeds should not exceed 250 metres.

Note: This must be a SELV port of an EN 60950 approved product.

Run the 2Mbit/s cables from the AC shelf to the allocated positions on the DDF. In partial equipped installations it may be appropriate to run enough cables to cater for a complete rack of equipment. This reduces the need to disturb original installation when adding additional equipment.

Feed the 2Mbit/s cables through the top hole on the most convenient side of the rack, and down the front of the rack.

Identify and label each cable at both ends as well as the DDF/Backhaul positions.

Terminate all cables with either BNC co-axial connectors (75Ω) or 25 pin D-type connectors (120Ω) according to the tables below.

| Pair | Designation | | Pin | |
|----------------|-------------|-----|-----|--|
| 1 | A5 | In | 1 | |
| | B5 | In | 2 | |
| | Screen | | 14 | |
| 2 | A6 | In | 4 | |
| | B6 | In | 5 | |
| | Screen | | 17 | |
| 3 | A7 | In | 7 | |
| | B7 | In | 8 | |
| | Screen | | 20 | |
| 4 | A8 | In | 10 | |
| | B8 | In | 11 | |
| | Screen | | 23 | |
| 5 | A5 | Out | 15 | |
| | B5 | Out | 16 | |
| | Screen | | 3 | |
| 6 | A6 | Out | 18 | |
| | B6 | Out | 19 | |
| | Screen | | 6 | |
| 7 | A7 | Out | 21 | |
| | B7 | Out | 22 | |
| | Screen | | 9 | |
| 8 | A8 | Out | 24 | |
| | B8 | Out | 25 | |
| | Screen | | 12 | |
| Overall Screen | | | 13 | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| Pair | Designation | | Pin | |
|----------------|-------------|----|-----|--|
| 1 | A1 | In | 1 | |
| | B1 | In | 2 | |
| | Screen | | 14 | |
| 2 | A2 | In | 4 | |
| | B2 | In | 5 | |
| | Screen | | 17 | |
| 3 | A3 | In | 7 | |
| | B3 | In | 8 | |
| | Screen | | 20 | |
| 4 | A4 | In | 10 | |
| | B4 | In | 11 | |
| | Screen | | 23 | |
| 5 | A5 | In | 15 | |
| | B5 | In | 16 | |
| | Screen | | 3 | |
| 6 | A6 | In | 18 | |
| | B6 | In | 19 | |
| | Screen | | 6 | |
| 7 | A7 | In | 21 | |
| | B7 | In | 22 | |
| | Screen | | 9 | |
| 8 | A8 | In | 24 | |
| | B8 | In | 25 | |
| | Screen | | 12 | |
| Overall Screen | | | 13 | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| Pair | Designation | | Pin | |
|----------------|-------------|-----|-----|--|
| 1 | A1 | Out | 1 | |
| | B1 | Out | 2 | |
| | Screen | | 14 | |
| 2 | A2 | Out | 4 | |
| | B2 | Out | 5 | |
| | Screen | | 17 | |
| 3 | A3 | Out | 7 | |
| | B3 | Out | 8 | |
| | Screen | | 20 | |
| 4 | A4 | Out | 10 | |
| | B4 | Out | 11 | |
| | Screen | | 23 | |
| 5 | A5 | Out | 15 | |
| | B5 | Out | 16 | |
| | Screen | | 3 | |
| 6 | A6 | Out | 18 | |
| | B6 | Out | 19 | |
| | Screen | | 6 | |
| 7 | A7 | Out | 21 | |
| | B7 | Out | 22 | |
| | Screen | | 9 | |
| 8 | A8 | Out | 24 | |
| | B8 | Out | 25 | |
| | Screen | | 12 | |
| Overall Screen | | | 13 | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 003 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank



CARD INSTALLATION

The AC rack is shipped with shelves fitted to customer requirements and internal cabling complete.



Warning: Before handling any cards or modules, observe full anti-static precautions

1. Preliminary

In a new installation Ensure that the AC Circuit on the Fuse and Alarm panel are switched are set to the OFF position (down) See Figure 12.



Warning: Isolation of power from the rack is only achieved by ensuring that both circuit breakers are in the off position.




Figure 12. Access Concentrator Rack Fuse and Alarm Panel

Ensure that the end of suite fuses are adequately rated and insert these into the respective fuse holder positions.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 004 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

2. Card Insertion

Insert the cards into the shelves, recording the serial numbers and revision status in the test form. See DLP007. The actual cards provided will depend upon the customer configuration.

- The load Sharing PSUs go in slots 1&2.
- The Shelf Controller goes in slot 3.
- All other slot positions are configurable via Sitespan.
- 3 CTUs are supported. Each CTU supports 4 CT modem shelves. Each CTU may be cabled for four 120 Ω E1s or four 75 Ω E1s.
- 8 XTUs are supported. Each XTU may be cabled for eight 120 Ω E1s.
- CU cards may go in any unused slot. (slots 15& 16 are preferred as they have no E1 connections).
- Slot 17 is available for card redundancy using a spare TU8 card, any other slot E1s may be routed to this slot by relay operation.

Figure 13 and Figure 14 below show typical card installation for V5.1 and V5.2 applications.




Figure 13. Typical Card set for V5.1




Figure 14. Typical card set for V5.2

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 004 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 005 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

SYSTEM TESTING

This section sets up the parameters for the system and the connection to Sitespan.

Refer to the Sitespan, document no. 605-0000-428 for the detailed configuration and set up procedures of the AS4000 System.

1. General

The following procedures need to be carried out in order to verify the functionality and operation of all cards fitted into the Access Concentrator prior to placing the AS4000 system into service.

If during testing, a fault occurs preventing the continuation of the test, the faulty module or card should be replaced and the test repeated for the card and all tests that are affected by the performance of that card.

All results must be entered on the Commissioning Test Result Sheet (DLP-014). Test forms should be photocopied as needed, ensure that sufficient copies of all sheets are available prior to the commencement of commissioning tests.

2. Card Provision for New Installation

Switch the Access Concentrator Rack **ON** by placing both breakers up and wait for the system to complete the power-up self test sequence successfully. The two breakers duplicate power to each shelf and the shelves will still function if one power supply fails though the LED indicators on the power supplies will not be on.

Using the DMM check that the DC voltage supply across the input terminals (TB1(-); TB2+; for Supply 1 and TB4(-); TB5(+) for supply 2). Ensure that the voltage measured complies with the site nominal voltage and is within the limits specified on the test results sheet.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 005 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

2.1. PSU Voltage AC Shelves: (Test 2a)

Using the DMM, measure and record the DC voltage at the front panel test points on each of the PSU's on the AC Shelf.




Figure 15. AC Shelf PSU

Ensure that the voltages measured are within the limit shown in Table 6. Record the results in test form.


| Voltage | Upper Limit | Lower Limit |
|---------|-------------|-------------|
| 5V DC | 5.25V | 4.75V |
| 3.3V DC | 3.0V | 3.3V |
| 2.1V DC | 2.1V | 2V |

Table 6. . PSU Voltage Test

3. Commissioning rack

The chart below shows the commissioning and testing process. The reference in brackets is the corresponding paragraph in the text. Tests are shown with a rounded corner box and procedures are shown in a square box. In addition each test has a number indicating the order of testing and reference for the test record sheets.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 005 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 005 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 006 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

TURN-UP AND DC MEASUREMENTS

| STEP | PROCEDURE |
|------|-----------|
|------|-----------|

1. Rack Turn-Up and Measuring Input Voltage(Test 1a)

This section describes the procedure for measuring and connecting DC to the rack, checking that the cards have the correct alarm indications on power-up and measuring the PSU output voltages.

Unscrew retaining screws on the face of the Fuse and Alarm Panel. Hinge forward the panel and using the DMM measure and record the Exchange DC voltage supply across the input terminals (TB1(-); TB2+; for Supply 1 and TB4(-); TB5(+) for supply 2). Ensure that the voltage measured complies with the site nominal voltage and is within the limits specified on the test results sheet.




Figure 16. Test Voltage (Expansion Rack)

Record the measured voltage on the test results sheet.

2. Switching on the rack. (Test 1b)

Switch the AC Shelves **ON** by placing both breakers up for each shelf and wait for the system to complete the power-up self test sequence successfully. The two breakers duplicate power to each shelf and the shelves will still function if one power supply fails though the LED indicators on the power supplies will not be on.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 006 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

Using the DMM check that the DC voltage supply across the input terminals (TB1(-); TB2+; for Supply 1 and TB4(-); TB5(+) for supply 2). Ensure that the voltage measured complies with the site nominal voltage and is within the limits specified on the test results sheet.

3. PSU Voltage AC Shelves: (Test 2a)

Using the DMM, measure and record the DC voltage at the front panel test points on each of the PSUs on the Access Concentrator Shelf.




Figure 17. Access Concentrator Shelf PSU

Ensure that the voltages measured are within the limit shown in Table 7. Record the results in test form.

| Voltage | Upper Limit | Lower Limit |
|---------|-------------|-------------|
| 5V DC | 5.25V | 4.75V |
| 3.3V DC | 3.0V | 3.3V |
| 2.1V DC | 2.1V | 2V |

Table 7. Access Concentrator Shelf PSU Voltages.

STOP. THIS PROCEDURE HAS BEEN COMPLETED.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

SETTING UP SYSTEM USING SITESPAN

Within Sitespan, both the racks and the shelves must be 'built' before connecting to the Racks. Do not connect Sitespan to the rack at this stage. This should be done prior to the commissioning of either the AC or CT racks.


The following steps must be followed:

| STEP | PROCEDURE |
|------|-----------|
|------|-----------|

1. Setting up Site Configuration on Sitespan

Before the system can be configured, Sitespan Version 3.4 Build 4 or later must be installed on the dedicated PC. Before installing, ensure that the PC is running Windows NT service pack 3 or later is set to run RAS and has a spare comms port or Digiport available. **Note** If the Sitespan managing an existing network is to be updated from a previous version then the current database must be updated prior to running the V3.4 version. See Appendix 4 for details of running the transfer program. For details on installing Sitespan software see the Sitespan User Guide 605-0000-426

1. Sitespan can then be started as follows:
2. Start the Server by selecting 'server' from the 'start menu' (In the 'Sitespan V34' folder, under programs)




3. Start the Client by selecting 'client' from the 'start menu' (In the 'Sitespan V34' folder, under programs)
4. From the client view, open 'template.ssd' from the file menu
5. Highlight the 'object list, server' and 'create server' from the 'edit menu'


| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |



6. If using the fixed network, select the name of the PC that Sitespan is running on.




7. Connect the server from the 'edit menu'




8. To create the AC Site select the server from the object list and select Create Site from the 'edit menu'

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |



9. From the Object List, Site click right mouse button and select Site Properties



10. Enter Site Details


The image shows a dialog box titled 'Edit Site Properties'. It contains a 'Name' field with the text 'Access Concentrator Site', an 'Address' field with placeholder text 'xx', 'xxxxxx', and 'xxxxxx', and two numeric input fields for 'Longitude (degrees)' and 'Latitude (degrees)', both containing the value '0'. On the right side of the dialog are three buttons: 'OK', 'Cancel', and 'Help'.

11. Repeat Steps 8-10 for each of the CT sites.


| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

2. Setting up CT Rack and Shelf configuration on Sitespan


1. Highlight the site, click right mouse button and select 'Create Child Element'



2. Select 'Airspan DA CT rack'




3. Highlight the rack in Object List, and create 'Airspan DA CT modem shelf' from the 'edit menu'




| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


4. Select '*1 (Top)*' (to set up modem shelf 1)



5. Highlight shelf, and edit 'parent properties'



6. Select '*Airspan DA CT Modem Shelf*'



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


7. Select Com port and unique TEI identifier to communicate with the AC shelf.

8. Set the reference clock source to the DTU connected to the CTU in the AC rack from where the clock source is derived. This is usually Slot 5 E1-1 for 75ohm Backhaul or Slot 5 E1-5 for 120ohm Backhaul. Enter the RF card type, Frequency and PN Code and set the TX gain to 3300 and the RX gain to 2200 (these are nominal values and are fine tuned when the RX sensitivity is set)

3. Assign Central terminal Card Slots


3.1. DTU Card

1. Highlight shelf, click right mouse button, click 'element view', and select 'Airspan DA CT Modem Shelf'




| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


- Highlight slot 5 for the DTU (Slot 5 is the first slot available for assigning as a DTU) and click right mouse button select 'Create Aux' from the 'edit menu'



- Select 'Airspan DA DTU'
- Display the shelf view and select the DTU card. Click right mouse button and select 'Airspan DA DTU Properties'.



- Set the impedance of the backhaul connections and the backhaul link used to connect the CTU and DTU. Set the Freelist entries to 5 for 160k and 2 for 80k.



Edit Card State

Radio List Management

Max. Net Entry Channels: 2

Free List Entries (160k): 5

Free List Entries (80k): 2

Free List Entries (40k): 0

Incoming Call Availability: 38 %

FRU State

☒ In Service

☐ Emulator

R/W Management

| R/W | State |
|-----|-------|
| 6 | IS |
| 7 | IS |
| 8 | IS |
| 9 | IS |
| 10 | IS |
| 11 | IS |
| 12 | IS |
| 13 | IS |

E1 Configuration


Backhaul E1: 1

☒ 75 Ohm ☐ 120 Ohm

OK Cancel


4. Setting up AC Rack and Shelf configuration on Sitespan

1. Highlight the site, click right mouse button and select 'Create Child Element'




2. Select *Airspan AC Rack*


| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |




- Highlight the rack in Object List, click right mouse button and select create 'Airspan DA AC shelf'



- Select the position for the AC shelf.




- From the object list shelf click right mouse button and select *Parent Properties*



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

6. Choose *Airspan DA AC Shelf*




7. Enter Shelf Name, Reference Clock Source to derive timing from the network. This is usually the first E1 on the first XTU card i.e slot 5 E1-1. The Com Port is the Sitespan PC port connected to the AC shelf. The TEI must be a unique number within the system. The shelf object list shows what TEIs have been allocated to each shelf. Leave the indirect box unchecked. The UCP threshold is used to detect changes in code phase and should be set between 3-5 to avoid unnecessary alarms. The CT shelves connected to the Access Concentrator are allocated to the E1 link connecting them, drop window and select shelf.


| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

5. Assign Access Concentrator Card Slots


1. From Object List, Shelf select Access Concentrator, click right mouse button and select *Element View*



2. Position mouse over Aux card position to insert card, click right mouse button and select *Create AUX*



3. Select the child type to create.




4. Repeat steps 1 to 3 for all cards to be installed in the shelf.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


6. Configure AC Cards

6.1. CTU

1. Position mouse over CTU card position to insert card, click right mouse button and select *Airspan CTU Properties*




2. Select the Impedance of the E1 connections to the Central Terminal. Repeat for other CTU cards.



6.2. CAS


1. With Shelf view displayed. Position mouse over the CAS Card(if CAS card installed) position to insert card, click right mouse button and select *Airspan CAS Properties*. Click left mouse button in the box alongside each E1 link provisioned to the Switch. Set the impedance of each link. If special signalling features are required, click the Configure button and enter the parameters. Repeat for other CAS cards.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |



6.3. DATA

1. With Shelf view displayed. Position mouse over the DATA Card (if DATA card installed) position to insert card, click right mouse button and select *Airspan DATA Properties*. Click left mouse button in the box alongside each E1 link provisioned to the Switch. Set the impedance of each link. If special signalling features are required, click the Configure button and enter the parameters. Repeat for other DATA cards.



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 007 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

6.4. V5.1

1. With Shelf view displayed. Position mouse over the V5.1 Card (if V5.1 card installed) position to insert card, click right mouse button and select *Airspan V5.1 Properties*. Click left mouse button on each E1 linkTab provisioned to the Switch. Enable Channel, set the impedance of each link. Enter Interface ID and Variant Number (these must match those provided at the switch). Select the service type (PSTN, ISDN or Mixed).
 - A) PSTN. Select the Timeslot 15,16 or 31 for signalling Each PSTN signalling Time Slot must be allocated a L3 address Number (these must also match those provided at the switch). Select each time slot in turn and enter the L3 number. If special signalling features are required, click the Configure button and enter the parameters. Repeat for other V5.1 cards.
 - B) ISDN Set the port and EF addresses Number (these must match those provided at the switch). The S, P and F type Cpaths can use the sane timeslot Common Channel signalling Path as the PSTN or may use a different time slot (these must match those provided at the switch).

STOP. THIS PROCEDURE HAS BEEN COMPLETED.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 008 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

SHELF CONTROLLER SOFTWARE DOWNLOADS

| STEP | PROCEDURE |
|------|-----------|
|------|-----------|

The SC must be loaded with the latest Shelf Controller and TU software to ensure that the cards operate correctly. All the software for the cards in the shelf is downloaded and stored in the SC card. All of the software versions are downloaded to the SC irrespective of whether the SC is an AC SC or a CT SC. This is useful for fault finding

1. Before downloading the latest software it **must** be placed in the 'download' directory created in the root directory on the Sitespan PC when Sitespan was installed. The SC is capable of storing two sets of configuration files
2. Connect the Access Concentrator shelf to Sitespan (ensuring the cable is connected to selected com port)






Figure 18. Access Concentrator Shelf Backplane

3. The following procedure must be followed on Sitespan to download the software to the SC card: Highlight shelf, click right mouse button and edit '*Parent Properties*'.



4. Select 'Software Downloads'


| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 008 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |



5. 'Double click' item of software to download.

| Network:MWINETT:Access Concentrator:DA AC RACK:Shelf1 | | | | |
|---|-----------------|---------------|-------------|-------|
| Description | Current Version | Other Version | New Version | State |
| AC Shelf Controller | - | - | - | |
| CT Modem Shelf Controller | - | - | - | |
| Modem EPLD | - | - | - | |
| AU EPLD | - | - | - | |

6. Check that the version for download is the latest version, select 'download'.



7. Repeat steps 5 and 6 for all the software files to be loaded. Download progress is shown on the main software download screen. Files waiting to be downloaded will show Download pending in the object list.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 008 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| >Description | Current Version | Other Version | New Version | State |
|---------------------------|-----------------|---------------|-------------|------------------|
| AC Shelf Controller | - | - | 1.70 | Download pending |
| AU EPLD | - | - | | |
| CAS XTU | - | - | 3.01 | Download pending |
| CT Modem Shelf Controller | - | - | 3.01 | Download pending |
| CTU | - | - | 1.70 | Download pending |

8. Wait for the download to complete which could take several hours.
9. Once the software downloads are complete reset by 'hot plugging' the Shelf Controller Card
10. All the cards on the modem shelf now boot-up.
11. The TU cards l display the following LED sequence:

Note: The boot-up procedure for these cards takes approximately 15minutes.


- a) Red LED, amber LEDs & green surface mount LEDs all ON. Green LED FLASHING
- b) Red LED ON, green LED FLASHING, amber LEDs OFF & green surface mount LEDs showing download progress.
- c) Green LED ON, green surface mount LEDs indicate card configuration as shown below

| LED | DTU |
|----------|-----|
| 1 Top | OFF |
| 2 | OFF |
| 3 | ON |
| 4 Bottom | OFF |


12. The rest of the cards displays the following LED sequence:

Note: The boot-up procedure for these cards takes a couple of minutes

- a) Red LED ON & green LED FLASHING
 - b) Green LED ON
13. If the cards do not boot-up correctly, which is indicated if any of the cards display a flashing red or continuous red LED only, follow the procedure in Appendix 3
14. Each card must be reset from Sitespan. Select card on shelf view 'double click' the card, or click right mouse button and select *Airspan (card type) View*



15. Click *Reset* button to reset



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 009 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

CONFIGURING THE ACCESS CONCENTRATOR

| STEP | PROCEDURE |
|------|-----------|
|------|-----------|

1. Configure the Access Concentrator

1. Select the Access Concentrator to be configured.
2. Connect the Access Concentrator shelf to Sitespan (ensuring the cable is connected to selected com port)




Figure 19. Access Concentrator Shelf Backplane

3. Re-boot the Shelf Controller card by 'Hotplugging'.
4. SC card boots-up and displays the following LED sequence:
 - a) Red & green LEDs both ON
 - b) All LEDs OFF
 - c) Green LED FLASHING
 - d) Green LED ON
 - e) The red LED temporarily comes ON
5. All the cards on the shelf now boot-up.
6. The TU cards display the following LED sequence:

Note: The boot-up procedure for these cards takes approximately 15minutes.

- d) Red LED, amber LEDs & green surface mount LEDs all ON. Green LED FLASHING

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 009 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

- e) Red LED ON, green LED FLASHING, amber LEDs OFF & green surface mount LEDs showing download progress.
- f) Green LED ON, green surface mount LEDs indicate card configuration as shown below

| LED | DTU | XTU |
|----------|-----|-----|
| 1 Top | OFF | ON |
| 2 | OFF | OFF |
| 3 | ON | OFF |
| 4 Bottom | OFF | OFF |

- 7. The rest of the cards displays the following LED sequence:

Note: The boot-up procedure for these cards takes a couple of minutes

- c) Red LED ON & green LED FLASHING
 - d) Green LED ON
- 8. If the cards do not boot-up correctly, i.e. any of the cards display a flashing red or continuous red LED only, follow the procedure in Appendix 2

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 009 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| | |
|-------------|------------------|
| STEP | PROCEDURE |
|-------------|------------------|

2. Alarm and Status Indications (Test 3)

1. Verify that the alarms and status indications (LED's) on the system comply with those detailed in the following tables.

Note: The following tables are set in order of appearance on the front of the card reading from top to bottom.

| TU8 | | | |
|-----------------|---------------|---|---------------|
| Position | Colour | Description | Status |
| TOP 1 | Red | Card failure LED, which shall be alight if the card self test fails, or if commanded by the SC. | OFF |
| 2 | Green | Card busy LED, to indicate live traffic is present and should not be removed. | ON |
| 3 | Red/yellow | E1 port 1 Alarm | * |
| 4 | Red/yellow | E1 port 2 Alarm | * |
| 5 | Red/yellow | E1 port 3 Alarm | * |
| 6 | Red/yellow | E1 port 4 Alarm | * |
| 7 | Red/yellow | E1 port 5 Alarm | * |
| 8 | Red/yellow | E1 port 6 Alarm | * |
| 9 | Red/yellow | E1 port 7 Alarm | * |
| 10 | Red/yellow | E1 port 8 Alarm | * |

LED Yellow if 2Mbit/s is not being sent, Red if 2Mbit/s not received.


| CU | | | |
|-----------------|---------------|---|---------------|
| Position | Colour | Description | Status |
| TOP 1 | Red | Card failure LED, which shall be alight if the card self test fails, or if commanded by the SC. | OFF |
| 2 | Green | Card busy LED, to indicate live traffic is present and should not be removed. | OFF |

| SC | | | |
|-----------------|---------------|---|---------------|
| Position | Colour | Description | Status |
| TOP 1 | Red | Card failure LED, which shall be alight if the card self test fails | OFF |
| | | OK Card is Active. | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 009 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

| PSU | | | |
|----------|--------|--|--------|
| Position | Colour | Description | Status |
| TOP 1 | Red | FUSE FAIL: Illuminated if either input fuse has blown. | OFF |
| 2 | Green | OK Card is Active. | ON |
| 3 | Red | I/P A FAIL input voltage A (BATTNEG0) not present | OFF |
| 4 | Red | I/P B FAIL input voltage B (BATTNEG1) not present | OFF |
| 5 | Red | O/P OVERLOAD. | OFF |
| 6 | Red | O/P UNDERLOAD | OFF |

Table 8. Access Concentrator Shelf Card LED Indications.




Note: LED function detailed in Table 8.

STEP


PROCEDURE

3. Self Test (Test 4)

- Execute the self test function (using Sitespan) on each card and ensure that it passes. Replace any faulty cards.
- Select card on shelf view 'double click' the card, or click right mouse button and select *Airspan (card type) View*



17. Click *Self Test* button to reset. Check that each card passes



18. This concludes the setting up at the access concentrator. The CT site can now be commissioned

STOP. THIS PROCEDURE HAS BEEN COMPLETED.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 009 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank



AS4000 Access Concentrator
Installation and Commissioning

605-0000-453

Issue 1.2dr Date 7/02/00

DLP 010

COMMISSIONING TEST RESULTS

1. Commissioning Test Results

Please photocopy test results sheet for use with each system

1.1. Test Equipment Calibration

| Item | Description | Model | Serial No | Calibration Date |
|------|--------------------|-------|-----------|---------------------|
| 1 | Digital Multimeter | | | |
| | | | | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 010 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

CUSTOMER:.....

SITE LOCATION:

RACK ID:

ENGINEER:.....

DATE:.....

| ACShelf 1 | Card Type | Serial Number | Rev Level |
|-----------|-----------|---------------|-----------|
| PSU 1 | PSU | | |
| PSU 2 | PSU | | |
| SC | SC | | |
| AUX 1 | | | |
| AUX 2 | | | |
| AUX 3 | | | |
| AUX 4 | | | |
| AUX 5 | | | |
| AUX 6 | | | |
| AUX 7 | | | |
| AUX 8 | | | |
| AUX 9 | | | |
| AUX 10 | | | |
| AUX 11 | | | |
| AUX 12 | | | |
| AUX 13 | | | |
| AUX 14 | | | |

| ACShelf 1 | Card Type | Serial Number | Rev Level |
|-----------|-----------|---------------|-----------|
| PSU 1 | PSU | | |
| PSU 2 | PSU | | |
| SC | SC | | |
| AUX 1 | | | |
| AUX 2 | | | |
| AUX 3 | | | |
| AUX 4 | | | |
| AUX 5 | | | |
| AUX 6 | | | |
| AUX 7 | | | |
| AUX 8 | | | |
| AUX 9 | | | |
| AUX 10 | | | |
| AUX 11 | | | |
| AUX 12 | | | |
| AUX 13 | | | |
| AUX 14 | | | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 010 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

Rack ID.....

| PARA | TASK / TEST | | LIMIT | RESULT |
|------|--|------------|--|--------|
| | Site Inspection & Verification | | | |
| | 2 Mbit/s Cabling | AC Shelf 1 | | |
| | | AC Shelf 2 | | |
| | | | | |
| | System Commissioning Tests | | | |
| | Test 1a Exchange DC Voltage Supply 1 Supply 2 | | -21.8 to -60.0V DC | |
| | Test 1b Exchange DC Voltage Supply 1 Supply 2 | | -21.8 to -60.0V DC | |
| | Test 2 AC Shelf 1 PSU1 | | 5V DC \pm 250mV 3.3V DC +0mV-300mV 2.1V DC+0mV-100mV | |
| | Test 2 AC Shelf 1 PSU2 | | 5V DC \pm 250mV 3.3V DC +0mV-300mV 2.1V DC+0mV-100mV | |
| | Test 2 AC Shelf 2 PSU1 | | 5V DC \pm 250mV 3.3V DC +0mV-300mV 2.1V DC+0mV-100mV | |
| | Test 2 AC Shelf 2 PSU2 | | 5V DC \pm 250mV 3.3V DC +0mV-300mV 2.1V DC+0mV-100mV | |

| PARA. | TASK / TEST | | LIMIT | RESULT |
|-------|--|--|-------|------------|
| | Power Up and Self Test | | | |
| | Test 3 AC Shelf 1 Alarms and Indications | PSU 1 PSU 2 SC Card Aux Cards (if fitted) | | Pass /Fail |
| | Test 3 AC Shelf 2 Alarms and Indications | PSU 1 PSU 2 SC Card Aux Cards (if fitted) | | |

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 010 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

Rack ID.....

| PARA. | TASK / TEST | | RESULT |
|--------------|---|--|---------------|
| | Test 4 AC Shelf 1 System Configuration Self test from Sitespan | SC Card AUX 1 AUX 2 AUX 3 AUX 4 AUX 5 AUX 6 AUX 7 AUX 8 AUX 9 AUX 10 AUX 11 AUX 12 AUX 13 AUX 14 | |
| | Test 4 AC Shelf 2 System Configuration Self test from Sitespan | SC Card AUX 1 AUX 2 AUX 3 AUX 4 AUX 5 AUX 6 AUX 7 AUX 8 AUX 9 AUX 10 AUX 11 AUX 12 AUX 13 AUX 14 | |



| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 011 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

SITE ACCEPTANCE

1. Site Inspection

Check all work areas are free of debris i.e. cable off-cuts, braid, dust and packaging and that the site is as found.

2. Site Acceptance Forms

ACC and customer copies of site acceptance forms are provided on the following pages.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 011 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This page left blank.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 011 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

AS4000- ACCESS CONCENTRATOR ACCEPTANCE FORM

CONTRACT OR CUSTOMER'S REF. NO:.....

AS4000 COMMUNICATIONS CORPORATION LTD REF. NO:.....

SITE IDENTITY:.....

The Customer accepts that the following equipment has been supplied, installed and tested.

.....
.....
.....

| | |
|--------------------------------|-------------------------|
| Customer Representative | |
| Name: _____ | Position: _____ |
| Date: _____ | Signature: _____ |
| ACC Representative | |
| Name: _____ | Position: _____ |
| Date: _____ | Signature: _____ |

ACC COPY

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 011 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This page left blank.

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 011 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

AS4000- ACCESS CONCENTRATOR ACCEPTANCE FORM

CONTRACT OR CUSTOMER'S REF. NO:.....

AS4000 COMMUNICATIONS CORPORATION LTD REF. NO:.....

SITE IDENTITY:.....

The Customer accepts that the following equipment has been supplied, installed and tested.

.....
.....
.....

| | |
|--------------------------------|-------------------------|
| Customer Representative | |
| Name: _____ | Position: _____ |
| Date: _____ | Signature: _____ |
| ACC Representative | |
| Name: _____ | Position: _____ |
| Date: _____ | Signature: _____ |

CUSTOMER COPY

| | |
|--|----------------|
| AS4000 Access Concentrator Installation and Commissioning | DLP 011 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


This Page Left Blank




APPENDIX 1

Appendix 1 BNC Terminations to Coax


1. Slide metal crimp sleeve over cable, trim outer sheath from cable as shown.




2. Trim back braid and dielectric to the dimensions as shown.




3. Fit contact over the centre conductor to butt against the dielectric, then crimp.



4. Press sub-assembly into body, until contact clicks into place and ensuring that the knurled ferrule is inserted between the dielectric and braid



5. Slide the sleeve along the cable, until it butts against the body sub-assembly. Crimp using VQ die.



| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 1 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank



PROCEDURE IN CASE OF CARD BOOT-UP FAILURE

Procedure in case of card boot-up failure

If the cards inserted into the shelf do not boot-up, the top red LED on the card will be either continuously ON or FLASHING. The following steps should be followed:

1. Check cards are properly inserted into the shelf, in the correct positions.
2. Reset the SC card using Sitespan, under the card view.
3. The cards boot-up. If the cards do not boot-up try and reset the shelf backplane configuration. Download the SetTUinv.txt to the SC. Ensure they are available before continuing.
4. Disconnect Sitespan from the shelf containing cards that will not boot-up.
5. Connect the LAT cable to the SC card
6. Send the text files for the correct shelf, one after another using Terminal.
7. Once completed, type the following:

TI 118

EA 118:0/119:0

ES 0

8. Wait 2 – 3 minutes for the process to complete.
9. Reset the SC by shorting Pins 2 & 3
10. Wait for 3 minutes: After 3 minutes the Shelf Controller has a green LED ON, and all the other cards have FLASHING red LEDs
11. Re-Connect Sitespan
12. The cards on the shelf boot-up. If the cards do not boot-up, then it is likely that one of the cards is faulty. Try replacing one of the cards and starting the procedure again.

NOTE: Try swapping the SC cards between the AC and the CT shelf, because all the latest software should be installed on both cards. This way it is easy to tell if the SC card is faulty or not.

| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 2 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |




This Page Intentionally Blank



LAT SETTINGS

1. LAT connected to SC

The following pictures show the Terminal Settings used when connecting a LAT terminal to the Shelf Controller:





| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 3 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank




SITESPAN DATABASE TRANSLATION V2.5 TO V3.4

1. Close down all Sitespan Client/Server applications running on the network.
2. Ensure that the server25.olg & server25.svd files are located on the root C: drive of your PC.
3. Ensure that server34.olg & server34.svd files **DO NOT** exist on the root C: drive of your PC.
4. If there is a server34.olg or server34.svd file in the directory then delete it/them.
5. Run the Sitespan V3.4 "trans" program




| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 4 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


6. Run the Sitespan Server for Sitespan V2.5



7. In the “Trans” program connect to the V2.5 Server by selecting “Create” and Select OK when asked to connect to the Remote Machine Name




8. The Source Server will then indicate that it is Connected and Ready




| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 4 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


9. Disconnect the Source Server (V2.5).



10. Shut down the Sitespan V2.5 Server program



11. Start the Destination Server V3.4




| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 4 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |


12. Connect to the Destination Server



1. The destination server will indicate that it is connected and ready



2. Click on the Transfer button. This will start converting the V2.5 database to the new V3.4 format



3. A status message will be displayed when the conversion has been completed

| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 4 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

4. Close the V3.4 Server and exit the “trans” program.

The files C:server34.olg & C:server34.svd should now be created on your PC.

Your Database is now compatible with the new V3.4 Server & Client applications.

| | |
|--|-----------------------|
| AS4000 Access Concentrator Installation and Commissioning | Appendix 4 |
| 605-0000-453 | |
| Issue 1.2dr Date 7/02/00 | |

This Page Intentionally Blank