

Nemko Test Report No.:

2L0288RUS1rev2

Applicant:

DeKolink Wireless

16 Bazel St. Qiryat-Arieh Petah-Tikva
Israel 49510

Equipment Under Test:

Compact Bi Directional Amplifier

In Accordance With:

FCC Part 24, Subpart E

Broadband PCS Repeaters

Tested By:

Nemko Dallas Inc.

802 N. Kealy

Lewisville, Texas 75057-3136



Authorized By:

Tom Tidwell, Wireless Group Manager

Date:

7/16/2002

Total Number of Pages:

79

Table of Contents

Section 1. Summary of Test Results	3
Section 2. General Equipment Specification	5
Section 3. RF Power Output	7
Section 4. Occupied Bandwidth.....	8
Section 5. Spurious Emissions at Antenna Terminals	25
Section 6. Field Strength of Spurious	62
Section 7. Frequency Stability	68
Section 8. Test Equipment List.....	69
ANNEX A - TEST DETAILS	70
ANNEX B - TEST DIAGRAMS	76

Section 1. Summary of Test Results

Manufacturer: DeKolink Wireless

Model No.: MW-CBDA-PCS-X-1W65 (X indicates PCS block of operation)

Serial No.: 02039040/02039042

General: **All measurements are traceable to national standards.**

These tests were conducted on a sample of the equipment for the purpose of demonstrating compliance with FCC Part 24, Subpart E.



New Submission



Production Unit



Class II Permissive Change



Pre-Production Unit

THIS TEST REPORT RELATES ONLY TO THE ITEM (S) TESTED.

THE FOLLOWING DEVIATIONS FROM, ADDITIONS TO, OR EXCLUSIONS FROM THE TEST SPECIFICATIONS HAVE BEEN MADE.

See “ Summary of Test Data”.

Nemko Dallas Inc. authorizes the above named company to reproduce this report provided it is reproduced in its entirety and for use by the company's employees only.

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Nemko Dallas Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report. This report applies only to the items tested.

Summary Of Test Data

NAME OF TEST	PARA. NO.	SPEC.	RESULT
RF Power Output	24.232	100W	Complies
Occupied Bandwidth (CDMA)	24.238	Input/Output	Complies
Spurious Emissions at Antenna Terminals	24.238(a)	-13 dBm	Complies
Field Strength of Spurious Emissions	24.238(a)	-13 dBm E.I.R.P.	Complies
Frequency Stability	24.235		N /A

Footnotes:

(1) Modulation characteristics were not tested since the E.U.T. processes but does not produce a modulated waveform.

Measurement uncertainty for each test configuration is expressed to 95% probability.


Section 2. General Equipment Specification

Supply Voltage Input:	115 VAC		
Frequency Bands: Downlink:	☒ Block A : 1930 – 1945 MHz ☒ Block D : 1945 – 1950 MHz ☒ Block B : 1950 – 1965 MHz ☒ Block E : 1965 – 1970 MHz ☒ Block F : 1970 – 1975 MHz ☒ Block C : 1975 – 1990 MHz		
Frequency Bands: Uplink:	☒ Block A : 1850 – 1865 MHz ☒ Block D : 1865 – 1870 MHz ☒ Block B : 1870 – 1885 MHz ☒ Block E : 1885 – 1890 MHz ☒ Block F : 1890 – 1895 MHz ☒ Block C : 1895 – 1910 MHz		
Type of Modulation and Designator:	CDMA (1M25G7W) ☒	GSM (200KGXW) ☒	
System Gain (rated):	65 dB		
Output Impedance:	50 ohms		
Max Input:	-45 dBm		
RF Output (Rated):	Uplink Downlink	0.25 W Total: 0.50 W	
Frequency Translation:	F1-F1 ☒	F1-F2 ☐	N/A ☐
Band Selection:	Software ☐	Duplexer ☒	Full band ☐

Description of Operation

The Compact Bi-Directional Amplifier (CBDA) assembly provides a repeater/booster to extend the coverage area of radio communications in buildings and RF shielded environments.

The CBDA Downlink amplifier receives the RF signals from base station amplifies and transmits them to the subscriber. The BDA Uplink amplifier receives the RF signals from the subscriber amplifies and transmits them to the base station.

Diagram

Section 3. RF Power Output

NAME OF TEST: RF Power Output	PARA. NO.: 2.1046
TESTED BY: Kevin Rose & David Light	DATE: 5/23/02

Test Results: Complies.**Measurement Data:**

	Modulation Type	Channel Output Power (dBm)	Channel Output Power (Watts)
Downlink A	CDMA	26.8	0.479
Uplink A	CDMA	24.1	0.257
Downlink C	CDMA	27.1	0.513
Uplink C	CDMA	23.9	0.245
Downlink A	GSM	27.3	0.537
Uplink A	GSM	25.6	0.363
Downlink C	GSM	26.8	0.479
Uplink C	GSM	25.2	0.380

Note - Device was tested at +/- 15% nominal voltage with no effect on output power

Equipment Used: 1464-1604-1052-1053-1036**Measurement Uncertainty:** +/- 1.7 dB**Temperature:** 23 °C**Relative Humidity:** 38 %

EQUIPMENT: Compact Bi Directional Amplifier

Section 4. Occupied Bandwidth

NAME OF TEST: Occupied Bandwidth (CDMA)	PARA. NO.: 2.1049
TESTED BY: Kevin Rose & David Light	DATE: 5/23/02

Test Results: Complies.**Test Data:** See attached plot(s).**Equipment Used:** 1464-1604-1052-1053**Measurement +/- 1.7 dB
Uncertainty:****Temperature:** 21 °C**Relative 35 %
Humidity:**

EQUIPMENT: Compact Bi Directional Amplifier



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667


Data Plot

Occupied Bandwidth

Page 1 of 4
Job No.: 210288r Date: May 23 2002 Complete x
Specification: 2.1049 Temperature(°C): 23 Preliminary: _____
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power
Sample Number: 2039040
Location: Lab 1 RBW: Refer to plots
Detector Type: Peak VBW: Refer to plots

Test Equipment Used

Antenna: _____ Directional Coupler: _____
Pre-Amp: _____ Cable #1: 1043
Filter: _____ Cable #2: 1046
Receiver: 1464 Cable #3: _____
Attenuator #1: 1604 Cable #4: _____
Attenuator #2: i wave model 392 Mixer: _____
Additional equipment used: 1053 1052
Measurement Uncertainty: +/-1.7 dB



Notes: Band A Output signal CDMA Uplink



Nemko Dallas, Inc.


Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667**Data Plot**

Page 2 of 4

Occupied Bandwidth

Job No.: 210288r Date: May 23 2002
Specification: 2.1 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power

Notes: Band A input signal CDMA UPlink



Nemko Dallas, Inc.


Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Occupied Bandwidth

Page 3 of 4
Job No.: 210288r Date: May 23 2002
Specification: 2.1049 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power



Notes: Band A output signal CDMA downlink



Nemko Dallas, Inc.


Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Test Plot:

Occupied Bandwidth

Page 4 of 4
Job No.: 210288r Date: May 23 2002
Specification: 2.1049 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power



Notes: Band A input signal CDMA Downlink



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot


Occupied Bandwidth

Page 1 of 4

Job No.: 210288r Date: May 23 2002 Complete x
Specification: 2.1049 Temperature(°C): 23 Preliminary: _____
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power
Sample Number: 2039042
Location: Lab 1 RBW: Refer to plots
Detector Type: Peak VBW: Refer to plots

Test Equipment Used

Antenna: _____ Directional Coupler: _____
Pre-Amp: _____ Cable #1: 1043
Filter: _____ Cable #2: 1046
Receiver: 1464 Cable #3: _____
Attenuator #1: 1604 Cable #4: _____
Attenuator #2: i wave model 392 Mixer: _____
Additional equipment used: 1053 1052
Measurement Uncertainty: +/-1.7 dB



Notes: Band C Output signal CDMA uplink



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Page 2 of 4

Job No.: 210288r

Date: May 23 2002

Specification: 2.1049

Temperature(°C): 23

Tested By: Kevin Rose


Relative Humidity(%) 38

E.U.T.: C Band repeater Dekolink

Configuration: TX full Power

Occupied Bandwidth

*ATTEN 10dB
RL 0dBm 10dB/ MKR -46.50dBm
1.899600GHz



CENTER 1.900000GHz SPAN 5.000MHz
RBW 30kHz VBW 30kHz SWP 50.0ms

Notes: Band C input signal CDMA Uplink



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Page 3 of 4

Job No.: 210288r Date: May 23 2002
Specification: 2.1049 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power

Occupied Bandwidth



Notes: Band C output signal CDMA Downlink




Nemko Dallas, Inc.

Dallas Headquarters:
802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Test Plot:

Occupied Bandwidth

Page 4 of 4
Job No.: 210288r Date: May 23 2002
Specification: 2.1049 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power



Notes: Band C input signal CDMA Downlink



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy

Lewisville, TX 75057

Tel: (972) 436-9600

Fax: (972) 436-2667

Data Plot

Page 1 of 4

Job No.: 2L0288

Specification: Part 24

Tested By: David Light

E.U.T.:	<u>BDA</u>
---------	------------

Configuration:	<u>TX FULL POWER</u>
----------------	----------------------

Sample Number: 1

Location:	Lab 1
-----------	-------

Detector Type:	Peak
----------------	------

Date: 7/16/2002Temperature(°C): 22

Relative Humidity(%)	55
----------------------	----

RBW: Refer to plots

VBW: Refer to plots

Complete X

Preliminary: _____

Occupied Bandwidth

Test Equipment Used

Antenna: _____

Pre-Amp: _____

Filter: _____

Receiver: 1036

Attenuator #1	1604
---------------	------

Attenuator #2:

Directional Coupler: _____

Cable #1:	1082
-----------	------

Cable #2: _____


Cable #3:

Cable #4: _____

Mixer: _____

Additional equipment used:

Measurement Uncertainty:	+/-1.7 dB
--------------------------	-----------



Date: 16.JUL.2002 14:05:11


Notes: **OUTPUT - UPLINK - A BLOCK**



Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.






Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.






Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.





Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Page 1 of 4

Occupied Bandwidth

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%): 55
E.U.T.: BDA
Configuration: TX FULL POWER
Sample Number: 1
Location: Lab 1 RBW: Refer to plots
Detector Type: Peak VBW: Refer to plots

Complete: x
Preliminary:

Measurement
Distance: NA m


Test Equipment Used

Antenna: Directional Coupler:
Pre-Amp: Cable #1: 1082
Filter: Cable #2:
Receiver: 1036 Cable #3:
Attenuator #1: 1604 Cable #4:
Attenuator #2: Mixer:
Additional equipment used:
Measurement Uncertainty: +/-1.7 dB



Ref Lvl
30 dBm

RBW 30 kHz RF Att 30 dB
VBW 30 kHz
SWT 6 ms Unit dBm



Date: 16.JUL.2002 13:40:15


Notes: OUTPUT - UPLINK - C BLOCK



Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.






Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667**Data Plot**

Page 3 of 4

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER

Occupied Bandwidth

Date: 16.JUL.2002 13:48:43

Notes: OUT PUT - DOWNLINK - C BLOCK



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Test Plot:**Occupied Bandwidth**

Page 4 of 4

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 13:46:55

Notes: INPUT - DOWNLINK - C BLOCK

EQUIPMENT: Compact Bi Directional Amplifier

Section 5. Spurious Emissions at Antenna Terminals

NAME OF TEST: Spurious Emissions @ Antenna Terminals	PARA. NO.: 2.1051
TESTED BY: Kevin Rose & David Light	DATE: 5/23/02

Test Results: Complies.

Test Data: See attached plot(s).

Equipment Used: 1464-1604-1052-1053

**Measurement +/- 1.6 dB
Uncertainty:**


Temperature: 23 °C

**Relative 38 %
Humidity:**

Test Data --- Spurious Emissions at Antenna Terminals

		Dallas Headquarters: 802 N. Kealy Lewisville, TX 75057 Tel: (972) 436-9600 Fax: (972) 436-2667	
Nemko Dallas, Inc.			
Data Plot		Spurious Emissions at Antenna Terminals	
Page <u>1</u> of 4		Complete <u>x</u>	
Job No.:	210288r	Date:	May 23 2002
Specification:	2.1051	Temperature(°C):	23
Tested By:	Kevin Rose	Relative Humidity(%)	38
E.U.T.:	A Band repeater Dekolink		
Configuration:	TX full Power		
Sample Number:	2039040		
Location:	Lab 1	RBW:	Refer to plots
Detector Type:	Peak	VBW:	Refer to plots
Test Equipment Used			
Antenna:		Directional Coupler:	
Pre-Amp:		Cable #1:	1043
Filter:		Cable #2:	1046
Receiver:	1464	Cable #3:	
Attenuator #1:	1604	Cable #4:	
Attenuator #2:	i wave model 392	Mixer:	
Additional equipment used:	1053 1052		
Measurement Uncertainty:	+/-1.7 dB		

*ATTEN 10dB MKR -41.00dBm
RL 31.0dBm 10dB/ 877.1MHz



START 30.0MHz STOP 1.0000GHz
*RBW 100kHz VBW 100kHz SWP 250ms

Notes:	Band A 30 Mhz - 1 Ghz display line -13dBm
	Downlink. Marker indicates the highest emission




Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667**Data Plot**

Page 2 of 4

Job No.: 210288r Date: May 23 2002
Specification: 2.1051 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power

Spurious Emissions at Antenna Terminals

Notes: Band A 1Ghz-20Ghz display line -13dBm
Downlink. Marker indicates the highest emission



Nemko Dallas, Inc.


Dallas Headquarters:
802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Spurious Emissions at Antenna Terminals

Page 3 of 4

Job No.: 210288r Date: May 23 2002
Specification: 2.1051 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power



Notes: Band A 1Ghz-20Ghz display line -13dBm
Uplink marker indicates the highest emission



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Test Plot:

Page 4 of 4


Spurious Emissions at Antenna Terminals

Job No.: 210288r Date: May 23 2002
Specification: 2.1051 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power



Notes: Band A 30 Mhz - 1 Ghz display line -13dBm
Uplink. Marker indicates the highest emission

EQUIPMENT: Compact Bi Directional Amplifier

		Dallas Headquarters: 802 N. Kealy Lewisville, TX 75057 Tel: (972) 436-9600 Fax: (972) 436-2667	
Nemko Dallas, Inc.			
Data Plot Page 1 of 2 Job No.: 210288r Specification: 2.1051 Tested By: Kevin Rose E.U.T.: C Band repeater Dekolink Configuration: TX full Power Sample Number: 2039042 Location: Lab 1 Detector Type: Peak		Spurious Emissions at Antenna Terminals Date: May 23 2002 Temperature(°C): 23 Relative Humidity(%) 38 Complete <u> x </u> Preliminary: _____ RBW: Refer to plots VBW: Refer to plots	
Test Equipment Used			
Antenna: _____ Pre-Amp: _____ Filter: _____ Receiver: 1464 Attenuator #1: 1604 Attenuator #2: i wave model 392 Additional equipment used: 1053 1052 Measurement Uncertainty: +/-1.7 dB		Directional Coupler: _____ Cable #1: 1043 Cable #2: 1046 Cable #3: _____ Cable #4: _____ Mixer: _____	
ATTEN 10dB RL 31.0dBm 10dB/ MKR -39.50dBm 356.6MHz R  START 30.0MHz STOP 1.0000GHz *RBW 100kHz VBW 100kHz SWP 250ms			
Notes: Band C 30 Mhz - 1 Ghz display line -13dBm downlink marker indicates the highest emission			




Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667**Data Plot**


Page 2 of 2

Job No.: 210288r Date: May 23 2002
Specification: 2.1051 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power

Spurious Emissions at Antenna Terminals

Notes: Band C 1Ghz-20Ghz display line -13dBm
Downlink. Marker indicates the highest emission

EQUIPMENT: Compact Bi Directional Amplifier

		Dallas Headquarters: 802 N. Kealy Lewisville, TX 75057 Tel: (972) 436-9600 Fax: (972) 436-2667	
Nemko Dallas, Inc.			
Data Plot Page 1 of 2 Job No.: 210288r Specification: 2.1051 Tested By: Kevin Rose E.U.T.: C Band repeater Dekolink Configuration: TX full Power Sample Number: 2039042 Location: Lab 1 Detector Type: Peak		Spurious Emissions at Antenna Terminals Date: May 23 2002 Temperature(°C): 23 Relative Humidity(%): 38 RBW: Refer to plots VBW: Refer to plots	
		Complete <u> x </u> Preliminary: _____	
Test Equipment Used			
Antenna: _____		Directional Coupler: _____	
Pre-Amp: _____		Cable #1: 1043	
Filter: _____		Cable #2: 1046	
Receiver: 1464		Cable #3: _____	
Attenuator #1: 1604		Cable #4: _____	
Attenuator #2: i wave model 392		Mixer: _____	
Additional equipment used: 1053 1052			
Measurement Uncertainty: +/-1.7 dB			
ATTEN 10dB MKR -39.33dBm RL 31.0dBm 10dB/ 549.0MHz			
			
START 30.0MHz STOP 1.0000GHz *RBW 100kHz VBW 100kHz SWP 250ms			
Notes: Band C 30MHz - 1GHz display line -13dBm Uplink. Marker indicates the highest emission			



Nemko Dallas, Inc.


Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Spurious Emissions at Antenna Terminals

Page 2 of 2
Job No.: 210288r Date: May 23 2002
Specification: 2.1051 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power



Notes: Band C 1GHz-20GHz display line -13dBm
Uplink. Marker indicates the highest emission



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot


Bandedges

Page 1 of 2

Job No.: 210288r Date: May 23 2002 Complete x
Specification: 24.238 Temperature(°C): 23 Preliminary: _____
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power
Sample Number: 2039040
Location: Lab 1 RBW: Refer to plots
Detector Type: Peak VBW: Refer to plots

Test Equipment Used

Antenna: _____ Directional Coupler: _____
Pre-Amp: _____ Cable #1: 1043
Filter: _____ Cable #2: 1046
Receiver: 1464 Cable #3: _____
Attenuator #1: 1604 Cable #4: _____
Attenuator #2: i wave model 392 Mixer: _____
Additional equipment used: 1053 1052
Measurement Uncertainty: +/-1.7 dB



Notes: Band A Output signal CDMA downlink
band edge 1.93Ghz display line is -13dBm



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Page 2 of 2

Job No.: 210288r Date: May 23 2002
Specification: 24.2380 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power

Bandedges



Notes: Band C input signal CDMA Downlink
Band Edge 1.85Ghz display line is -13dBm

EQUIPMENT: Compact Bi Directional Amplifier



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Page 1 of 2

Job No.: 210288r

Date: May 23 2002

Specification: 24.238

Temperature(°C): 23

Tested By: Kevin Rose

Relative Humidity(%) 38

E.U.T.: C Band repeater Dekolink

Configuration: TX full Power

Sample Number: 2039042

Location: Lab 1

RBW: Refer to plots

Detector Type: Peak

VBW: Refer to plots

Complete xPreliminary:

Test Equipment Used

Antenna: Directional Coupler: Pre-Amp:

Cable #1: 1043

Filter:

Cable #2: 1046

Receiver: 1464

Cable #3:

Attenuator #1: 1604


Cable #4:

Attenuator #2: i wave model 392

Mixer:

Additional equipment used: 1053 1052

Measurement Uncertainty: +/-1.7 dB



Notes: Band C Output signal CDMA uplink
band edge 1.91GHz



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Page 2 of 2

Job No.: 210288r Date: May 23 2002
Specification: 24.2 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power

Bandedges



Notes: Band C input signal CDMA downlink
Band Edge 1.99Mhz

EQUIPMENT: Compact Bi Directional Amplifier



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Intermodulation Characteristics

Page 1 of 4

Job No.: 210288r

Date: May 23 2002

Complete x

Specification: 2.1049

Temperature(°C): 23

Preliminary:

Tested By: Kevin Rose

Relative Humidity(%) 38

E.U.T.: A Band repeater Dekolink

Configuration: TX full Power

Sample Number: 2039042

Location: Lab 1

RBW: Refer to plots

Detector Type: Peak

VBW: Refer to plots

Test Equipment Used

Antenna: Directional Coupler: Pre-Amp:

Cable #1: 1043

Filter:

Cable #2: 1046

Receiver: 1464

Cable #3:

Attenuator #1: 1604


Cable #4:

Attenuator #2: i wave model 392

Mixer:

Additional equipment used: 1053 1052

Measurement Uncertainty: +/-1.7 dB



Notes: Band A band peak emission out of band CDMA
down link



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Intermodulation Characteristics

Page 3 of 4

Job No.: 210288r Date: May 23 2002
Specification: 2.1049 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: A Band repeater Dekolink
Configuration: TX full Power



Notes: Band A band peak emission out of band CDMA Uplink



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Intermodulation Characteristics


Page 1 of 4

Job No.: 210288r Date: May 23 2002
Specification: 2.1049 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power
Sample Number: 2039042
Location: Lab 1 RBW: Refer to plots
Detector Type: Peak VBW: Refer to plots

Complete x
Preliminary: _____

Test Equipment Used

Antenna: _____ Directional Coupler: _____
Pre-Amp: _____ Cable #1: 1043
Filter: _____ Cable #2: 1046
Receiver: 1464 Cable #3: _____
Attenuator #1: 1604 Cable #4: _____
Attenuator #2: i wave model 392 Mixer: _____
Additional equipment used: 1053 1052
Measurement Uncertainty: +/-1.7 dB



Notes: Band C upper band peak emission out of band CDMA Uplink
down link



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Intermodulation Characteristics

Page 3 of 4

Job No.: 210288r Date: May 23 2002
Specification: 2.1049 Temperature(°C): 23
Tested By: Kevin Rose Relative Humidity(%) 38
E.U.T.: C Band repeater Dekolink
Configuration: TX full Power



Notes: Band C upper band peak emission out of band CDMA Uplink
uplink



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Page 1 of 5

Spurious Emissions at Antenna Terminals


Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%): 55
E.U.T.: BDA
Configuration: TX FULL POWER
Sample Number: 1
Location: Lab 1 RBW: Refer to plots
Detector Type: Peak VBW: Refer to plots

Complete x
Preliminary:

Measurement
Distance: NA m

Test Equipment Used

Antenna: Directional Coupler:
Pre-Amp: Cable #1: 1082
Filter: Cable #2:
Receiver: 1036 Cable #3:
Attenuator #1: 1604 Cable #4:
Attenuator #2: Mixer:
Additional equipment used:
Measurement Uncertainty: +/-1.7 dB




Notes: MARKER 1 INDICATES CARRIER LEVEL
MARKER 2 INDICATES HIGHEST OUT OF BAND EMISSION
LOWER BANDEDGE - A BLOCK



Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.






Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667**Data Plot****Spurious Emissions at Antenna Terminals**

Page 3 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 10:12:36

Notes: UPPER BANDEDGE
MARKER INDICATES CARRIER FREQUENCY
Uplink



Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Test Plot:

Page 4 of 5

Job No.: 2L0288

Date: 7/16/2002Specification: Part 24

Temperature(°C): 22


Tested By:	David Light
------------	-------------

Relative Humidity(%) 55

E.U.T.:	BDA
---------	-----

Configuration:	TX FULL POWER
----------------	---------------

Spurious Emissions at Antenna Terminals



Date: 16.JUL.2002 10:14:36

Notes:

Lower bandedge

Marker indicates carrier frequency

Uplink



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Test Plot:

Spurious Emissions at Antenna Terminals

Page 5 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 11:01:08

Notes: Harmonic emissions - Uplink



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667



Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.






Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.





Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot**Spurious Emissions at Antenna Terminals**

Page 3 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Notes: UPPER BANDEDGE
MARKER INDICATES CARRIER FREQUENCY
DOWNLINK



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Test Plot:**Spurious Emissions at Antenna Terminals**

Page 4 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 12:29:15

Notes: Lower bandedge
Marker indicates carrier frequency
DOWNLINK




Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667**Test Plot:****Spurious Emissions at Antenna Terminals**

Page 5 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 12:31:56


Notes: Harmonic emissions - DOWNLINK



Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.






Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.





Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Spurious Emissions at Antenna Terminals

Page 3 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 13:29:40

Notes: UPPER BANDEGE
MARKER INDICATES CARRIER FREQUENCY
UPLINK



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Test Plot:**Spurious Emissions at Antenna Terminals**

Page 4 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 13:28:33

Notes: Lower bandedge
Marker indicates carrier frequency
UPLINK



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Test Plot:

Spurious Emissions at Antenna Terminals

Page 5 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER




Date: 16.JUL.2002 13:26:53

Notes: Harmonic emissions - UPLINK



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot**Spurious Emissions at Antenna Terminals**

Page 2 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 12:45:36

Notes: MARKER 1 INDICATES CARRIER LEVEL
MARKER 2 INDICATES HIGHEST OUT OF BAND EMISSION
UPPER BANDEDGE - C BLOCK
DOWNLINK



Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot

Spurious Emissions at Antenna Terminals

Page 3 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 12:47:29


Notes: UPPER BANDEDGE
MARKER INDICATES CARRIER FREQUENCY
DOWNLINK



Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.





Nemko Dallas, Inc.

Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Test Plot:

Spurious Emissions at Antenna Terminals

Page 5 of 5

Job No.: 2L0288 Date: 7/16/2002
Specification: Part 24 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 55
E.U.T.: BDA
Configuration: TX FULL POWER



Date: 16.JUL.2002 12:50:43

Notes: Harmonic emissions - DOWNLINK

Section 6. Field Strength of Spurious

NAME OF TEST: Field Strength of Spurious Emissions	PARA. NO.: 2.1051
TESTED BY: Kevin Rose	DATE: 5/24/02

Test Results: Complies.

Test Data: See attached table.

Equipment Used: 1016-1464-1043-1484-1485

Measurement +/-1.7 dB
Uncertainty:

Temperature: 23 °C

Relative 38 %
Humidity:

Test Data --- Field Strength of Spurious

						Dallas Headquarters: 802 N. Kealy Lewisville, TX 75057 Tel: (972) 436-9600 Fax: (972) 436-2667				
Nemko Dallas, Inc.										
Field Strength of Spurious Emissions										
Page 1 of 1						Complete <u> X </u>				
Job No.: 210288r		Date: 5/24/2002				Preliminary <u> </u>				
Specification: 2.1053		Temperature(°C): 21								
Tested By: Kevin Rose		Relative Humidity(%) 48								
E.U.T.: band A PCS CDMA repeater uplink										
Configuration: Tx Full Power										
Sample No: 2039040										
Location: AC 3		RBW: 1 MHz				Measurement				
Detector Type: Peak		VBW: 1 MHz				Distance: 3 m				
Test Equipment Used										
Antenna: 1304		Directional Coupler:								
Pre-Amp: 1016		Cable #1: 1043								
Filter:		Cable #2: 1484								
Receiver: 1464		Cable #3: 1485								
Attenuator #1:		Cable #4:								
Attenuator #2:		Mixer:								
Additional equipment used:										
Measurement Uncertainty: +/-3.6 dB										
Frequency (MHz)	Meter Reading (dBm)	Correction Factor (dB)		Pre-Amp Gain (dB)	Substitution Antenna Gain (dBd)		ERP (dBm)	ERP (mW)	Polarity	Comments
3706	-59.3	40.4		33.3	8.0		-44.2	0.000038	V	uplink
5559	-62.4	38.5		32.5	9.1		-47.3	0.000018	V	uplink
7412	-61.3	39.4		33.4	10.0		-45.3	0.000030	V	uplink
9265	-61.6	39.3		36.1	10.1		-48.4	0.000015	V	uplink
11118	-61.5	42.0		36.1	11.1		-44.6	0.000035	V	uplink / NF
12971	-61.3	44.5		34.2	11.7		-39.3	0.000118	V	uplink / NF
14824	-62.4	48.1		34.5	10.1		-38.7	0.000135	V	uplink / NF
16677	-62.5	44.3		34.9	13.0		-40.1	0.000099	V	uplink / NF
18530	-61.2	53.1		34.2	6.4		-36.0	0.000254	V	uplink / NF
3706	-58.3	34.3		33.3	8.0		-49.3	0.000012	H	uplink
5559	-61.7	36.0		32.5	9.1		-49.1	0.000012	H	uplink
7412	-61.5	38.7		33.4	10.0		-46.2	0.000024	H	uplink
9265	-62.1	41.4		36.1	10.1		-46.8	0.000021	H	uplink
11118	-62.3	44.4		36.1	11.1		-42.9	0.000051	H	uplink / NF
12971	-62.4	47.5		34.2	11.7		-37.4	0.000183	H	uplink / NF
14824	-61.8	48.7		34.5	10.1		-37.5	0.000177	H	uplink / NF
16677	-61.5	46.1		34.9	13.0		-37.2	0.000189	H	uplink / NF
18530	-60.9	54.6		34.2	6.4		-34.1	0.000393	H	uplink / NF
Notes: uplink 1853 MHz / Scanned to the 10th harmonic										

EQUIPMENT: Compact Bi Directional Amplifier

BROADBAND PCS REPEATERS
PROJECT NO.: 2L0288RUS1rev2

						Dallas Headquarters: 802 N. Kealy Lewisville, TX 75057 Tel: (972) 436-9600 Fax: (972) 436-2667				
Nemko Dallas, Inc.										
<u>Field Strength of Spurious Emissions</u>										
Page <u>1</u> of <u>1</u> Job No.: <u>210288r</u> Date: <u>5/24/2002</u> Specification: <u>2.1053</u> Temperature(°C): <u>21</u> Tested By: <u>Kevin Rose</u> Relative Humidity(%) <u>48</u> E.U.T.: <u>band A PCS CDMA repeater downlink</u> Configuration: <u>Tx Full Power</u> Sample No: <u>2039040</u> Location: <u>AC 3</u> RBW: <u>1 MHz</u> Measurement Detector Type: <u>Peak</u> VBW: <u>1 MHz</u> Distance: <u>3</u> m						Complete <u>X</u> Preliminary _____				
<u>Test Equipment Used</u> Antenna: <u>1304</u> Directional Coupler: _____ Pre-Amp: <u>1016</u> Cable #1: <u>1043</u> Filter: _____ Cable #2: <u>1484</u> Receiver: <u>1464</u> Cable #3: <u>1485</u> Attenuator #1: _____ Cable #4: _____ Attenuator #2: _____ Mixer: _____ Additional equipment used: _____ Measurement Uncertainty: <u>+/-3.6 dB</u>										
Frequency (MHz)	Meter Reading (dBm)	Correction Factor (dB)		Pre-Amp Gain (dB)	Substitution Antenna Gain (dBd)		ERP (dBm)	ERP (mW)	Polarity	Comments
3880	-60.8	40.4		33.3	8.0		-45.7	0.000027	V	downlink
5820	-61.0	38.5		32.5	9.1		-45.9	0.000025	V	downlink
7760	-61.5	40.4		33.4	9.4		-45.0	0.000031	V	downlink
9700	-61.8	40.4		36.1	10.5		-47.0	0.000020	V	downlink
77640	-61.3	53.1		36.1	6.4		-38.0	0.000160	V	downlink / NF
13580	-61.5	47.6		34.2	10.4		-37.7	0.000171	V	downlink / NF
15520	-60.8	43.2		34.5	13.6		-38.5	0.000142	V	downlink / NF
17460	-62.3	47.0		34.9	11.7		-38.4	0.000143	V	downlink / NF
19400	-61.9	53.1		34.2	6.4		-36.7	0.000216	V	downlink / NF
3880	-59.3	34.3		33.3	8.0		-50.3	0.000009	H	downlink
5820	-61.2	36.0		32.5	9.1		-48.6	0.000014	H	downlink
7760	-60.3	39.8		33.4	9.4		-44.5	0.000036	H	downlink
9700	-60.5	42.6		36.1	10.5		-43.5	0.000045	H	downlink
77640	-61.2	54.6		36.1	6.4		-36.3	0.000237	H	downlink / NF
13580	-61.5	50.8		34.2	10.4		-34.5	0.000359	H	downlink / NF
15520	-61.9	44.0		34.5	13.6		-38.8	0.000132	H	downlink / NF
17460	-61.8	50.5		34.9	11.7		-34.5	0.000357	H	downlink / NF
19400	-60.9	54.6		34.2	6.4		-34.1	0.000393	H	downlink / NF
Notes: <u>downlink 1940 MHz / Scanned to the 10th harmonic</u>										

EQUIPMENT: Compact Bi Directional Amplifier

BROADBAND PCS REPEATERS
PROJECT NO.: 2L0288RUS1rev2

						Dallas Headquarters: 802 N. Kealy Lewisville, TX 75057 Tel: (972) 436-9600 Fax: (972) 436-2667				
Nemko Dallas, Inc.										
<u>Field Strength of Spurious Emissions</u>										
Page <u>1</u> of <u>1</u> Job No.: <u>210288r</u> Date: <u>5/24/2002</u> Specification: <u>2.1053</u> Temperature(°C): <u>21</u> Tested By: <u>Kevin Rose</u> Relative Humidity(%) <u>48</u> E.U.T.: <u>band C PCS CDMA repeater downlink</u> Configuration: <u>Tx Full Power</u> Sample No: <u>2039042</u> Location: <u>AC 3</u> RBW: <u>1 MHz</u> Measurement Detector Type: <u>Peak</u> VBW: <u>1 MHz</u> Distance: <u>3</u> m						Complete <u>X</u> Preliminary _____				
<u>Test Equipment Used</u> Antenna: <u>1304</u> Directional Coupler: _____ Pre-Amp: <u>1016</u> Cable #1: <u>1043</u> Filter: _____ Cable #2: <u>1484</u> Receiver: <u>1464</u> Cable #3: <u>1485</u> Attenuator #1: _____ Cable #4: _____ Attenuator #2: _____ Mixer: _____ Additional equipment used: _____ Measurement Uncertainty: <u>+/-3.6 dB</u>										
Frequency (MHz)	Meter Reading (dBm)	Correction Factor (dB)		Pre-Amp Gain (dB)	Substitution Antenna Gain (dBd)		ERP (dBm)	ERP (mW)	Polarity	Comments
3960	-61.5	40.4		33.3	8.0		-46.4	0.000023	V	Downlink
5940	-61.0	38.5		32.5	9.1		-45.9	0.000025	V	Downlink
7920	-61.8	40.4		33.4	9.4		-45.3	0.000029	V	Downlink
9900	-60.8	40.4		36.1	10.5		-46.0	0.000025	V	Downlink
11880	-60.2	-49.3		36.1	11.0		-134.6	0.000000	V	Downlink / NF
13860	-60.4	47.6		34.2	10.4		-36.6	0.000221	V	Downlink / NF
15840	-60.9	43.2		34.5	13.6		-38.6	0.000138	V	Downlink / NF
17820	-61.2	51.0		34.9	8.7		-36.4	0.000229	V	Downlink / NF
19800	-60.9	53.1		34.2	6.4		-35.7	0.000272	V	Downlink / NF
3960	-61.8	34.3		33.3	8.0		-52.8	0.000005	H	Downlink
5940	-61.0	36.0		32.5	9.1		-48.4	0.000014	H	Downlink
7920	-63.0	39.8		33.4	9.4		-47.2	0.000019	H	Downlink
9900	-61.8	42.6		36.1	10.5		-44.8	0.000033	H	Downlink
11880	-62.0	46.0		36.1	11.0		-41.1	0.000078	H	Downlink / NF
13860	-61.0	50.8		34.2	10.4		-34.0	0.000403	H	Downlink / NF
15840	-61.0	44.0		34.5	13.6		-37.9	0.000162	H	Downlink / NF
17820	-61.3	53.6		34.9	8.7		-33.9	0.000407	H	Downlink / NF
19800	-62.2	54.6		34.2	6.4		-35.4	0.000291	H	Downlink / NF
Notes: Downlink 1980 MHz / Scanned to the 10th harmonic										

EQUIPMENT: Compact Bi Directional Amplifier

BROADBAND PCS REPEATERS
PROJECT NO.: 2L0288RUS1rev2

						Dallas Headquarters: 802 N. Kealy Lewisville, TX 75057 Tel: (972) 436-9600 Fax: (972) 436-2667				
Nemko Dallas, Inc.										
<u>Field Strength of Spurious Emissions</u>										
Page <u>1</u> of <u>1</u>						Complete <u>X</u>				
Job No.: 210288r		Date: 5/24/2002				Preliminary _____				
Specification: 2.1053		Temperature(°C): <u>21</u>								
Tested By: Kevin Rose		Relative Humidity(%) <u>48</u>								
E.U.T.: band C PCS CDMA repeater uplink										
Configuration: Tx Full Power										
Sample No: 2039042										
Location: AC 3		RBW: 1 MHz		Measurement						
Detector Type: Peak		VBW: 1 MHz		Distance: <u>3</u> m						
<u>Test Equipment Used</u>										
Antenna: 1304		Directional Coupler: _____								
Pre-Amp: 1016		Cable #1: 1043								
Filter: _____		Cable #2: 1484								
Receiver: 1464		Cable #3: 1485								
Attenuator #1: _____		Cable #4: _____								
Attenuator #2: _____		Mixer: _____								
Additional equipment used: _____										
Measurement Uncertainty: <u>+/-3.6 dB</u>										
Frequency (MHz)	Meter Reading (dBm)	Correction Factor (dB)		Pre-Amp Gain (dB)	Substitution Antenna Gain (dBd)		ERP (dBm)	ERP (mW)	Polarity	Comments
3802	-58.7	40.4		33.3	8.0		-43.6	0.000043	V	uplink
5703	-63.5	38.5		32.5	9.1		-48.4	0.000014	V	uplink
7604	-63.0	40.4		33.4	9.4		-46.5	0.000022	V	uplink
9505	-60.1	40.4		36.1	10.5		-45.3	0.000030	V	uplink
1140.6	-61.2	31.5		36.1	4.8		-61.1	0.000001	V	uplink / NF
1330.7	-62.5	31.5		34.2	4.8		-60.5	0.000001	V	uplink / NF
1520.8	-60.9	29.9		34.5	6.4		-59.2	0.000001	V	uplink / NF
1710.9	-61.3	29.9		34.9	6.4		-60.0	0.000001	V	uplink / NF
1901	-61.6	29.9		34.2	6.4		-59.6	0.000001	V	uplink / NF
3802	-59.5	34.3		33.3	8.0		-50.5	0.000009	H	uplink
5703	-62.3	36.0		32.5	9.1		-49.7	0.000011	H	uplink
7604	-62.0	39.8		33.4	9.4		-46.2	0.000024	H	uplink
9505	-62.2	42.6		36.1	10.5		-45.2	0.000030	H	uplink
1140.6	-62.6	31.1		36.1	4.8		-62.9	0.000001	H	uplink / NF
1330.7	-61.3	31.1		34.2	4.8		-59.7	0.000001	H	uplink / NF
1520.8	-62.5	32.7		34.5	6.4		-58.0	0.000002	H	uplink / NF
1710.9	-61.8	32.7		34.9	6.4		-57.7	0.000002	H	uplink / NF
1901	-61.3	32.7		34.2	6.4		-56.5	0.000002	H	uplink / NF
Notes: <u>uplink 1901 MHz / Scanned to the 10th harmonic</u>										


EQUIPMENT: Compact Bi Directional Amplifier

Photographs of Test Setup

FRONT VIEW



REAR VIEW



Section 7. Frequency Stability

NAME OF TEST: Frequency Stability	PARA. NO.: 2.1055
TESTED BY:	DATE:

Test Results: Complies.

Measurement Data: See attached table
Standard Test Frequency: _____ MHz
Standard Test Voltage: _____

Equipment Used:

Measurement Uncertainty: +/- 1.6 dB

Lab Temperature: °C

Relative Humidity: %

Section 8. Test Equipment List

NEMKO	Description	Manufacturer	Model	Serial #	Cal. Date	Due Date
1464	Spectrum analyzer	Hewlett Packard	8563E	3551A04428	1/2/01	1/3/03
1604	ATTENUATOR	NARDA	776B-20	NONE	9/13/01	9/13/02
1043	Flexible cable 1m	Astrolab Inc.	32027-2-29094K-1M		1/18/02	1/18/03
1046	Flex cable 1m	Astrolab Inc.	32022-2-29094K-1M	N/A	1/18/02	1/18/03
1053	SIGNAL GENERATOR	ROHDE & SCHWARZ	SMIQ 03	DE22081	8/9/01	8/9/02
1052	I/Q MODULATION GENERATOR	Rhode & Schwarz	AMIQ	DE30619	9/25/00	9/27/03
1484	Cable 2.0-18.0 Ghz	Storm	PR90-010-072	N/A	6/1/01	6/1/02
1485	Cable 2.0-18.0 Ghz	Storm	PR90-010-216	N/A	6/1/01	6/1/02
1036	Spectrum analyzer	Rohde & Schwarz	FSEK30	830844/006	12/18/01	12/18/03

ANNEX A - TEST DETAILS

NAME OF TEST: RF Power Output**PARA. NO.: 2.1046**

Minimum Standard: Para. No.24.232. Base stations are limited to 1640 watts peak E.I.R.P. with an antenna height up to 300 meters HAAT. In no case may the peak output power of a base station transmitter exceed 100 watts.

Method Of Measurement:Detachable Antenna:

The peak power at antenna terminals is measured using an in-line peak power meter. Power output is measured with the maximum rated input level.

Integral Antenna:

If the antenna is not detachable from the circuit then the Peak Power Output is derived from the peak radiated field strength of the fundamental emission by using the plane wave relation $GP/4\pi R^2 = E^2/120\pi$ and proceeding as follows:

$$P = \frac{E^2 R^2}{30G} = \frac{E^2 3^2}{30G}$$

where,

P = the equivalent isotropic radiated power in watts

E = the maximum measured field strength in V/m

R = the measurement range (3 meters)

G = the numeric gain of the transmit antenna in relation to an isotropic radiator

NAME OF TEST: Occupied Bandwidth**PARA. NO.: 2.1047**

Minimum Standard: Para. No. 24.238(b). The emission bandwidth is defined as the width of the signal between two points, one below the carrier center frequency and one above the carrier center frequency, outside of which all emissions are attenuated at least 26 dB.

Method Of Measurement:**CDMA**

Spectrum analyzer settings:

RBW: 30 kHz

VBW: $\geq$ RBW

Span: 5 MHz

Sweep: Auto

Mask: Set markers to -26 dB from peak of CW.

GSM

RBW: 3 kHz

VBW: $\geq$ RBW

Span: 2 MHz

Sweep: Auto

Mask: Set markers to -26 dB from peak of CW.

NAME OF TEST: Spurious Emission at Antenna Terminals	PARA. NO.: 2.1051
---	--------------------------

Minimum Standard: Para. No.24.238 (a). On any frequency outside a licensee's frequency block, the power of any emission shall be attenuated below the transmitter power by at least $43 + 10 \log (P)$ dB.

Method Of Measurement:

Spectrum analyzer settings:

CDMA

RBW: 1 MHz (> 1 MHz from Band Edge)

RBW: 30 kHz (< 1MHz from Band Edge)

VBW: $\geq$ RBW

Sweep: Auto

Video Avg: 6 Sweeps

To demonstrate compliance at band edges the frequency of the input signal is set to the lowest and highest assigned channel and the center frequency of the spectrum analyzer is set to the upper and lower edges of the appropriate frequency block.

NAME OF TEST: Field Strength of Spurious Radiation**PARA. NO.: 2.1053**

Minimum Standard: Para. No.24.238(a). On any frequency outside a licensee's frequency block, the power of any emission shall be attenuated below the transmitter power by at least $43 + 10 \log (P)$ dB.

Calculation Of Field Strength Limit

An example of attenuation requirement of $43 + 10 \log P$ is equivalent to -13 dBm (5×10^{-5} Watts) at the antenna terminal. We determine the field strength limit by using the plane wave relation.

$$GP/4\pi R^2 = E^2/120\pi$$

For emissions ≤ 1 GHz:

$G = 1.64$ (Dipole Gain)

$P = 10^{-5}$ Watts (Maximum spurious output power)

$R = 3\text{m}$ (Measurement Distance)

$$E = \frac{\sqrt{30GP}}{R}$$

$$E = \frac{\sqrt{30 \times 1.64 \times 5 \times 10^{-5}}}{3} = 0.016533 \text{ V / m} = 84.4 \text{ dB}\mu\text{V / m}$$

For emissions > 1 GHz:

$G = 1$ (Isotropic Gain)

$P = 1 \times 10^{-5}$ Watts (Maximum spurious output power)

$R = 3\text{m}$ (Measurement Distance)

$$E = 84.4 - 20 \log \sqrt{1.64} = 82.3 \text{ dB}\mu\text{V / m} @ 3\text{m}$$

NAME OF TEST: Frequency Stability**PARA. NO.: 2.1055**

Minimum Standard: Para. No. 24.235. The frequency stability shall be sufficient to ensure that the fundamental emission stays within the authorized frequency block.

Method Of Measurement:Frequency Stability With Voltage Variation


The E.U.T. is placed in an environmental chamber and allowed to stabilize at +20 degrees Celsius for at least 15 minutes. The frequency counter and signal generator are phase locked with the same 10 MHz reference frequency by connecting the 10 MHz ref. out of the counter to the 10 MHz ref, in of the signal generator. With the voltage input to the E.U.T. set to 85% S.T.V., the frequency is measured in 30 second intervals for a period of 5 minutes. This procedure is repeated at 100% S.T.V. and 115% S.T.V.

Frequency Stability With Temperature Variation


The input voltage to the E.U.T. is set to S.T.V. and the temperature of the environmental chamber is varied in 10 degree steps from -30 degrees C to +50 degrees C. The E.U.T. is allowed to stabilize at each temperature and the frequency is measured in 30 second intervals for a period of 5 minutes.

ANNEX B - TEST DIAGRAMS



Para. No. 2.985 - R.F. Power Output




Para. No. 2.989 - Occupied Bandwidth



Para. No. 2.991 Spurious Emissions at Antenna Terminals



Para. No. 2.993 - Field Strength of Spurious Radiation



Para. No. 2.995 - Frequency Stability

