



FOUNTAIN TECHNOLOGIES, INC.

COMPLIANCE LABORATORY

50 Randolph Rd.  
Somerset, NJ 08873

Tel: (732) 560-9010  
Fax: (732) 560-9173

## ELECTROMAGNETIC EMISSION COMPLIANCE REPORT

of

TRANSMITTER  
MODEL: DRY SIGNAL  
FCC ID: OZ8DRYSIGNAL

May 15, 2000

This report concerns (check one): Original grant <input checked="" type="checkbox"/> Class II change <input type="checkbox"/>	
Equipment type: <u>TRANSMITTER</u>	
Deferred grant requested per 47 CF 0.457(d)(1)(ii)? yes <input type="checkbox"/> no <input checked="" type="checkbox"/>	
If yes, defer until: _____ (date)	
Company agrees to notify the Commission by _____ (date)	
of the intended date of announcement of the product so that the grant can be issued on that date.	
Transition Rules Request per 15.37? yes <input type="checkbox"/> no <input checked="" type="checkbox"/>	
If no, assumed Part 15, Subpart B for unintentional radiators - the new 47 CFR [10-1-90 Edition] provision.	
Report prepared for:	DRY 4 LIFE, INC.
Report prepared by:	Fountain Compliance Lab
Report number:	0048-2K0410-01T



The test result in this report IS supported and covered by the NVLAP accreditation

Table of Contents

Report Cover Page ..... 1

Table of Contents..... 2

Figures..... 3

1. GENERAL INFORMATION..... 4

    1.1 Verification of Compliance..... 4

    1.2 Equipment Modifications..... 5

    1.3 Product Information..... 6

    1.4 Test Methodology ..... 6

    1.5 Test Facility..... 6

    1.6 Test Equipment..... 6

    1.7 Statement of the Document Use..... 7

2. PRODUCT LABELING..... 8

3. SYSTEM TEST CONFIGURATION..... 9

    3.1 Justification..... 9

    3.2 Special Accessories..... 9

    3.3 Configuration of Tested System..... 9

4. SYSTEM SCHEMATICS ..... 12

5. RADIATED EMISSION DATA ..... 13

    5.1 Field Strength Calculation ..... 13

    5.2 Test Methods and Conditions ..... 13

    5.3 Test Data..... 13

    5.4 Occupied Bandwidth..... 14

6. PHOTOS OF TESTED EUT ..... 17

Figures

Figure 2.1 FCC ID Label ..... 8

Figure 2.2 Location of Label on Back of the EUT..... 8

Figure 3.1 Radiated Test Setup, Position 1 ..... 10

Figure 3.2 Radiated Test Setup, Position 2 ..... 10

Figure 3.3 Radiated Test Setup, Position 3 ..... 11

Figure 4.1 EUT Schematics ..... 12

Figure 5.1 Pulse Train Timing ..... 15

Figure 5.2 Occupied Bandwidth ..... 16

Figure 6.1 Front View ..... 18

Figure 6.2 Rear View ..... 19

Figure 6.3 Component Side ..... 20

# 1. GENERAL INFORMATION


## 1.1 Verification of Compliance

EUT: TRANSMITTER  
 Model: DRYSIGNAL  
 Applicant: DRY 4 LIFE, INC.  
 Test Type: FCC Part 15C CERTIFICATION  
 Result: PASS  
 Tested by: FOUNTAIN COMPLIANCE LABORATORY  
 Test Date: 05/12/00  
 Report Number: 0048-2K0410-01T

The above equipment was tested by Fountain Technologies, Inc. Compliance Laboratory for compliance with the requirement set forth in the FCC rules and regulations Part 15, subpart C. This said equipment in the configuration described in the report, shows the maximum emission levels emanating from equipment are within the compliance requirements.

The estimated uncertainty of the test result is given as following. The method of uncertainty calculation is provided in Fountain Compliance Lab. Doc. No. 0048-01-01.

	Prob. Dist.	Uncertainty(dB)	Uncertainty(dB)	Uncertainty(dB)
		30-1000MHz	1-6.5GHz	Conducted
Combined Std. Uncertainty $u_c$	norm.	$\pm 2.36$	$\pm 2.99$	$\pm 1.83$



Wei Li  
 Lab Manager  
 Fountain Compliance Lab  
 Fountain Technologies, Inc.

Date: May 15, 2000

## **1.2 Equipment Modifications**

N/A

### 1.3 Product Information

#### System Configuration

ITEM	DESCRIPTION	FCC ID	CABLE
Product	TRANSMITTER	OZ8DRYSIGNAL(1)	
Housing	PLASTICS		
Power Supply	DC BATTERY		
Clock/OSC Freq.	418 MHz		
Device Type	Periodic Operation		

(1) EUT submitted for grant.

### 1.4 Test Methodology

Radiated tests were performed according to the procedures in ANSI C63.4-1992 at an antenna to EUT distance of 3 meters.

### 1.5 Test Facility

The open area test site and conducted measurement facility used to collect the radiated and conducted data are located at 50 Randolph Road, Somerset, New Jersey. This site has been accepted by FCC to perform measurements under Part 15 or 18 in a letter dated May 19, 1997 (Refer to: 31040/PRV 1300F2). The NVLAP Lab code for accreditation of FCC EMC Test Method is: 200101-0.

### 1.6 Test Equipment

Manufacture	Model	Serial No.	Description	Last Cal dd/mm/yy	Cal Due dd/mm/yy
Hewlett-Packard	HP8546A	3625A00341	EMI Receiver	15/12/99	15/12/00
Fischer Custom	LISN-2	900-4-008	Line Impedance Stabilization Networks	20/05/99	20/05/00
Fischer Custom	LISN-2	900-4-009	Line Impedance Stabilization Networks	26/04/00	26/04/01
EMCO	3115	4945	Double Ridge Guide Horn Antenna	05/12/99	05/12/00
EMCO	3104C	4396	30-200MHz Biconical Antenna	02/05/00	02/05/01
EMCO	3146	3350	200-1000MHz Log-Periodic Antenna	02/05/00	02/05/01

All Test Equipment Used are Calibrated Traceable to NIST Standards.

### **1.7 Statement for the Document Use**

This report shall not be reproduced except in full, without the written approval of the laboratory. And this report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government.

## **2. PRODUCT LABELING**

**See attachment: fcclabel.jpg**

**Fig 2.1 FCC ID Label**

**Fig. 2.2 Location of Label**



### **3. SYSTEM TEST CONFIGURATION**

#### **3.1 Justification**

The system was configured for testing in a typical fashion (as a customer would normally use it). And its antenna was permanently attached to the EUT (Made on the PCB). Fresh batteries are used during the test in order to generate maxim emission from EUT.

This transmitter will deactivate within 5 seconds after activation.

#### **3.2 Special Accessories**

N/A

#### **3.3 Configuration of Tested System**

Figure 3.1 and Figure 3.3 illustrate this system, which is tested standing along.



**Figure 3.1 Radiated Test Setup, Position 1**



**Figure 3.2 Radiated Test Setup, Position 2**



**Figure 3.3 Radiated Test Setup, Position 3**

#### **4. SYSTEM SCHEMATICS**

See attachment: schematic.jpg & complist1.jpg, complist2.jpg

**Figure 4.1(a) (b) (c) System Schematics**

## 5. RADIATED EMISSION DATA

### 5.1 Field Strength Calculation

The corrected field strength is automatically calculated by EMI Receiver using following:

$$FS = RA - AF - CF - AG$$

where FS: Corrected Field Strength in dB $\mu$ V/m

RA: Amplitude of EMI Receiver before correction in dB $\mu$ V

AF: Antenna Factor in dB/m

CF: Cable Attenuation Factor in dB

AG: Built-in Preamplifier Gain in dB (Stored in receiver as part of the calibration data)

The pulse train timing plots are showed in Figure 5.1.

The pulse train timing plots as follows:

The total time for each pulse train is 48 ms, The short pulse is 0.25ms. The long pulse is 1.75ms.

$$\text{Coeff.} = (7 \times 1.75 + 11 \times 0.25) / 48 = 31.25\%$$

The maximum average field strength should be 0.3125 of the peak field strength measured. So we use peak value minus 10.1dB as calculated maximum average field strength.

### 5.2 Test Methods and Conditions


The EUT exercise program was loaded during the radiated emission test. The initial step in collecting radiated data is a EMI Receiver scan of the measurement range 30MHz - 5GHz using peak detector. IF bandwidth is 120kHz and video bandwidth is 300kHz for measuring 30MHz-1GHz. Both bandwidths are 1MHz for above 1GHz measurement.

### 5.3 Test Data

The following data lists the significant emission frequencies, polarity and position, peak reading of the EMI Receiver, calculated average reading, the FCC limit, and the difference between the peak reading and the limit. Explanation of the correction and calculation are given in section 5.1.

Test Personnel:

Tester Signature



Typed/Printed Name: David Tu

Date: May 15, 2000

## Radiated Test Data

Frequency (MHz)	Polarity [H or V], Position (X,Y,Z)	Height (m)	Azimuth (Degree)	Peak Reading (dBμV/m)	Calculated Average Reading (dBμV/m)	FCC 3m Limit (dBμV/m)	Difference from limit (dB)
418.0	H,X	1.0	045	69.4	59.3	80.3	-21
418.0	H,Y	2.1	045	64.2	54.1	80.3	-26.2
418.0	H,Z	1.2	180	66.3	56.2	80.3	-24.1
836.0	H,X	1.0	255	67.6	57.5	60.3	-2.8
836.0	H,Y	1.4	225	63.0	52.9	60.3	-7.4
836.0	H,Z	1.4	225	62.0	51.9	60.3	-8.4
1254.1	H,X	2.2	225	62.8	52.7	60.3	-7.6
1254.1	H,Y	1.0	85	65.4	55.3	60.3	-5
1254.1	H,Z	1.0	105	63.6	53.5	60.3	-6.8
1672.1	H,X	2.3	085	58.0	47.9	54.0	-6.1
1672.1	H,Y	1.0	180	60.1	50	54.0	-4
1672.1	H,Z	1.0	225	60.6	50.5	54.0	-3.5
418.0	V,X	1.1	200	61.7	51.6	80.3	-28.7
418.0	V,Y	1.6	180	70.7	60.6	80.3	-19.7
418.0	V,Z	1.5	225	71.2	61.1	80.3	-19.2
836.0	V,X	1.5	155	61.5	51.4	60.3	-8.9
836.0	V,Y	1.3	180	66.4	56.3	60.3	-4
836.0	V,Z	1.3	235	68.0	57.9	60.3	-2.4
1254.1	V,X	2.4	115	67.4	57.3	60.3	-3
1254.1	V,Y	2.4	135	66.9	56.8	60.3	-3.5
1254.1	V,Z	1.0	135	60.1	50.0	60.3	-9.7
1672.1	V,X	2.5	285	60.7	50.6	54.0	-3.4
1672.1	V,Y	1.4	105	60.7	50.6	54.0	-3.4
1672.1	V,Z	1.3	135	60.1	50	54.0	-4

- (1) See Figure 3.1, 3.2 and 3.3 for definition of position X-1, Y-2, Z-3.
- (2) Restricted band.
- (3) Fundamental limit is 3750-12500 microvolts/meter linear interpolations.
- (4) Spurious limit is 375-1250 microvolts/meter linear interpolations.

## 5.4 Occupied Bandwidth

The bandwidth of the emission shall be no wider than 0.25% of the center frequency, in this case, 1.045MHz(418 x 0.25%). Bandwidth is determined at the points 20dB down from the modulated carrier. Figure 5.1 shows the occupied bandwidth plot.

See attachment: Pulsetrn.jpg

### Figure 5.1 Pulse Train Timing

See attachment: ocupband.jpg

## Figure 5.2 Occupied Bandwidth



## **6. PHOTOS OF TESTED EUT**

The following photos show the inside details of the EUT.

See Attachments: front.jpg, rear.jpg, component.jpg