

FCC and ISCED Canada Radio Testing of the

Sensus Metering Systems Inc.
IDTB007

In accordance with FCC 47 CFR Part 24 Subpart D, Part 101 Subpart C and ISCED Canada's Radio Standards Specifications RSS-119, RSS-134

Prepared for: Sensus Metering Systems Inc.
639 Davis Drive
Morrisville, NC 27560

FCC ID: SDBIDTB007
IC: 2220A-IDTB007

COMMERCIAL-IN-CONFIDENCE

Document Number: TP0721006662.300 | Issue: 01

RESPONSIBLE FOR	NAME	DATE	SIGNATURE
Authorized Signatory	Dave Ernest	2025 -February-20	
Testing	Thierry Jean-Charles	2025-February-20	

Signatures in this approval box have checked this document in line with the requirements of TÜV SÜD Product Service document control rules.

FCC Accreditation
Designation Number US1063 Tampa, FL Test Laboratory
Innovation, Science, and Economic Development Canada
Accreditation
Site Number 2087A-2 Tampa, FL Test Laboratory

EXECUTIVE SUMMARY

Samples of this product were tested and found to be in compliance with FCC Part 24 Subpart D, Part 101 Subpart C and ISCED Canada's RSS-119, RSS-134.

 A2LA Cert. No. 2955.15	DISCLAIMER AND COPYRIGHT This non-binding report has been prepared by TÜV SÜD America with all reasonable skill and care. The document is confidential to the potential Client and TÜV SÜD America. No part of this document may be reproduced without the prior written approval of TÜV SÜD America. © TÜV SÜD.
	DISCLAIMER AND COPYRIGHT Our A2LA Accreditation does not cover opinions and interpretations and any expressed are outside the scope of our A2LA Accreditation. Results of test not covered by our A2LA Accreditation Schedule are marked NUA (Not A2LA Accredited).

TÜV SÜD America
5610 West Sligh Ave., Suite 100
Tampa, FL 33634

Phone: 813-284-2715
www.tuv-sud-america.com



America

Add value.
Inspire trust.

TÜV SÜD

TÜV®



Contents

1	Report Summary	3
1.1	Report Modification Record.....	3
1.2	Introduction.....	3
1.3	Brief Summary of Results	6
1.4	Product Information	7
1.5	Deviations from the Standard.....	12
1.6	EUT Modification Record	12
1.7	Test Location	12
2	Test Details	13
2.1	RF Power Output.....	13
2.2	Out of Band Unwanted Emissions	22
2.3	Occupied Bandwidth	67
2.4	Spurious Emissions at Antenna Terminals	98
2.5	Field Strength of Spurious Radiation	108
2.6	Frequency Stability.....	123
3	Test Equipment Information	134
3.1	General Test Equipment Used.....	134
4	Diagram of Test Set-ups	136
5	Measurement Uncertainty	141
6	Accreditation, Disclaimers and Copyright.....	142



1 Report Summary

1.1 Report Modification Record

Alterations and additions to this report will be issued to the holders of each copy in the form of a complete document.

Issue	Description of Change	Date of Issue
1	First Issue	2025-February-20

1.2 Introduction

The purpose of this report is to demonstrate compliance with the FCC's Code of Federal Regulations Part 24 Subpart D, Part 101 Subpart C and Innovation Science and Economic Development Canada's Radio Standards Specification RSS-119, RSS-134 for the tests documented herein.

The test covers an alternate FEM and TCXO (Epson) configuration for the EUT.



Applicant	Sensus Metering Systems Inc.
Manufacturer	Sensus Metering Systems Inc.
Applicant's Email Address	James.Francisco@xylem.com
Model Number(s)	IDTB007
Serial Number(s)	Radiated Spurious Emissions: 825512079174777; Epson TCXO 825512079174769; TXC TCXO RF Conducted Measurements: 825512079174736; Epson TCXO 825512079174759; TXC TCXO
FCC ID	SDBIDTB007
ISED Certification Number	2220A-IDTB007
Hardware Version(s)	Rev. F
Software Version(s)	F.C.20
Number of Samples Tested	4
Test Specification/Issue/Date	US Code of Federal Regulations (CFR): Title 47, Part 24, Subpart D: Personal Communications Services – 2024 US Code of Federal Regulations (CFR): Title 47, Part 101, Subpart C: Fixed Microwave Services -2024 Industry Canada Radio Standards Specification: RSS-119 - Land Mobile and Fixed Equipment Operating in the Frequency Range 27.41-960 MHz, Issue 12, May 2015, Amendment (April 1, 2022) Industry Canada Radio Standards Specification: RSS-134 - 900 MHz Narrowband Personal Communication Service, Issue 2, February 2016
Test Plan/Issue/Date	2024-November-13
Order Number	0721006662
Date	2024-December-19
Date of Receipt of EUT	2025-January-16
Start of Test	2025-January-17
Finish of Test	2025-February-07
Name of Engineer(s)	Thierry Jean-Charles
Related Document(s)	US Code of Federal Regulations (CFR): Title 47, Part 2, Subpart J: Equipment Authorization Procedures - 2025



Innovation, Science and Economic Development Canada
Radio Standards Specification: RSS-GEN - General
Requirements for Compliance of Radio Apparatus, Issue 5,
Amendment 1, March 2019

ANSI C63.26: 2015: American National Standard for
Compliance Testing of Transmitters Used in Licensed Radio
Services.



1.3 Brief Summary of Results

A brief summary of the tests carried out in accordance with 24 Subpart D, Part 101 Subpart C and ISSED Canada's RSS-119, RSS-134 is shown below.

Table 1.3-1: Test Result Summary

Test Parameter	Test Plan (Yes/No)	Test Results	FCC 47 CFR Rule Part	ISED Canada's RSS	Test Report Page No.
RF Power Output	Yes	Pass	2.1046; 24.132; 101.113(a)	RSS-Gen 6.12; RSS-119 5.4; RSS-134 4.3(a), (b)	13
Out of Band Unwanted Emissions	Yes	Pass	2.1051; 24.133 a(1), a(2); 101.111 a(5),a(6)	RSS-Gen 6.13; RSS-119 5.8.3, 5.8.6; RSS-134 4.4	22
Occupied Bandwidth	Yes	Pass	2.1049; 101.109	RSS-Gen 6.7	67
Spurious Emissions at Antenna Terminals	Yes	Pass	2.1051; 24.133 a(1), a(2); 101.111 a(5),a(6)	RSS-Gen 6.13; RSS-119 5.8.3, 5.8.6; RSS-134 4.4	98
Field Strength of Spurious Radiation	Yes	Pass	2.1053; 24.133 a(1), a(2); 101.111a(5),a(6)	RSS-Gen 6.13; RSS-119 5.8.3, 5.8.6; RSS-134 4.4	108
Frequency Stability	Yes	Pass	2.1055; 24.135; 101.107	RSS-Gen 6.11; RSS-119 5.3; RSS-134 4.5	123



1.4 Product Information

1.4.1 Technical Description

The equipment under test was the Stratus IQ+ Radio Module model IDTB007. The device is a transceiver module consisting of a standard FlexNet protocol with FEM controlled output capable of 1W nominal conducted output power. The modular design enables Sensus to locate the transceiver in several standard S form meters retailed to Utilities.

Technical Details


Mode of Operation	Flexnet Radio
Frequency Range:	901 - 960 MHz
Antenna Type/Gain:	Printed Monopole Antenna, 2 dBi
Input Power:	4.2 VDC

The IDTB007transmitters produce 14 distinct modulation formats. The emissions designators for the modulation types used by the IDTB007 transmitters are as follows:

EMISSIONS DESIGNATORS:

Normal Mode	9K60F2D (7-FSK)
Double Density Mode	9K60F2D (13-FSK)
C&I Mode (Half-Baud)	4K80F2D (7-FSK)
Priority	4K80F2D (13-FSK)
2SFSK (Half Baud)	5K00F1D (2-SFSK)
4SFSK (Half Baud)	5K60F1D (4-SFSK)
8SFSK (Half Baud)	5K90F1D (8-SFSK)
2SFSK	10K0F1D (2-SFSK)
4SFSK	11K3F1D (4-SFSK)
8SFSK	11K9F1D (8-SFSK)
MPass Mode (5 kbps)	5K90F1D (2-GFSK)
MPass Mode (10 kbps)	11K8F1D (2-GFSK)
M4Pass (10 kbps)	4K70F1D (4-GFSK)
M4Pass (20 kbps)	9K30F1D (4-GFSK)

A full description and detailed product specification details are available from the manufacturer.

**Table 1.4.1-1 – Cable Descriptions**

Cable/Port	Description
Power Leads	2.2 m, Not Shielded, EUT to DC Power Supply

Table 1.4.1-2 – Support Equipment Descriptions

Make/Model	Description
Lambda / LA-200	Regulated DC Power Supply, SN: LA2-AA20-45 0470



Declaration of Build Status

EQUIPMENT DESCRIPTION	
Model Name/Number	Stratus IQ+ Radio Module
Part Number	7002811250000
Hardware Version	Rev. F
Software Version	F.C.20
FCC ID (if applicable)	SDBIDTB007
ISED ID (if applicable)	2220A-IDTB007
Technical Description (Please provide a brief description of the intended use of the equipment)	Electric meter radio module.

UN-INTENTIONAL RADIATOR	
Highest frequency generated or used in the device or on which the device operates or tunes	3838.047MHz
Lowest frequency generated or used in the device or on which the device operates or tunes	32.768kHz
Class A Digital Device (Use in commercial, industrial or business environment) ☐	
Class B Digital Device (Use in residential environment only) ☒	

Power Source			
AC	Single Phase	Three Phase	Nominal Voltage
	☐	☐	
External DC	Nominal Voltage	Maximum Current	
	4.2V	1.2A	
Battery	Nominal Voltage	Battery Operating End Point Voltage	

EXTREME CONDITIONS			
Maximum temperature	+85	°C	Minimum temperature
			-40
			°C

Ancillaries
Please list all ancillaries which will be used with the device.
N/A

I hereby declare that the information supplied is correct and complete.

Name: James Francisco

Position held: Staff Regulatory Engineer Date: February 11, 2025



1.4.2 Modes of Operation

The tested mode of operation was the Flexnet radio in continuous transmit mode. The EUT was configured using the Sensus Flexnet Spotlight V2.2.1.0 software tool. The TX output power of the radio was not configurable.

1.4.3 Monitoring of Performance

The following performance attributes were monitored:

1. Transmitter Output Power
2. Transmitter Emissions Masks
3. Transmitter Occupied Bandwidth
4. Transmitter Spurious Emissions at the Antenna Port
5. Transmitter Radiated Spurious Emissions
6. Transmitter Frequency Stability over Temperature and Voltage

Samples with the TXC and Epson TCXO were provided for evaluation. Full testing was performed on one TCXO variant while spot check measurements were performed on the second variant as deemed applicable. The frequency stability measurements were performed on the sample with the new TCXO (Epson).

The EUT was configured with power leads for testing purposes. Preliminary radiated spurious measurements were performed for the EUT standalone in three orthogonal orientations. The final measurements were performed on the configuration leading to the highest emissions.

The RF conducted measurements were performed for the EUT configured with an RF connector at the antenna port to allow direct coupling to a spectrum analyzer. The EUT was placed inside of a fixture for programming purposes for the RF conducted measurements.

The EUT is designed to operate in multiple bands under the requirements of CFR 47 Parts 24 and 101. The following is a list of the frequency bands of operation sorted based on the FCC rule parts in which the band is associated.

CFR Title 47 Rule Part	ISED Canada RSS	Frequency Band of Operation (MHz)
24D	134	901.0 - 902.0
24D	134	930.0 - 931.0
24D	134	940.0 - 941.0
101	119	928.85 - 929.0
101	119	932.0 - 932.5
101	119	941.0 - 941.5
101	119	952.0 – 953.0
101	N/A	959.85 - 960.0



Based on the requirements set forth in accordance 47 CFR 2.1046-2.1057 as stated above, the methodology in selecting the places to test in the available bands of operation is outlined in the following table.

CFR Title 47 Rule Part	ISED Canada RSS	Frequency Band of Operation (MHz)	Location in the Range of Operation	Approx. Test Freq.
24D	134	901.0 - 902.0	Middle	901.5000
101	119	928.85 - 929.0	Middle	928.9250
24D	134	930.0 - 931.0	Middle	930.5000
101	119	932.0 - 932.5	Middle	932.2500
24D	134	940.0 - 941.0	1 near top and 1 near bottom	940.0125
101	119	941.0 - 941.5		941.4875
101	119	952.0 – 953.0	Middle	952.5
101	N/A	959.85 – 960.0	Middle	959.9250

1.4.4 Performance Criteria

The parameters evaluated are summarized below.

Table 1.4.4-1 - Performance Criteria

Parameter	Requirement
RF Output Power	FCC 47 CFR Part 2.1046; 24.132; 101.113(a) ISED Canada RSS-119 5.4; RSS-134 4.3(a),(b)
Out-of-Band Unwanted Emissions	FCC 47 CFR Parts: 2.1051; 24.133 a(1), a(2); 101.111a(5), a(6) ISED Canada RSS-119 5.8.3, 5.8.6; RSS-134 4.4
Occupied Bandwidth	ISED Canada RSS-GEN 6.7
Unwanted Emissions at the Antenna Terminal	FCC 47 CFR Parts: 2.1051; 24.133 a(1), a(2); 101.111 a(5),a(6) ISED Canada RSS-119 5.8.3, 5.8.6; RSS-134 4.4
Radiated Spurious Emissions	FCC 47 CFR Parts: 2.1053; 24.133 a(1), a(2); 101.111 a(5), a(6) ISED Canada RSS-119 5.8.3, 5.8.6; RSS-134 4.4
Frequency Stability	FCC Parts: 2.1055; 24.135, 101.107 ISED Canada RSS-119 5.3, RSS-134 4.5



1.5 Deviations from the Standard

No deviations from the applicable test standard were made during testing.

1.6 EUT Modification Record

The table below details modifications made to the EUT during the test program. The modifications incorporated during each test are recorded on the appropriate test pages.

Modification State	Description of Modification still fitted to EUT	Modification Fitted By	Date Modification Fitted
None			

1.7 Test Location

TÜV SÜD Product Service conducted the following tests at our Tampa FL Test Laboratory.

Test Name	Name of Engineer(s)	Accreditation
DC Powered, Operating		
RF Power Output	Thierry Jean-Charles	A2LA
Out of Band Emissions	Thierry Jean-Charles	A2LA
Occupied Bandwidth	Thierry Jean-Charles	A2LA
Spurious Emissions at the Antenna Terminal	Thierry Jean-Charles	A2LA
Field Strength of Spurious Radiation	Thierry Jean-Charles	A2LA
Frequency Stability	Thierry Jean-Charles	A2LA

Office Address:

TÜV SÜD America, Inc.
5610 W. Sligh Ave, Suite 100
Tampa, FL 33634
USA



2 Test Details

2.1 RF Power Output

2.1.1 Specification Reference

FCC 47 CFR Part 2.1046; 24.132; 101.113(a)
ISED Canada RSS-119 5.4; RSS-134 4.3(a),(b)

2.1.2 Equipment Under Test and Modification State

825512079174736; Epson TCXO
825512079174759; TXC TCXO

2.1.3 Date of Test

2025-February-03 to 2025-February-05

2.1.4 Test Method

The RF output of the equipment under test was directly connected to the input of the Spectrum Analyzer through 30 dB of passive attenuation. The resolution and video bandwidths of the spectrum analyzer were set at sufficient levels, >> signal bandwidth.

2.1.5 Environmental Conditions

Ambient Temperature	25.7 °C
Relative Humidity	34.1 %
Atmospheric Pressure	1020.5 mbar



2.1.6 Test Results

Table 2.1.6-1 – FCC Part 24.132 Limits

Station Type	Frequency Range (MHz)	E.R.P. Limits (Watts)	E.R.P. Limits (dBm)
Stations	901 - 902	7	38.45
Mobile Stations	930 – 931 940 – 941	7	38.45
Base Stations	930 – 931 940 – 941	3500	65.44

Table 2.1.6-2 – FCC Part 101.113 Limits

Frequency Range (MHz)	E.I.R.P. Limits Fixed (dBW)	E.I.R.P. Limits Mobile (dBW)
928 - 929	17	
932 – 932.5	17	
941 – 941.5	30	14
952 - 960	40	14

FCC 47 CFR Part 2.1046; 24.132; ISD Canada RSS-134 4.3(a),(b)

IDTB007 - Epson TCXO

Table 2.1.6-3 - RF Output Power – Epson TCXO – FCC 47 CFR Part 24.132; ISD Canada RSS-134 4.3

Frequency MHz	Power (dBm)	Antenna Gain (dBi)	ERP (dBm)	Limit (dBm)	Margin (dB)
901.5	30.08	2	29.93	38.45	8.52




Figure 2.1.6-1 - RF Output Power – Epson TCXO – 901.5 MHz



IDTB007 - TXC TCXO

Table 2.1.6-4 - RF Output Power – TXC TCXO – FCC 47 CFR Part 24.132; ISED Canada RSS-134 4.3

Frequency MHz	Power (dBm)	Antenna Gain (dBi)	ERP (dBm)	Limit (dBm)	Margin (dB)
901.5	30.15	2	30.00	38.45	8.45
930.5	30.13	2	29.98	38.45	8.47
940.0124	30.07	2	29.92	38.45	8.53




Figure 2.1.6-2 - RF Output Power – TXC TCXO – 901.5 MHz




Figure 2.1.6-3 - RF Output Power – TXC TCXO – 930.5 MHz




Figure 2.1.6-4 - RF Output Power – TXC TCXO – 940.0125 MHz



FCC 47 CFR Part 2.1046; 101.113(a); ISED Canada RSS-119 5.4

Table 2.1.6-5 - RF Output Power – TXC TCXO – FCC 47 CFR Part 101.113(a); ISED Canada RSS-119 5.4

Frequency MHz	Power (dBm)	Antenna Gain (dBi)	EIRP (dBm)	Limit (dBm)	Margin (dB)
928.925	30.16	2	32.16	47	14.84
932.25	30.13	2	32.13	47	14.87
941.4875	29.96	2	31.96	44	12.04
952.5	29.92	2	31.92	44	12.08
959.925	29.94	2	31.94	44	12.06




Figure 2.1.6-5 - RF Output Power – TXC TCXO – 928.925 MHz




Figure 2.1.6-6 - RF Output Power – TXC TCXO – 932.25 MHz




Figure 2.1.6-7 - RF Output Power – TXC TCXO – 941.4875 MHz




Figure 2.1.6-8 - RF Output Power – TXC TCXO – 952.5 MHz




Figure 2.1.6-9 - RF Output Power – TXC TCXO – 959.925 MHz



2.1.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Digital MultiMeter	Fluke	115	BEMC02108	N/A	12	15-Jan-2026
Duratest 175 Cable 26.5GHz	Teledyne Storm Products	921-0101-036	BEMC02112	N/A	12	18-Oct-2025
Signal & Spectrum Analyzer	Rohde & Schwarz	FSW43	DEMC3085	2.90 SP1	12	03-Jun-2025
DC Power Supply	Xantrex	HPD-60-5	TAME01064	N/A	N/A	NCR
30 dB Fixed Attenuator	Mini-Circuits	BW-S30W5+	TEMC00264	N/A	12	06-Apr-2025

TU - Traceability Unscheduled

O/P MON – Output Monitored with Calibrated Equipment

N/A - Not Applicable

NCR – No Calibration Required

2.2 Out of Band Unwanted Emissions

2.2.1 Specification Reference

FCC 47 CFR Parts: 2.1051; 24.133 a(1), a(2); 101.111 a(5), a(6)
ISED Canada RSS-119 5.8.3, 5.8.6; RSS-134 4.4

2.2.2 Equipment Under Test and Modification State

825512079174759; TXC TCXO

2.2.3 Date of Test

2025-February-04 to 2025-February-05

2.2.4 Test Method

The RF output of the equipment under test was directly connected to the input of the Spectrum Analyzer through a 30 dB passive attenuator. The spectrum analyzer resolution and video bandwidths were set to 300 Hz and 3000 Hz, respectively. The internal correction factors of the spectrum analyzer were employed to correct any cable or attenuator losses. Results of the test are shown below for all modes of operation.

2.2.5 Environmental Conditions

Ambient Temperature	25.7 °C
Relative Humidity	34.1 %
Atmospheric Pressure	1020.5 mbar

2.2.6 Test Results

DC Powered Operating

FCC 47 CFR Parts: 2.1051; 24.133 a(1), a(2); ISED Canada RSS-134 4.4




Figure 2.2.6-1 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- Normal Mode




Figure 2.2.6-2 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- Double Density Mode




Figure 2.2.6-3 - Emissions Mask – TXC TCXO – 901.5 MHz - 12.5 kHz Channel Spacing - C&I Mode




Figure 2.2.6-4 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- C&I Mode




Figure 2.2.6-5 - Emissions Mask – TXC TCXO – 901.5 MHz - 12.5 kHz Channel Spacing - Priority Mode




Figure 2.2.6-6 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- Priority Mode




Figure 2.2.6-7 - Emissions Mask – TXC TCXO – 901.5 MHz - 12.5 kHz Channel Spacing - 2SFSK (Half Baud) Mode




Figure 2.2.6-8 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- 2SFSK (Half Baud) Mode




Figure 2.2.6-9 - Emissions Mask – TXC TCXO – 901.5 MHz - 12.5 kHz Channel Spacing - 4FSK (Half Baud) Mode




Figure 2.2.6-10 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- 4FSK (Half Baud) Mode




Figure 2.2.6-11 - Emissions Mask – TXC TCXO – 901.5 MHz - 12.5 kHz Channel Spacing - 8FSK (Half Baud) Mode




Figure 2.2.6-12 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- 8FSK (Half Baud) Mode




Figure 2.2.6-13 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- 2FSK Mode




Figure 2.2.6-14 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- 4FSK Mode




Figure 2.2.6-15 - Emissions Mask – TXC TCXO – 901.5 MHz - 25 kHz Channel Spacing- 8FSK Mode




Figure 2.2.6-16 - Emissions Mask – TXC TCXO – 930.5 MHz - 12.5 kHz Channel Spacing- mPass5k Mode




Figure 2.2.6-17 - Emissions Mask – TXC TCXO – 930.5 MHz - 25 kHz Channel Spacing- mPass5k Mode




Figure 2.2.6-18 - Emissions Mask – TXC TCXO – 930.5 MHz - 25 kHz Channel Spacing-
mPass10k Mode




Figure 2.2.6-19 - Emissions Mask – TXC TCXO – 930.5 MHz - 12.5 kHz Channel Spacing-
m4Pass10 Mode




Figure 2.2.6-20 - Emissions Mask – TxC TCXO – 930.5 MHz - 25 kHz Channel Spacing-
m4Pass10 Mode




Figure 2.2.6-21 - Emissions Mask – TxC TCXO – 930.5 MHz - 25 kHz Channel Spacing-
m4Pass20k Mode




Figure 2.2.6-22 - Emissions Mask – TXC TCXO – 940.0125 MHz - 12.5 kHz Channel Spacing-
mPass5k Mode




Figure 2.2.6-23 - Emissions Mask – TXC TCXO – 940.0125 MHz - 25 kHz Channel Spacing-
mPass5k Mode




Figure 2.2.6-24 - Emissions Mask – TXC TCXO – 940.0125 MHz - 25 kHz Channel Spacing-
mPass10k Mode




Figure 2.2.6-25 - Emissions Mask – TXC TCXO – 940.0125 MHz - 12.5 kHz Channel Spacing-
m4Pass10 Mode




Figure 2.2.6-26 - Emissions Mask – TXC TCXO – 940.0125 MHz - 25 kHz Channel Spacing-
m4Pass10 Mode




Figure 2.2.6-27 - Emissions Mask – TXC TCXO – 940.0125 MHz - 25 kHz Channel Spacing-
m4Pass20k Mode

FCC 47 CFR Parts: 2.1051; 101.111 a(5), a(6); ISED Canada RSS-119 5.8.6




Figure 2.2.6-28 - Emissions Mask – TxC TCXO – 928.925 MHz - 25 kHz Channel Spacing- Normal Mode




Figure 2.2.6-29 - Emissions Mask – TxC TCXO – 928.925 MHz - 25 kHz Channel Spacing- Double Density Mode




Figure 2.2.6-30 - Emissions Mask – TXC TCXO – 928.925 MHz - 25 kHz Channel Spacing- C&I Mode




Figure 2.2.6-31 - Emissions Mask – TXC TCXO – 928.925 MHz - 25 kHz Channel Spacing- Priority Mode




Figure 2.2.6-32 - Emissions Mask – TxC TCXO – 928.925 MHz - 12.5 kHz Channel Spacing - 2SFSK (Half Baud) Mode




Figure 2.2.6-33 - Emissions Mask – TxC TCXO – 928.925 MHz - 25 kHz Channel Spacing- 2SFSK (Half Baud) Mode




Figure 2.2.6-34 - Emissions Mask – TxC TCXO – 928.925 MHz - 12.5 kHz Channel Spacing - 4FSK (Half Baud) Mode




Figure 2.2.6-35 - Emissions Mask – TxC TCXO – 928.925 MHz - 25 kHz Channel Spacing- 4FSK (Half Baud) Mode




Figure 2.2.6-36 - Emissions Mask – TXC TCXO – 928.925 MHz - 12.5 kHz Channel Spacing - 8FSK (Half Baud) Mode




Figure 2.2.6-37 - Emissions Mask – TXC TCXO – 928.925 MHz - 25 kHz Channel Spacing- 8FSK (Half Baud) Mode




Figure 2.2.6-38 - Emissions Mask – TXC TCXO – 928.925 MHz - 25 kHz Channel Spacing- 2FSK Mode




Figure 2.2.6-39 - Emissions Mask – TXC TCXO – 928.925 MHz - 25 kHz Channel Spacing- 4FSK Mode




Figure 2.2.6-40 - Emissions Mask – TXC TCXO – 928.925 MHz - 25 kHz Channel Spacing- 8FSK Mode




Figure 2.2.6-41 - Emissions Mask – TXC TCXO – 932.25 MHz - 25 kHz Channel Spacing- Normal Mode




Figure 2.2.6-42 - Emissions Mask – TXC TCXO – 932.25 MHz - 25 kHz Channel Spacing- Double Density Mode




Figure 2.2.6-43 - Emissions Mask – TxC TCXO – 932.25 MHz - 25 kHz Channel Spacing- C&I Mode




Figure 2.2.6-44 - Emissions Mask – TxC TCXO – 932.25 MHz - 25 kHz Channel Spacing- Priority Mode




Figure 2.2.6-45 - Emissions Mask – TXC TCXO – 932.25 MHz - 12.5 kHz Channel Spacing - 2SFSK (Half Baud) Mode




Figure 2.2.6-46 - Emissions Mask – TXC TCXO – 932.25 MHz - 25 kHz Channel Spacing- 2SFSK (Half Baud) Mode




Figure 2.2.6-47 - Emissions Mask – TXC TCXO – 932.25 MHz - 12.5 kHz Channel Spacing - 4FSK (Half Baud) Mode




Figure 2.2.6-48 - Emissions Mask – TXC TCXO – 932.25 MHz - 25 kHz Channel Spacing- 4FSK (Half Baud) Mode




Figure 2.2.6-49 - Emissions Mask – TXC TCXO – 932.25 MHz - 12.5 kHz Channel Spacing - 8FSFSK (Half Baud) Mode






Figure 2.2.6-50 - Emissions Mask – TXC TCXO – 932.25 MHz - 25 kHz Channel Spacing- 8FSFSK (Half Baud) Mode






Figure 2.2.6-53 - Emissions Mask – TXC TCXO – 932.25 MHz - 25 kHz Channel Spacing- 8SFSK Mode






Figure 2.2.6-54 - Emissions Mask – TXC TCXO – 941.4875 MHz - 12.5 kHz Channel Spacing - mPass5k Mode






Figure 2.2.6-57 - Emissions Mask – TXC TCXO – 941.4875 MHz - 12.5 kHz Channel Spacing - m4Pass10 Mode




Figure 2.2.6-58 - Emissions Mask – TXC TCXO – 941.4875 MHz - 25 kHz Channel Spacing - m4Pass10 Mode




Figure 2.2.6-59 - Emissions Mask – TXC TCXO – 941.4875 MHz - 25 kHz Channel Spacing - m4Pass20k Mode






Figure 2.2.6-60 - Emissions Mask – TXC TCXO – 952.5 MHz - 12.5 kHz Channel Spacing - mPass5k Mode






Figure 2.2.6-63 - Emissions Mask – TXC TCXO – 952.5 MHz - 12.5 kHz Channel Spacing - m4Pass10 Mode






Figure 2.2.6-64 - Emissions Mask – TXC TCXO – 952.5 MHz - 25 kHz Channel Spacing - m4Pass10 Mode






Figure 2.2.6-67 - Emissions Mask – TxC TCXO – 959.925 MHz - 25 kHz Channel Spacing-
mPass5k Mode




Figure 2.2.6-68 - Emissions Mask – TxC TCXO – 959.925 MHz - 25 kHz Channel Spacing-
mPass10k Mode




Figure 2.2.6-69 - Emissions Mask – TxC TCXO – 959.925 MHz - 12.5 kHz Channel Spacing - m4Pass10 Mode





Figure 2.2.6-70 - Emissions Mask – TxC TCXO – 959.925 MHz - 25 kHz Channel Spacing- m4Pass10 Mode



ISED Canada RSS-119 5.8.3




Figure 2.2.6-72 - Emissions Mask – TXC TCXO – 928.925 MHz - 12.5 kHz Channel Spacing - 2FSK (Half Baud) Mode




Figure 2.2.6-73 - Emissions Mask – TXC TCXO – 928.925 MHz - 12.5 kHz Channel Spacing - 4FSK (Half Baud) Mode




Figure 2.2.6-74 - Emissions Mask – TxC TCXO – 928.925 MHz - 12.5 kHz Channel Spacing - 8FSK (Half Baud) Mode




Figure 2.2.6-75 - Emissions Mask – TxC TCXO – 932.25 MHz - 12.5 kHz Channel Spacing - 2FSK (Half Baud) Mode




Figure 2.2.6-76 - Emissions Mask – TXC TCXO – 932.25 MHz - 12.5 kHz Channel Spacing - 4FSK (Half Baud) Mode




Figure 2.2.6-77 - Emissions Mask – TXC TCXO – 932.25 MHz - 12.5 kHz Channel Spacing - 8FSK (Half Baud) Mode




Figure 2.2.6-78 - Emissions Mask – TxC TCXO – 941.4875 MHz - 12.5 kHz Channel Spacing - mPass5k Mode




Figure 2.2.6-79 - Emissions Mask – TxC TCXO – 941.4875 MHz - 12.5 kHz Channel Spacing - m4Pass10 Mode




Figure 2.2.6-80 - Emissions Mask – TxC TCXO – 952.5 MHz - 12.5 kHz Channel Spacing - mPass5k Mode




Figure 2.2.6-81 - Emissions Mask – TxC TCXO – 952.5 MHz - 12.5 kHz Channel Spacing - m4Pass10 Mode




Figure 2.2.6-82 - Emissions Mask – TxC TCXO – 959.925 MHz - 12.5 kHz Channel Spacing - mPass5k Mode




Figure 2.2.6-83 - Emissions Mask – TxC TCXO – 959.925 MHz - 12.5 kHz Channel Spacing - m4Pass10 Mode



2.2.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Digital MultiMeter	Fluke	115	BEMC02108	N/A	12	15-Jan-2026
Duratest 175 Cable 26.5GHz	Teledyne Storm Products	921-0101-036	BEMC02112	N/A	12	18-Oct-2025
Signal & Spectrum Analyzer	Rohde & Schwarz	FSW43	DEMC3085	2.90 SP1	12	03-Jun-2025
DC Power Supply	Xantrex	HPD-60-5	TAME01064	N/A	N/A	NCR
30 dB Fixed Attenuator	Mini-Circuits	BW-S30W5+	TEMC00264	N/A	12	06-Apr-2025

TU - Traceability Unscheduled

O/P MON – Output Monitored with Calibrated Equipment

N/A - Not Applicable

NCR – No Calibration Required

2.3 Occupied Bandwidth

2.3.1 Specification Reference

FCC Section 2.1049; ISSED Canada RSS-GEN 6.7

2.3.2 Equipment Under Test and Modification State

825512079174759; TXC TCXO

2.3.3 Date of Test

2025-February-03 to 2025-February-05

2.3.4 Test Method

The RF output of the equipment under test was directly connected to the input of the Spectrum Analyzer through suitable of passive attenuation. The internal correction factors of the spectrum analyzer were employed to correct for any cable and attenuator losses.

The spectrum analyzer center frequency is set to the nominal EUT channel center frequency. The frequency span for the spectrum analyzer shall be set wide enough to capture all modulation products including the emission skirts. The nominal IF filter 3 dB bandwidth (RBW) is in the range of 1% to 5% of the OBW, and the VBW was set $\geq 3 \times$ RBW. The reference level was set to prevent the signal amplitude from exceeding the maximum spectrum analyzer input mixer level for linear operation. The measurements were made using the spectrum analyzer's 99% BW function.

2.3.5 Environmental Conditions

Ambient Temperature	25.7 °C
Relative Humidity	34.1 %
Atmospheric Pressure	1020.5 mbar

2.3.6 Test Results

FCC 47 CFR Parts: 2.1049; 24.133 a(1), a(2); ISED Canada RSS-134 4.4

Table 2.3.6-1 - 99% Bandwidth – TXC TCXO – 901.5 MHz

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
901.5	RSS-134	Normal	11.7259
901.5	RSS-134	Double Density	13.6054
901.5	RSS-134	C&I	6.0920
901.5	RSS-134	Priority	6.8999
901.5	RSS-134	2-SFSK-HB	5.9372
901.5	RSS-134	4 SFSK-HB	6.9723
901.5	RSS-134	8 SFSK-HB	7.3355
901.5	RSS-134	2-SFSK	11.8916
901.5	RSS-134	4-SFSK	13.8970
901.5	RSS-134	8-SFSK	14.6702




Figure 2.3.6-1 - 99% Bandwidth – TXC TCXO – 901.5 MHz - Normal Mode




Figure 2.3.6-2 - 99% Bandwidth – TXC TCXO – 901.5 MHz - Double Density Mode




Figure 2.3.6-3 - 99% Bandwidth – TXC TCXO – 901.5 MHz - C&I Mode




Figure 2.3.6-4 - 99% Bandwidth – TXC TCXO – 901.5 MHz - Priority Mode




Figure 2.3.6-5 - 99% Bandwidth – TXC TCXO – 901.5 MHz - 2FSK (Half Baud) Mode




Figure 2.3.6-6 - 99% Bandwidth – TXC TCXO – 901.5 MHz - 4FSK (Half Baud) Mode




Figure 2.3.6-7 - 99% Bandwidth – TXC TCXO – 901.5 MHz - 8FSK (Half Baud) Mode




Figure 2.3.6-8 - 99% Bandwidth – TXC TCXO – 901.5 MHz - 2FSK Mode




Figure 2.3.6-9 - 99% Bandwidth – TXC TCXO – 901.5 MHz - 4FSK Mode




Figure 2.3.6-10 - 99% Bandwidth – TXC TCXO – 901.5 MHz - 8SFSK Mode

Table 2.3.6-2 - 99% Bandwidth – TXC TCXO – 928.925 MHz

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
928.925	RSS-119	Normal	11.825
928.925	RSS-119	Double Density	13.383
928.925	RSS-119	C&I	6.073
928.925	RSS-119	Priority	6.880
928.925	RSS-119	2-SFSK-HB	5.943
928.925	RSS-119	4-SFSK-HB	6.973
928.925	RSS-119	8-SFSK-HB	7.239
928.925	RSS-119	2-SFSK	11.800
928.925	RSS-119	4-SFSK	14.009
928.925	RSS-119	8-SFSK	14.489




Figure 2.3.6-11 - 99% Bandwidth – TXC TCXO – 928.925 MHz - Normal Mode




Figure 2.3.6-12 - 99% Bandwidth – TXC TCXO – 928.925 MHz - Double Density Mode




Figure 2.3.6-13 - 99% Bandwidth – TXC TCXO – 928.925 MHz - C&I Mode




Figure 2.3.6-14 - 99% Bandwidth – TXC TCXO – 928.925 MHz - Priority Mode




Figure 2.3.6-15 - 99% Bandwidth – TXC TCXO – 928.925 MHz - 2FSK (Half Baud) Mode




Figure 2.3.6-16 - 99% Bandwidth – TXC TCXO – 928.925 MHz - 4FSK (Half Baud) Mode




Figure 2.3.6-17 - 99% Bandwidth – TXC TCXO – 928.925 MHz - 8FSK (Half Baud) Mode




Figure 2.3.6-18 - 99% Bandwidth – TXC TCXO – 928.925 MHz - 2FSK Mode




Figure 2.3.6-19 - 99% Bandwidth – TXC TCXO – 928.925 MHz - 4FSK Mode




Figure 2.3.6-20 - 99% Bandwidth – TXC TCXO – 928.925 MHz - 8FSK Mode



Table 2.3.6-3 - 99% Bandwidth – TXC TCXO – 930.5 MHz

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
930.5	RSS-134	mPass5K	5.861
930.5	RSS-134	mPass10k	11.828
930.5	RSS-134	m4Pass10k	6.133
930.5	RSS-134	m4Pass20k	12.032




Figure 2.3.6-21 - 99% Bandwidth – TXC TCXO – 930.5 MHz - mPass5k Mode




Figure 2.3.6-22 - 99% Bandwidth – TXC TCXO – 930.5 MHz - mPass10k Mode




Figure 2.3.6-23 - 99% Bandwidth – TXC TCXO – 930.5 MHz - m4Pass10 Mode




Figure 2.3.6-24 - 99% Bandwidth – TxC TCXO – 930.5 MHz - m4Pass20k Mode

Table 2.3.6-4 - 99% Bandwidth – TxC TCXO – 932.25 MHz

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
932.25	RSS-119	Normal	11.619
932.25	RSS-119	DD	13.269
932.25	RSS-119	C&I	6.153
932.25	RSS-119	Priority	6.764
932.25	RSS-119	2SFSK-HB	5.957
932.25	RSS-119	4SFSK-HB	6.970
932.25	RSS-119	8SFSK-HB	7.239
932.25	RSS-119	2SFSK	11.791
932.25	RSS-119	4SFSK	13.793
932.25	RSS-119	8SFSK	14.500




Figure 2.3.6-25 - 99% Bandwidth – TXC TCXO – 932.25 MHz - Normal Mode




Figure 2.3.6-26 - 99% Bandwidth – TXC TCXO – 932.25 MHz - Double Density Mode




Figure 2.3.6-27 - 99% Bandwidth – TXC TCXO – 932.25 MHz - C&I Mode




Figure 2.3.6-28 - 99% Bandwidth – TXC TCXO – 932.25 MHz - Priority Mode




Figure 2.3.6-29 - 99% Bandwidth – TXC TCXO – 932.25 MHz - 2SFSK (Half Baud) Mode




Figure 2.3.6-30 - 99% Bandwidth – TXC TCXO – 932.25 MHz - 4SFSK (Half Baud) Mode




Figure 2.3.6-31 - 99% Bandwidth – TXC TCXO – 932.25 MHz - 8FSK (Half Baud) Mode



Figure 2.3.6-32 - 99% Bandwidth – TXC TCXO – 932.25 MHz - 2FSK Mode




Figure 2.3.6-33 - 99% Bandwidth – TXC TCXO – 932.25 MHz - 4FSK Mode





Figure 2.3.6-34 - 99% Bandwidth – TXC TCXO – 932.25 MHz - 8FSK Mode

**Table 2.3.6-5 - 99% Bandwidth – TXC TCXO – 940.0125 MHz**

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
940.0125	RSS-134	mPass5k	5.797
940.0125	RSS-134	mPass10k	11.703
940.0125	RSS-134	m4Pass10k	6.074
940.0125	RSS-134	m4Pass20k	11.940

**Figure 2.3.6-35 - 99% Bandwidth – TXC TCXO – 940.0125 MHz - mPass5k Mode**




Figure 2.3.6-36 - 99% Bandwidth – TxC TCXO – 940.0125 MHz - mPass10k Mode




Figure 2.3.6-37 - 99% Bandwidth – TxC TCXO – 940.0125 MHz - m4Pass10 Mode




Figure 2.3.6-38 - 99% Bandwidth – TXC TCXO – 940.0125 MHz - m4Pass20k Mode

Table 2.3.6-6 - 99% Bandwidth – TXC TCXO – 941.4875 MHz

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
941.4875	RSS-119	mPass5k	5.801
941.4875	RSS-119	mPass10k	11.703
941.4875	RSS-119	m4Pass10k	6.000
941.4875	RSS-119	m4Pass20k	12.161




Figure 2.3.6-39 - 99% Bandwidth – TxC TCXO – 941.4875 MHz - mPass5k Mode




Figure 2.3.6-40 - 99% Bandwidth – TxC TCXO – 941.4875 MHz - mPass10k Mode




Figure 2.3.6-41 - 99% Bandwidth – TxC TCXO – 941.4875 MHz - m4Pass10 Mode





Figure 2.3.6-42 - 99% Bandwidth – TxC TCXO – 941.4875 MHz - m4Pass20k Mode

Table 2.3.6-7 - 99% Bandwidth – TXC TCXO – 952.5 MHz

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
952.5	RSS-119	mPass5k	5.798
952.5	RSS-119	mPass10k	11.731
952.5	RSS-119	m4Pass10k	5.972
952.5	RSS-119	m4Pass20k	12.017

**Figure 2.3.6-43 - 99% Bandwidth – TXC TCXO – 952.5 MHz - mPass5k Mode**




Figure 2.3.6-44 - 99% Bandwidth – TXC TCXO – 952.5 MHz - mPass10k Mode




Figure 2.3.6-45 - 99% Bandwidth – TXC TCXO – 952.5 MHz - m4Pass10 Mode




Figure 2.3.6-46 - 99% Bandwidth – TXC TCXO – 952.5 MHz - m4Pass20k Mode

Table 2.3.6-8 - 99% Bandwidth – TXC TCXO – 959.925 MHz

Frequency (MHz)	ISED Canada Rule Part	Mode	99% Bandwidth (kHz)
959.925	N/A	mPass5k	5.853
959.925	N/A	mPass10k	11.800
959.925	N/A	m4Pass10k	6.019
959.925	N/A	m4Pass20k	11.983




Figure 2.3.6-47 - 99% Bandwidth – TxC TCXO – 959.925 MHz - mPass5k Mode




Figure 2.3.6-48 - 99% Bandwidth – TxC TCXO – 959.925 MHz - mPass10k Mode




Figure 2.3.6-49 - 99% Bandwidth – TxC TCXO – 959.925 MHz - m4Pass10 Mode




Figure 2.3.6-50 - 99% Bandwidth – TxC TCXO – 959.925 MHz - m4Pass20k Mode



2.3.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Digital MultiMeter	Fluke	115	BEMC02108	N/A	12	15-Jan-2026
Duratest 175 Cable 26.5GHz	Teledyne Storm Products	921-0101-036	BEMC02112	N/A	12	18-Oct-2025
Signal & Spectrum Analyzer	Rohde & Schwarz	FSW43	DEMC3085	2.90 SP1	12	03-Jun-2025
DC Power Supply	Xantrex	HPD-60-5	TAME01064	N/A	N/A	NCR
30 dB Fixed Attenuator	Mini-Circuits	BW-S30W5+	TEMC00264	N/A	12	06-Apr-2025

TU - Traceability Unscheduled

O/P MON – Output Monitored with Calibrated Equipment

N/A - Not Applicable

NCR – No Calibration Required

2.4 Spurious Emissions at Antenna Terminals

2.4.1 Specification Reference

FCC 47 CFR Parts: 2.1051; 24.133 a(1), a(2); 101.111 a(5), a(6)
ISED Canada RSS-119 5.8.3, 5.8.6; RSS-134 4.4

2.4.2 Equipment Under Test and Modification State

825512079174759; TXC TCXO

2.4.3 Date of Test

2025-February-03 to 2025-February-05

2.4.4 Test Method

The RF output of the equipment under test was directly connected to the input of the Spectrum Analyzer through a 30 dB passive attenuator. The spectrum analyzer resolution bandwidth was set to 100 kHz below 1000 MHz and 1 MHz above 1000 MHz. The internal correction factors of the spectrum analyzer were employed to correct for any cable or attenuator. The spectrum was investigated in accordance with CFR 47 Part 2.1057

2.4.5 Environmental Conditions

Ambient Temperature 25.7 °C
Relative Humidity 34.1 %
Atmospheric Pressure 1020.5 mbar

2.4.6 Test Results

DC Powered, Operating

FCC Part 24.133a(1),(a2); ISED Canada RSS-134 4.4

Table 2.4.6-1 – Conducted Spurious – TXC TCXO – 901.5 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
901.5	1803	-25.88	-13	12.88




Figure 2.4.6-1 - Transmitter Conducted Spurious Emissions – TXC TCXO – 901.5 MHz - Normal Mode

Table 2.4.6-2 – Conducted Spurious – TXC TCXO – 930.5 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
930.5	1861	-23.75	-13	10.75




Figure 2.4.6-2 - Transmitter Conducted Spurious Emissions – TXC TCXO – 930.5 MHz - mPass5k Mode

Table 2.4.6-3 – Conducted Spurious – TXC TCXO – 940.0125 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
940.0125	1880.025	-23.45	-13	10.45




Figure 2.4.6-3 - Transmitter Conducted Spurious Emissions – TXC TCXO – 940.0125 MHz - mPass5k Mode

FCC 47 CFR Parts: 101.111 a(6), ISED Canada RSS-119 5.8.6

Table 2.4.6-4 – Conducted Spurious – TXC TCXO – 928.925 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
928.925	1857.85	-23.59	-20	3.59




Figure 2.4.6-4 - Transmitter Conducted Spurious Emissions – TXC TCXO – 928.925 MHz - Normal Mode

Table 2.4.6-5 – Conducted Spurious – TXC TCXO – 932.25 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
932.25	1864.5	-23.76	-20	3.76




Figure 2.4.6-5 - Transmitter Conducted Spurious Emissions – TXC TCXO – 932.25 MHz - Normal Mode

Table 2.4.6-6 – Conducted Spurious – TXC TCXO – 941.4875 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
941.4875	1882.975	-23.5	-20	3.5




Figure 2.4.6-6 - Transmitter Conducted Spurious Emissions – TxC TCXO – 941.4875 MHz - mPass5k Mode

Table 2.4.6-7 – Conducted Spurious – TxC TCXO – 952.5 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
959.925	1919.85	-22.94	-20	2.94




Figure 2.4.6-7 - Transmitter Conducted Spurious Emissions – TXC TCXO – 952.5 MHz - mPass5k Mode

Table 2.4.6-8 – Conducted Spurious – TXC TCXO – 959.925 MHz

Fundamental Frequency (MHz)	Spurious Frequency (MHz)	Spurious (dBm)	Limit (dBm)	Margin (dB)
959.925	1919.85	-22.97	-20	2.97




Figure 2.4.6-8 - Transmitter Conducted Spurious Emissions – TXC TCXO – 959.925 MHz - mPass5k Mode



2.4.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Digital MultiMeter	Fluke	115	BEMC02108	N/A	12	15-Jan-2026
Duratest 175 Cable 26.5GHz	Teledyne Storm Products	921-0101-036	BEMC02112	N/A	12	18-Oct-2025
Signal & Spectrum Analyzer	Rohde & Schwarz	FSW43	DEMC3085	2.90 SP1	12	03-Jun-2025
DC Power Supply	Xantrex	HPD-60-5	TAME01064	N/A	N/A	NCR
30 dB Fixed Attenuator	Mini-Circuits	BW-S30W5+	TEMC00264	N/A	12	06-Apr-2025

TU - Traceability Unscheduled

O/P MON – Output Monitored with Calibrated Equipment

N/A - Not Applicable

NCR – No Calibration Required



2.5 Field Strength of Spurious Radiation

2.5.1 Specification Reference

FCC 47 CFR Parts: 2.1053; 24.133 a(1), a(2); 101.111 a(5), a(6)
ISED Canada RSS-119 5.8.3, 5.8.6; RSS-134 4.4

2.5.2 Equipment Under Test and Modification State

825512079174777; Epson TCXO
825512079174769; TXC TCXO

2.5.3 Date of Test

2025-January-17 to 2025-January-28

2.5.4 Test Method

The EUT was evaluated in accordance to ANSI C63.26:2015 Section 5.5.3 Measurement of Spurious Emissions using Substitution Method.

Radiated emissions tests were made over the frequency range of 30 MHz to 10 times the highest fundamental frequency. The equipment under test is placed in the Semi-Anechoic Chamber on a RF transparent table at the turntable center. For each spurious emission, the antenna mast is raised and lowered from one (1) to four (4) meters and the turntable is rotated 360° and the maximum reading on the spectrum analyzer is recorded. This was repeated for both horizontal and vertical polarizations of the receive antenna.

The equipment under test is then replaced with a substitution antenna fed by a signal generator. The signal generator's frequency is set to that of the spurious emission recorded from the equipment under test. The antenna mast is raised and lowered from one (1) to four (4) meters to obtain a maximum reading on the spectrum analyzer. The output of the signal generator is then adjusted until the reading on the spectrum analyzer matches that obtained from the equipment under test. The signal generator level is recorded. The power in dBm of each spurious emission is calculated by correcting the signal generator level for the cable loss and gain of the substitution antenna referenced to a dipole. The spectrum was investigated in accordance to FCC CFR 47 Part 2.1057.

The magnitude of all spurious emissions not reported were attenuated below the noise floor of the measurement system and therefore not specified in this report. Results are shown below.

2.5.5 Environmental Conditions

Ambient Temperature	24.1 °C
Relative Humidity	32.8 %
Atmospheric Pressure	1016.9 mbar



2.5.6 Test Results

DC Powered, Operating

FCC Part 24.133a(1),(a2); ISED Canada RSS-134 4.4

IDTB007 - Epson TCXO

Table 2.5.6-1 - Transmitter Radiated Spurious Emissions – KDS TCXO – 901.5 MHz - Normal Mode

Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1803	-43.31	H	-43.13	-13.00	30.13
2704.5	-40.13	H	-36.24	-13.00	23.24
3606	-43.97	H	-39.40	-13.00	26.40
4507.5	-46.56	H	-40.07	-13.00	27.07
5409	-53.83	H	-46.22	-13.00	33.22
6310.5	-52.92	H	-43.12	-13.00	30.12
7212	-59.97	H	-55.44	-13.00	42.44
8113.5	-57.22	H	-49.31	-13.00	36.31
9015	-60.32	H	-54.57	-13.00	41.57
1803	-39.49	V	-38.22	-13.00	25.22
2704.5	-42.13	V	-38.15	-13.00	25.15
3606	-45.84	V	-40.94	-13.00	27.94
4507.5	-47.07	V	-39.96	-13.00	26.96
5409	-55.95	V	-49.34	-13.00	36.34
6310.5	-53.18	V	-43.24	-13.00	30.24
7212	-57.99	V	-51.27	-13.00	38.27
8113.5	-60.38	V	-55.44	-13.00	42.44
9015	-62.38	V	-58.17	-13.00	45.17



IDTB007 - TXC TCXO

Table 2.5.6-2 - Transmitter Radiated Spurious Emissions – TXC TCXO – 901.5 MHz - Normal Mode

Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1803	-43.63	H	-43.45	-13.00	30.45
2704.5	-39.53	H	-35.60	-13.00	22.60
3606	-45.06	H	-40.75	-13.00	27.75
4507.5	-44.63	H	-37.84	-13.00	24.84
5409	-53.27	H	-45.30	-13.00	32.30
6310.5	-54.71	H	-45.52	-13.00	32.52
7212	-60.07	H	-55.54	-13.00	42.54
8113.5	-58.13	H	-49.50	-13.00	36.50
9015	-57.54	H	-49.42	-13.00	36.42
1803	-41.42	V	-40.19	-13.00	27.19
2704.5	-40.23	V	-35.96	-13.00	22.96
3606	-46.03	V	-41.13	-13.00	28.13
4507.5	-46.15	V	-38.84	-13.00	25.84
5409	-54.38	V	-47.13	-13.00	34.13
6310.5	-53.73	V	-43.79	-13.00	30.79
7212	-60.31	V	-54.81	-13.00	41.81
8113.5	-60.75	V	-55.81	-13.00	42.81
9015	-61.48	V	-57.27	-13.00	44.27



Table 2.5.6-3 - Transmitter Radiated Spurious Emissions – TXC TCXO – 930.5 MHz - mPass5k Mode

Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1861	-49.99	H	-49.83	-13.00	36.83
2791.5	-49.26	H	-47.21	-13.00	34.21
3722	-43.79	H	-38.66	-13.00	25.66
4652.5	-54.15	H	-49.10	-13.00	36.10
5583	-55.34	H	-49.12	-13.00	36.12
6513.5	-54.64	H	-45.14	-13.00	32.14
7444	-59.06	H	-51.88	-13.00	38.88
8374.5	-60.59	H	-53.63	-13.00	40.63
9305	-62.19	H	-58.24	-13.00	45.24
1861	-46.84	V	-46.09	-13.00	33.09
2791.5	-50.64	V	-48.41	-13.00	35.41
3722	-44.80	V	-39.20	-13.00	26.20
4652.5	-54.10	V	-48.20	-13.00	35.20
5583	-53.55	V	-45.39	-13.00	32.39
6513.5	-55.90	V	-46.65	-13.00	33.65
7444	-60.97	V	-54.75	-13.00	41.75
8374.5	-60.63	V	-53.46	-13.00	40.46
9305	-62.15	V	-56.07	-13.00	43.07



Table 2.5.6-4 - Transmitter Radiated Spurious Emissions – TXC TCXO – 940.0125 MHz - mPass5k Mode

Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1880.025	-51.53	H	-52.17	-13.00	39.17
2820.0375	-50.16	H	-48.55	-13.00	35.55
3760.05	-45.60	H	-41.35	-13.00	28.35
4700.0625	-55.82	H	-51.49	-13.00	38.49
5640.075	-54.69	H	-47.21	-13.00	34.21
6580.0875	-58.73	H	-51.82	-13.00	38.82
7520.1	-58.41	H	-50.51	-13.00	37.51
8460.1125	-61.83	H	-56.20	-13.00	43.20
9400.125	-61.01	H	-55.89	-13.00	42.89
1880.025	-48.69	V	-48.34	-13.00	35.34
2820.0375	-51.45	V	-50.43	-13.00	37.43
3760.05	-45.30	V	-39.96	-13.00	26.96
4700.0625	-55.56	V	-50.51	-13.00	37.51
5640.075	-54.33	V	-46.57	-13.00	33.57
6580.0875	-59.99	V	-52.44	-13.00	39.44
7520.1	-61.00	V	-54.31	-13.00	41.31
8460.1125	-63.04	V	-57.36	-13.00	44.36
9400.125	-57.25	V	-47.52	-13.00	34.52



FCC 47 CFR Parts: 101.111 a(6), ISED Canada RSS-119 5.8.3, 5.8.6

The most stringent limits are applied for the measurement results.

Table 2.5.6-5 - Transmitter Radiated Spurious Emissions – TXC TCXO – 928.925 MHz - Normal Mode

Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1857.85	-51.97	H	-52.22	-20.00	32.22
2786.775	-48.72	H	-46.44	-20.00	26.44
3715.7	-43.36	H	-38.04	-20.00	18.04
4644.625	-58.24	H	-56.37	-20.00	36.37
5573.55	-55.22	H	-48.15	-20.00	28.15
6502.475	-55.27	H	-45.55	-20.00	25.55
7431.4	-58.93	H	-51.14	-20.00	31.14
8360.325	-60.51	H	-52.91	-20.00	32.91
9289.25	-62.04	H	-57.49	-20.00	37.49
1857.85	-46.54	V	-45.35	-20.00	25.35
2786.775	-50.28	V	-48.27	-20.00	28.27
3715.7	-44.97	V	-39.33	-20.00	19.33
4644.625	-53.71	V	-47.31	-20.00	27.31
5573.55	-54.61	V	-46.20	-20.00	26.20
6502.475	-55.08	V	-44.59	-20.00	24.59
7431.4	-60.45	V	-53.84	-20.00	33.84
8360.325	-60.05	V	-50.93	-20.00	30.93
9289.25	-62.20	V	-56.31	-20.00	36.31

Table 2.5.6-6 - Transmitter Radiated Spurious Emissions – TXC TCXO – 932.25 MHz - Normal Mode



Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1864.5	-50.53	H	-50.72	-20.00	30.72
2796.75	-49.91	H	-48.19	-20.00	28.19
3729	-43.73	H	-38.71	-20.00	18.71
4661.25	-55.44	H	-51.12	-20.00	31.12
5593.5	-54.98	H	-48.41	-20.00	28.41
6525.75	-55.34	H	-46.76	-20.00	26.76
7458	-59.14	H	-52.32	-20.00	32.32
8390.25	-59.90	H	-51.91	-20.00	31.91
9322.5	-61.67	H	-55.72	-20.00	35.72
1864.5	-47.46	V	-46.99	-20.00	26.99
2796.75	-50.67	V	-48.76	-20.00	28.76
3729	-44.41	V	-38.89	-20.00	18.89
4661.25	-55.46	V	-50.48	-20.00	30.48
5593.5	-54.31	V	-46.85	-20.00	26.85
6525.75	-56.04	V	-48.02	-20.00	28.02
7458	-59.91	V	-52.85	-20.00	32.85
8390.25	-61.19	V	-54.22	-20.00	34.22
9322.5	-62.00	V	-55.77	-20.00	35.77

Table 2.5.6-7 - Transmitter Radiated Spurious Emissions – TXC TCXO – 941.4875 MHz - mPass5k Mode



Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1882.975	-52.09	H	-52.84	-20.00	32.84
2824.4625	-49.99	H	-48.42	-20.00	28.42
3765.95	-45.25	H	-40.98	-20.00	20.98
4707.4375	-56.39	H	-52.55	-20.00	32.55
5648.925	-55.11	H	-48.93	-20.00	28.93
6590.4125	-58.95	H	-51.73	-20.00	31.73
7531.9	-58.59	H	-51.40	-20.00	31.40
8473.3875	-60.74	H	-54.06	-20.00	34.06
9414.875	-60.34	H	-54.93	-20.00	34.93
1882.975	-49.58	V	-49.11	-20.00	29.11
2824.4625	-50.17	V	-48.30	-20.00	28.30
3765.95	-45.67	V	-40.31	-20.00	20.31
4707.4375	-56.88	V	-51.87	-20.00	31.87
5648.925	-54.42	V	-47.13	-20.00	27.13
6590.4125	-60.23	V	-52.94	-20.00	32.94
7531.9	-61.68	V	-55.99	-20.00	35.99
8473.3875	-62.42	V	-56.60	-20.00	36.60
9414.875	-61.81	V	-55.79	-20.00	35.79

Table 2.5.6-8 - Transmitter Radiated Spurious Emissions – TXC TCXO – 952.5 MHz - mPass5k Mode



Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1905	-50.30	H	-50.74	-20.00	30.74
2857.5	-46.80	H	-43.79	-20.00	23.79
3810	-46.94	H	-42.65	-20.00	22.65
4762.5	-55.49	H	-50.47	-20.00	30.47
5715	-55.15	H	-48.34	-20.00	28.34
6667.5	-57.05	H	-49.32	-20.00	29.32
7620	-57.84	H	-49.24	-20.00	29.24
8572.5	-57.53	H	-48.70	-20.00	28.70
9525	-61.09	H	-55.96	-20.00	35.96
1905	-48.72	V	-48.62	-20.00	28.62
2857.5	-47.11	V	-43.71	-20.00	23.71
3810	-47.06	V	-41.98	-20.00	21.98
4762.5	-54.85	V	-48.96	-20.00	28.96
5715	-54.24	V	-46.10	-20.00	26.10
6667.5	-59.45	V	-52.21	-20.00	32.21
7620	-59.68	V	-52.59	-20.00	32.59
8572.5	-60.22	V	-53.49	-20.00	33.49
9525	-61.70	V	-55.51	-20.00	35.51



Table 2.5.6-9 - Transmitter Radiated Spurious Emissions – TXC TCXO – 959.925 MHz - mPass5k Mode

Frequency (MHz)	Spectrum Analyzer Level (dBm)	Antenna Polarity (H/V)	Spurious ERP (dBm)	Limit (dBm)	Margin (dB)
1919.85	-49.21	H	-49.68	-20.00	29.68
2879.775	-44.16	H	-40.02	-20.00	20.02
3839.7	-50.13	H	-46.26	-20.00	26.26
4799.625	-53.11	H	-46.12	-20.00	26.12
5759.55	-56.66	H	-49.12	-20.00	29.12
6719.475	-56.20	H	-46.62	-20.00	26.62
7679.4	-57.83	H	-48.07	-20.00	28.07
8639.325	-55.85	H	-45.95	-20.00	25.95
9599.25	-60.25	H	-53.67	-20.00	33.67
1919.85	-46.50	V	-45.92	-20.00	25.92
2879.775	-43.41	V	-39.24	-20.00	19.24
3839.7	-49.72	V	-45.28	-20.00	25.28
4799.625	-53.99	V	-47.12	-20.00	27.12
5759.55	-56.32	V	-49.07	-20.00	29.07
6719.475	-58.65	V	-51.55	-20.00	31.55
7679.4	-59.45	V	-52.41	-20.00	32.41
8639.325	-58.06	V	-50.35	-20.00	30.35
9599.25	-60.18	V	-53.93	-20.00	33.93



Representative Plots




Figure 2.5.6-1 - Transmitter Radiated Spurious Emissions – TXC TCXO – 928.925 MHz - Normal Mode – 9 kHz – 30 MHz – Vertical Polarization




Figure 2.5.6-2 - Transmitter Radiated Spurious Emissions – TXC TCXO – 928.925 MHz - Normal Mode – 30 MHz – 1 GHz – Horizontal Polarization




Figure 2.5.6-3 - Transmitter Radiated Spurious Emissions – TXC TCXO – 928.925 MHz - Normal Mode – 30 MHz – 1 GHz – Vertical Polarization




Figure 2.5.6-4 - Transmitter Radiated Spurious Emissions – TXC TCXO – 928.925 MHz - Normal Mode – 1 GHz – 10 GHz – Horizontal Polarization




Figure 2.5.6-5 - Transmitter Radiated Spurious Emissions – TXC TCXO – 928.925 MHz - Normal Mode – 1 GHz – 10 GHz – Vertical Polarization



2.5.7 Sample Calculations

$$\text{ERP} = \text{Pgen} - \text{Cables Loss} + \text{Substitution Antenna Gain [dBd]}$$

Where:

ERP is the EUT radiated Power in dBm

Pgen is the signal generator setting [dBm]

Cable Loss is the Transmit cable loss [dB]

Substitution Antenna Gain [dBd] = $10 \log(\text{antenna numeric gain}) - 2.15$.

Example Calculation

Radiated Power: $-37 - 8.45 + 7.438 = -38.012 \text{ dBm}$

Margin: $-20 - (-38.012) = 18 \text{ dBm}$



2.5.8 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Active Loop Antenna	EMCO	6502	BEMC00078	N/A	24	06-Sep-2025
100Hz-26.5GHz EMC analyzer/HYZ	Hewlett Packard	E7405A	BEMC00523	A.14.06	12	25-Jun-2025
Linear Polarized Horn antenna, 1-18 GHz	EMCO	3115	BEMC02006	N/A	24	12-Feb-2026
Notch Filter	Trilithic, Inc.	7NM867/122-X1-AA	BEMC02069	N/A	12	25-Nov-2025
Tile Automation Software	ETS Lindgren	TILE4! - Version 4.2.A	BEMC02095	4.2A	N/A	NCR
Digital MultiMeter	Fluke	115	BEMC02108	N/A	12	15-Jan-2026
Synthesized Signal Generator 0.05 - 26 GHz	Hewlett Packard	8673D	BEMC02126	N/A	24	26-Jun-2026
PE-P160 40 GHz Cable	Pasternack	PE360-396	BEMC02147	N/A	12	10-Jun-2025
BI LOG PERIODIC, ANTENNA	Schaffner	CBL6112B	TEMC00005	N/A	24	07-Nov-2025
EMC Chamber	Panashield	N/A	TEMC00031	N/A	24	19-Oct-2025
Double Ridge Guide Horn	ETS Lindgren	3117	TEMC00061	N/A	24	15-Feb-2026
Microwave Preamplifier	Com-Power Corporation	PAM-118A	TEMC00160	N/A	12	12-Dec-2025
1.2 GHz High Pass Filter	Micro-Tronics	HPM50108-01	TEMC00175	N/A	12	19-Feb-2025
R & S ESW EMI Test Receiver	Rohde & Schwarz	ESW	TEMC00232	2.00 SP1	12	04-Jun-2025
DC to 18 GHz Cable	SSI Technologies	2801-03-03-360/WN	TEMC00293	N/A	12	13-Dec-2025

TU - Traceability Unscheduled

O/P MON – Output Monitored with Calibrated Equipment

N/A - Not Applicable

NCR – No Calibration Required

2.6 Frequency Stability

2.6.1 Specification Reference

FCC Section 2.1055; FCC Section 24.135, 101.107
ISED Canada RSS-134 4.5

2.6.2 Equipment Under Test and Modification State

825512079174736; Epson TCXO

2.6.3 Date of Test

2025-February-06 to 2025-February-07

2.6.4 Test Method

The equipment under test is placed inside an environmental chamber. The RF output is directly coupled to the input of the measurement equipment and a power supply is attached to the primary supply voltage.

Frequency measurements were made at the extremes of the of temperature range -30° C to +50° C and at intervals of 10° C at normal supply voltage. Sufficient time to stabilize all components of the equipment was allowed at each frequency measurement. At a temperature 20° C the supply voltage was varied from 85 to 115 percent of the nominal value . The maximum variation of frequency was recorded.

2.6.5 Environmental Conditions

Ambient Temperature	23.6 °C
Relative Humidity	37.7 %
Atmospheric Pressure	1018.0 mbar



2.6.6 Test Results

Table 2.6.6-1 - FCC Part 24.135 Frequency Stability Limits

Frequency Range MHz	Percent	PPM
901 - 902	±0.0001	±1.0
930 - 931		
940 - 941		

Table 2.6.6-2 - FCC Part 101.107 Frequency Stability Limits

Frequency Range MHz	Percent	PPM
928 – 929	±0.0005	±5.0
932 – 932.5	±0.00015	±1.5
941 – 941.5	±0.00015	±1.5
952 – 960	±0.0005	±5.0

Note: The most stringent limit of 1.0 ppm was used across all the bands of operation.



IDTB007 – Epson TCXO

Frequency Stability

Frequency (MHz): 901.500280

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature	Frequency	Frequency Error	Voltage	Voltage
C	MHz	(PPM)	(%)	(VDC)
-30 C	901.500251	-0.033	100%	4.20
-20 C	901.500225	-0.062	100%	4.20
-10 C	901.500232	-0.054	100%	4.20
0 C	901.500308	0.031	100%	4.20
10 C	901.500315	0.038	100%	4.20
20 C	901.500280	0.000	100%	4.20
30 C	901.500349	0.076	100%	4.20
40 C	901.500347	0.073	100%	4.20
50 C	901.500234	-0.051	100%	4.20
20 C	901.500198	-0.091	85%	3.57
20 C	901.500226	-0.060	115%	4.83




Figure 2.6.6-1 - Frequency Stability – Epson TCXO – 901.5 MHz



Frequency Stability

Frequency (MHz): 928.92517

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature C	Frequency MHz	Frequency Error (PPM)	Voltage (%)	Voltage (VDC)
-30 C	928.925100	-0.079	100%	4.20
-20 C	928.925102	-0.077	100%	4.20
-10 C	928.925137	-0.039	100%	4.20
0 C	928.925161	-0.014	100%	4.20
10 C	928.925143	-0.033	100%	4.20
20 C	928.925174	0.000	100%	4.20
30 C	928.925203	0.032	100%	4.20
40 C	928.925122	-0.055	100%	4.20
50 C	928.925089	-0.092	100%	4.20
20 C	928.925080	-0.101	85%	3.57
20 C	928.925211	0.040	115%	4.83




Figure 2.6.6-2 - Frequency Stability – Epson TCXO – 928.925 MHz



Frequency Stability

Frequency (MHz): 930.5002

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature C	Frequency MHz	Frequency Error (PPM)	Voltage (%)	Voltage (VDC)
-30 C	930.500081	-0.097	100%	4.20
-20 C	930.500067	-0.112	100%	4.20
-10 C	930.500123	-0.051	100%	4.20
0 C	930.500144	-0.029	100%	4.20
10 C	930.500116	-0.059	100%	4.20
20 C	930.500171	0.000	100%	4.20
30 C	930.500167	-0.004	100%	4.20
40 C	930.500107	-0.068	100%	4.20
50 C	930.500070	-0.108	100%	4.20
20 C	930.500072	-0.106	85%	3.57
20 C	930.500134	-0.039	115%	4.83




Figure 2.6.6-3 - Frequency Stability – Epson TCXO – 930.5 MHz



Frequency Stability

Frequency (MHz): 932.2502

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature C	Frequency MHz	Frequency Error (PPM)	Voltage (%)	Voltage (VDC)
-30 C	932.250063	-0.094	100%	4.20
-20 C	932.250045	-0.113	100%	4.20
-10 C	932.250104	-0.050	100%	4.20
0 C	932.250126	-0.026	100%	4.20
10 C	932.250093	-0.061	100%	4.20
20 C	932.250150	0.000	100%	4.20
30 C	932.250160	0.010	100%	4.20
40 C	932.250088	-0.067	100%	4.20
50 C	932.250048	-0.110	100%	4.20
20 C	932.250053	-0.105	85%	3.57
20 C	932.250180	0.031	115%	4.83




Figure 2.6.6-4 - Frequency Stability – Epson TCXO – 932.25 MHz



Frequency Stability

Frequency (MHz): 940.0126

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature C	Frequency MHz	Frequency Error (PPM)	Voltage (%)	Voltage (VDC)
-30 C	940.012510	-0.104	100%	4.20
-20 C	940.012501	-0.114	100%	4.20
-10 C	940.012543	-0.069	100%	4.20
0 C	940.012574	-0.036	100%	4.20
10 C	940.012544	-0.068	100%	4.20
20 C	940.012608	0.000	100%	4.20
30 C	940.012573	-0.037	100%	4.20
40 C	940.012545	-0.067	100%	4.20
50 C	940.012493	-0.122	100%	4.20
20 C	940.012497	-0.118	85%	3.57
20 C	940.012557	-0.054	115%	4.83




Figure 2.6.6-5 - Frequency Stability – Epson TCXO – 940.0125 MHz



Frequency Stability

Frequency (MHz): 941.4876

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature C	Frequency MHz	Frequency Error (PPM)	Voltage (%)	Voltage (VDC)
-30 C	941.487508	-0.106	100%	4.20
-20 C	941.487495	-0.120	100%	4.20
-10 C	941.487555	-0.056	100%	4.20
0 C	941.487573	-0.037	100%	4.20
10 C	941.487536	-0.076	100%	4.20
20 C	941.487607	0.000	100%	4.20
30 C	941.487618	0.012	100%	4.20
40 C	941.487539	-0.073	100%	4.20
50 C	941.487491	-0.124	100%	4.20
20 C	941.487508	-0.105	85%	3.57
20 C	941.487628	0.022	115%	4.83




Figure 2.6.6-6 - Frequency Stability – Epson TCXO – 941.4875 MHz



Frequency Stability

Frequency (MHz): 952.5000

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature C	Frequency MHz	Frequency Error (PPM)	Voltage (%)	Voltage (VDC)
-30 C	952.499944	-0.106	100%	4.20
-20 C	952.499938	-0.112	100%	4.20
-10 C	952.499996	-0.052	100%	4.20
0 C	952.500006	-0.041	100%	4.20
10 C	952.499974	-0.075	100%	4.20
20 C	952.500045	0.000	100%	4.20
30 C	952.500033	-0.013	100%	4.20
40 C	952.499972	-0.077	100%	4.20
50 C	952.499922	-0.129	100%	4.20
20 C	952.499935	-0.116	85%	3.57
20 C	952.500029	-0.017	115%	4.83




Figure 2.6.6-7 - Frequency Stability – Epson TCXO – 952.5 MHz



Frequency Stability

Frequency (MHz): 959.9250

Deviation Limit (PPM): 1

Nominal Voltage (VDC): 4.2

Temperature C	Frequency MHz	Frequency Error (PPM)	Voltage (%)	Voltage (VDC)
-30 C	959.924912	-0.108	100%	4.20
-20 C	959.924900	-0.121	100%	4.20
-10 C	959.924970	-0.048	100%	4.20
0 C	959.924975	-0.042	100%	4.20
10 C	959.924939	-0.079	100%	4.20
20 C	959.925015	0.000	100%	4.20
30 C	959.925001	-0.015	100%	4.20
40 C	959.924942	-0.076	100%	4.20
50 C	959.924891	-0.130	100%	4.20
20 C	959.924908	-0.112	85%	3.57
20 C	959.924990	-0.026	115%	4.83




Figure 2.6.6-8 - Frequency Stability – Epson TCXO – 959.925 MHz



2.6.7 Test Location and Test Equipment Used

This test was carried out in TÜV SÜD America, Inc., 5610 W. Sligh Ave, Suite 100, Tampa, FL 33634, USA.

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Digital Thermometer	Omega Engineering, Inc.	MDSS41-TC	BEMC00002	N/A	24	19-Sep-2025
Digital MultiMeter	Fluke	115	BEMC02108	N/A	12	15-Jan-2026
Signal & Spectrum Analyzer	Rohde & Schwarz	FSW43	DEMC3085	2.90 SP1	12	03-Jun-2025
DC Power Supply	Xantrex	HPD-60-5	TAME01064	N/A	N/A	NCR
Temperature Test Chamber	Sun Electronic Systems, Inc.	EC127	TEMC00242	5.10	N/A	NCR
30 dB Fixed Attenuator	Mini-Circuits	BW-S30W5+	TEMC00264	N/A	12	06-Apr-2025
Flexible Test Cable	Mini-Circuits	ULC-8FT-SMSM+	TEMC00267	N/A	12	08-Mar-2025

TU - Traceability Unscheduled

O/P MON – Output Monitored with Calibrated Equipment

N/A - Not Applicable

NCR - No Calibration Required



3 Test Equipment Information

3.1 General Test Equipment Used

Instrument	Manufacturer	Type No	TE No	Software / Firmware Revision	Calibration Period (months)	Calibration Due
Digital Thermometer	Omega Engineering, Inc.	MDSS41-TC	BEMC00002	N/A	24	19-Sep-2025
100Hz-26.5GHz EMC analyzer/HYZ	Hewlett Packard	E7405A	BEMC00523	A.14.06	12	25-Jun-2025
Linear Polarized Horn antenna, 1-18 GHz	EMCO	3115	BEMC02006	N/A	24	12-Feb-2026
Notch Filter	Trilithic, Inc.	7NM867/122-X1-AA	BEMC02069	N/A	12	25-Nov-2025
Tile Automation Software	ETS Lindgren	TILE4! - Version 4.2.A	BEMC02095	4.2A	N/A	NCR
Digital MultiMeter	Fluke	115	BEMC02108	N/A	12	15-Jan-2026
Duratest 175 Cable 26.5GHz	Teledyne Storm Products	921-0101-036	BEMC02112	N/A	12	18-Oct-2025
Synthesized Signal Generator 0.05 - 26 GHz	Hewlett Packard	8673D	BEMC02126	N/A	24	26-Jun-2026
PE-P160 40 GHz Cable	Pasternack	PE360-396	BEMC02147	N/A	12	10-Jun-2025
Signal & Spectrum Analyzer	Rohde & Schwarz	FSW43	DEMC3085	2.90 SP1	12	03-Jun-2025
DC Power Supply	Xantrex	HPD-60-5	TAME01064	N/A	N/A	NCR
BI LOG PERIODIC, ANTENNA	Schaffner	CBL6112B	TEMC00005	N/A	24	07-Nov-2025
EMC Chamber	Panashield	N/A	TEMC00031	N/A	24	19-Oct-2025
Double Ridge Guide Horn	ETS Lindgren	3117	TEMC00061	N/A	24	15-Feb-2026
Microwave Preamplifier	Com-Power Corporation	PAM-118A	TEMC00160	N/A	12	12-Dec-2025
1.2 GHz High Pass Filter	Micro-Tronics	HPM50108-01	TEMC00175	N/A	12	19-Feb-2025
R & S ESW EMI Test Receiver	Rohde & Schwarz	ESW	TEMC00232	2.00 SP1	12	04-Jun-2025
Temperature Test Chamber	Sun Electronic Systems, Inc.	EC127	TEMC00242	5.10	N/A	NCR
30 dB Fixed Attenuator	Mini-Circuits	BW-S30W5+	TEMC00264	N/A	12	06-Apr-2025
Flexible Test Cable	Mini-Circuits	ULC-8FT-SMSM+	TEMC00267	N/A	12	08-Mar-2025
DC to 18 GHz Cable	SSI Technologies	2801-03-03-360/WN	TEMC00293	N/A	12	13-Dec-2025



TU - Traceability Unscheduled
O/P MON – Output Monitored with Calibrated Equipment
N/A - Not Applicable
NCR - No Calibration Required

4 Diagram of Test Set-ups




Figure 4-1 – RF Conducted Emissions Test Setup up, General Measurements




Figure 4-2 – RF Conducted Emissions Test Setup up, Extreme Conditions




Figure 4-3 – Radiated Emissions Test Setup up to 30 MHz




Figure 4-4 – Radiated Emissions Test Setup up to 1 GHz




Figure 4-5 – Radiated Emissions Test Setup above 1 GHz




Figure 4-6 – Substitution Test Setup above 1 GHz

5 Measurement Uncertainty

For a 95% confidence level, the measurement uncertainties for defined systems are:

Table 5-1 - Values of U_{CISPR} and U_{Lab}

Measurement	U_{CISPR}	U_{Lab}
Conducted disturbance (mains port) (9 kHz – 150 kHz) (150 kHz – 30 MHz)	3.8 dB 3.4 dB	3.71 dB 3.31 dB
Conducted disturbance (telecom port) (150 kHz – 30 MHz 55 dB LCL) (150 kHz – 30 MHz 65 dB LCL) (150 kHz – 30 MHz 75 dB LCL)	5.0 dB 5.0 dB 5.0 dB	4.11 dB 4.50 dB 4.94 dB
Radiated disturbance (electric field strength on an open area test site or alternative test site) (30 MHz – 1 000 MHz) (1 – 6 GHz) (6-18 GHz)	6.3 dB 5.2 dB 5.5 dB	5.94 dB 5.07 dB 5.07 dB

Notes:

U_{CISPR} resembles a value of measurement uncertainty for a specific test, which was determined by considering uncertainties associated with the quantities listed in CISPR 16-4-2:2011.



6 Accreditation, Disclaimers and Copyright

TÜV SÜD America Inc.'s reports apply only to the specific sample tested under stated test conditions. It is the manufacturer's responsibility to assure the continued compliance of production units of this model. TÜV SÜD America, Inc. shall have no liability for any deductions, inferences or generalizations drawn by the client or others from TÜV SÜD America, Inc.'s issued reports.

This report is the confidential property of the client. As a mutual protection to our clients, the public and TÜV SÜD America, Inc., extracts from the test report shall not be reproduced, except in full without TÜV SÜD America, Inc.'s written approval.

This report must not be used to claim product certification, approval, or endorsement by A2LA, NIST, or any agency of the federal government.