


Page: 161 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3 :5550 MHz

:Tx CH Mid :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
11100.00	Average	24.04	17.36	41.40	54.00	-12.60
11100.00	Peak	31.75	17.36	49.11	74.00	-24.89

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 162 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3 :5550 MHz

:Tx CH Mid :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
11100.00	Average	24.00	17.36	41.36	54.00	-12.64
11100.00	Peak	33.39	17.36	50.75	74.00	-23.25

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 163 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3 :5670 MHz

:Tx CH High :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Detector	Spectrum	Factor	Actual	Limit	Margin	
Mode	Reading Level		FS	@3m		
PK/QP/AV	dΒμV	dB	dBμV/m	dBμV/m	dB	
Average	23.97	16.32	40.29	54.00	-13.71	
Peak	33.13	16.32	49.45	74.00	-24.55	
	Mode PK/QP/AV Average	Mode Reading Level PK/QP/AV dBµV Average 23.97	Mode         Reading Level           PK/QP/AV         dBμV         dB           Average         23.97         16.32	Mode Price         PS PK/QP/AV         FS dBμV/m           Average         23.97         16.32         40.29	Mode Pk/QP/AV         Reading Level PK/QP/AV         FS dBμV/m         @3m dBμV/m           Average         23.97         16.32         40.29         54.00	Mode Pk/QP/AV         Reading Level PK/QP/AV         FS dBμV         @3m dBμV/m           Average         23.97         16.32         40.29         54.00         -13.71

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 164 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3 :5670 MHz

:Tx CH High :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
11340.00	Average	24.04	16.32	40.36	54.00	-13.64
11340.00	Peak	33.43	16.32	49.75	74.00	-24.25

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 165 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3/4

:5710 MHz :Tx CH 142 :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
11420.00	Average	24.16	17.08	41.24	54.00	-12.76
11420.00	Peak	33.55	17.08	50.63	74.00	-23.37

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 166 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3/4

:5710 MHz :Tx CH 142 :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
11420.00	Average	24.26	17.08	41.34	54.00	-12.66
11420.00	Peak	33.71	17.08	50.79	74.00	-23.21

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



EUT Pol.


Report No.: T190506W05-RP4

Page: 167 of 234

#### Radiated Spurious Emission Measurement Result 802.11n HT40 5725~5850 MHz

:E2 Plan

**Project Number** :T190506W05 Test Date :2019-05-18 **Operation Band** :802.11n40 / Band4 Temp./Humi. :21/52 **Fundamental Frequency** :5755 MHz Engineer :Kane **Operation Mode** :Tx CH Low Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBμV/m	dB
11510.00	Average	24.10	15.83	39.93	54.00	-14.07
11510.00	Peak	33.76	15.83	49.59	74.00	-24.41

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 168 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band4 :5755 MHz

:Tx CH Low :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Limit Margin
@3m
dBµV/m dB
54.00 -13.99
74.00 -24.24

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 169 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band4 :5795 MHz

:Tx CH High :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
11590.00	Average	24.01	16.74	40.75	54.00	-13.25
11590.00	Peak	33.82	16.74	50.56	74.00	-23.44

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 170 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band4 :5795 MHz

:Tx CH High :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
11590.00	Average	23.12	16.74	39.86	54.00	-14.14
11590.00	Peak	33.90	16.74	50.64	74.00	-23.36

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



EUT Pol.

10

0 1000

8800

Report No.: T190506W05-RP4

Page: 171 of 234


32200.

40000

# Radiated Spurious Emission Measurement Result 802.11ac VHT80 5150~5250 MHz

:E2 Plan

**Project Number** :T190506W05 Test Date :2019-05-18 **Operation Band** :802.11ac80 / Band1 Temp./Humi. :21/52 **Fundamental Frequency** :5210 MHz Engineer :Kane **Operation Mode** :Tx CH Low Measurement Antenna Pol. :VERTICAL



Frequency (MHz)

16600.

Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	-
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBμV/m	dB
10420.00	Peak	33.67	15.31	48.98	68.20	-19.22

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.

除非另有說明,此報告結果僅對測試之樣品負責,同時此樣品僅保留仍天。本報告未經本公司書面許可,不可部份複製。
This document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at <a href="https://www.sgs.com/terms">www.sgs.com/terms</a> and Conditions for Electronic Documents at <a href="https://www.sgs.com/terms">www.sgs.com/terms</a> e-document.htm. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders

may be prosecuted to the fullest extent of the law



Page: 172 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band1 :5210 MHz

:Tx CH Low :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	_
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBμV/m	dB
10420.00	Peak	33.95	15.31	49.26	68.20	-18.94

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



EUT Pol.


Report No.: T190506W05-RP4

Page: 173 of 234

# Radiated Spurious Emission Measurement Result 802.11ac VHT80 5250~5350 MHz

:E2 Plan

**Project Number** :T190506W05 Test Date :2019-05-18 **Operation Band** :802.11ac80 / Band2 Temp./Humi. :21/52 **Fundamental Frequency** Engineer :5290 MHz :Kane **Operation Mode** :Tx CH High Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
10580.00	Peak	34.25	15.21	49.46	68.20	-18.74

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 174 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band2 :5290 MHz

:Tx CH High :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBµV/m	dB
10580.00	Peak	33.60	15.21	48.81	68.20	-19.39

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 175 of 234

# Radiated Spurious Emission Measurement Result 802.11ac VHT80 5470~5725 MHz

**Project Number** :T190506W05 Test Date :2019-05-18 **Operation Band** :802.11ac80 / Band3 Temp./Humi. :21/52 **Fundamental Frequency** :5530 MHz Engineer :Kane **Operation Mode** :Tx CH Low Measurement Antenna Pol. :VERTICAL

EUT Pol. :E2 Plan



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
 MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBμV/m	dB
 11060.00	Average	23.97	17.46	41.43	54.00	-12.57
11060.00	Peak	32.90	17.46	50.36	74.00	-23.64

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 176 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band3

:5530 MHz :Tx CH Low :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
11060.00	Average	24.03	17.46	41.49	54.00	-12.51
11060.00	Peak	33.77	17.46	51.23	74.00	-22.77

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 177 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band3

:5610 MHz :Tx CH Mid :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
11220.00	Average	24.41	16.62	41.03	54.00	-12.97
11220.00	Peak	32.97	16.62	49.59	74.00	-24.41

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 178 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band3 :5610 MHz

:Tx CH Mid :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
11220.00	Average	24.18	16.62	40.80	54.00	-13.20
11220.00	Peak	33.35	16.62	49.97	74.00	-24.03

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 179 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band3/4

:5690 MHz :Tx CH High :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBµV/m	dBµV/m	dB
11380.00	Average	24.17	16.77	40.94	54.00	-13.06
11380.00	Peak	34.10	16.77	50.87	74.00	-23.13

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 180 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band3/4

:5690 MHz :Tx CH High :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
11380.00	Average	24.05	16.77	40.82	54.00	-13.18
11380.00	Peak	33.86	16.77	50.63	74.00	-23.37

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 181 of 234

### Radiated Spurious Emission Measurement Result 802.11ac VHT80 5725~5850 MHz

**Project Number** :T190506W05 Test Date :2019-05-18 **Operation Band** :802.11ac80 / Band4 Temp./Humi. :21/52

**Fundamental Frequency** :5775 MHz Engineer :Kane

**Operation Mode** :Tx CH Low Measurement Antenna Pol. :VERTICAL EUT Pol. :E2 Plan



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBµV/m	dB
11550.00	Average	24.28	16.09	40.37	54.00	-13.63
11550.00	Peak	33.73	16.09	49.82	74.00	-24.18

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 182 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band4

:5775 MHz :Tx CH Low :E2 Plan

**Test Date** :2019-05-18 Temp./Humi. :21/52 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBµV/m	dBµV/m	dB
11550.00	Average	24.09	16.09	40.18	54.00	-13.82
11550.00	Peak	32.23	16.09	48.32	74.00	-25.68

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 183 of 234


# Band edge falling to restricted band

#### 802.11a mode

:T190506W05 **Project Number Operation Band** :802.11a / Band1

**Fundamental Frequency** :5180 MHz **Operation Mode** :BE CH Low

EUT Pol. :E2 Plan **Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5148.88	Average	37.94	4.92	42.86	54.00	-11.14
5148.88	Peak	57.27	4.92	62.19	74.00	-11.81
5150.00	Average	38.32	4.92	43.24	54.00	-10.76
5150.00	Peak	55.25	4.92	60.17	74.00	-13.83

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 184 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band1 :5180 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBμV/m	dB
5148.16	Average	43.27	4.92	48.19	54.00	-5.81
5148.16	Peak	64.29	4.92	69.21	74.00	-4.79
5150.00	Average	43.97	4.92	48.89	54.00	-5.11
5150.00	Peak	62.21	4.92	67.13	74.00	-6.87

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 185 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band2 :5320 MHz :BE CH High

:E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
5350.00	Average	39.42	5.21	44.63	54.00	-9.37
5350.00	Peak	56.95	5.21	62.16	74.00	-11.84
5352.60	Average	38.92	5.22	44.14	54.00	-9.86
5352.60	Peak	58.61	5.22	63.83	74.00	-10.17

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 186 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band2 :5320 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5350.00	Average	43.89	5.21	49.10	54.00	-4.90
5350.00	Peak	63.13	5.21	68.34	74.00	-5.66
5352.48	Average	43.02	5.22	48.24	54.00	-5.76
5352.48	Peak	64.77	5.22	69.99	74.00	-4.01

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 187 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band3 :5500 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5460.00	Average	37.09	5.63	42.72	54.00	-11.28
5460.00	Peak	51.73	5.63	57.36	74.00	-16.64
5464.16	Peak	53.45	5.63	59.08	68.20	-9.12
5470.00	Peak	50.09	5.65	55.74	68.20	-12.46

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 188 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band3 :5500 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5460.00	Average	41.12	5.63	46.75	54.00	-7.25
5460.00	Peak	57.39	5.63	63.02	74.00	-10.98
5464.28	Peak	60.27	5.63	65.90	68.20	-2.30
5470.00	Peak	57.83	5.65	63.48	68.20	-4.72

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 189 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band3 :5700 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	_
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBµV/m	dB
5725.00	Peak	51.97	6.34	58.31	68.20	-9.89

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 190 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band3 :5700 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	-
MHz	PK/QP/AV	dBµV	dB	dBµV/m	dBµV/m	dB
5725.00	Peak	59.44	6.34	65.78	68.20	-2.42

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 191 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band4 :5745 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5650.00	Peak	48.40	6.04	54.44	68.20	-13.76
5700.00	Peak	56.90	6.32	63.22	105.20	-41.98
5720.00	Peak	63.97	6.33	70.30	110.80	-40.50
5725.00	Peak	65.62	6.34	71.96	122.20	-50.24

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 192 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band4 :5745 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5650.00	Peak	50.84	6.04	56.88	68.20	-11.32
5700.00	Peak	64.85	6.32	71.17	105.20	-34.03
5720.00	Peak	71.92	6.33	78.25	110.80	-32.55
5725.00	Peak	74.90	6.34	81.24	122.20	-40.96

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 193 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band4 :5825 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBµV/m	dBµV/m	dB
5850.00	Peak	60.68	6.39	67.07	122.20	-55.13
5855.00	Peak	59.11	6.38	65.49	110.80	-45.31
5875.00	Peak	56.29	6.37	62.66	105.20	-42.54
5925.00	Peak	48.70	6.42	55.12	68.20	-13.08

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 194 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11a / Band4 :5825 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-17 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBµV/m	dBµV/m	dB
5850.00	Peak	70.54	6.39	76.93	122.20	-45.27
5855.00	Peak	69.27	6.38	75.65	110.80	-35.15
5875.00	Peak	66.20	6.37	72.57	105.20	-32.63
5925.00	Peak	49.67	6.42	56.09	68.20	-12.11

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 195 of 234


#### 802.11n20 HT mode

**Proiect Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band1

:5180 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
 MHz	PK/QP/AV	dBµV	dB	dBµV/m	dBµV/m	dB
5150.00	Average	43.58	4.92	48.50	54.00	-5.50
5150.00	Peak	65.44	4.92	70.36	74.00	-3.64

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 196 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band1 :5180 MHz

:BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
 MHz	PK/QP/AV	dΒμ̈V	dB	dBµV/m	dBµV/m	dB
5150.00	Average	47.23	4.92	52.15	54.00	-1.85
5150.00	Peak	66.81	4.92	71.73	74.00	-2.27

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 197 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band2 :5320 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
MHz	PK/QP/AV	dBµV	dB	dBµV/m	dBµV/m	dB
5350.00	Average	43.87	5.21	49.08	54.00	-4.92
5350.00	Peak	65.85	5.21	71.06	74.00	-2.94
	5350.00	Mode MHz PK/QP/AV 5350.00 Average	Mode MHzReading Level PK/QP/AVReading Level dBμV5350.00Average43.87	Mode MHz         Reading Level PK/QP/AV         dBμV         dB           5350.00         Average         43.87         5.21	Mode Mode Peading Level         FS MHz           MHz         PK/QP/AV         dBμV         dB dBμV/m           5350.00         Average         43.87         5.21         49.08	Mode MHz         Reading Level PK/QP/AV         FS dBμV/m         @3m dBμV/m           5350.00         Average         43.87         5.21         49.08         54.00

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 198 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band2 :5320 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
5350.00	Average	46.90	5.21	52.11	54.00	-1.89
5350.00	Peak	67.14	5.21	72.35	74.00	-1.65

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 199 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band3 :5500 MHz

:BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dΒμV/m	dB
5460.00	Average	37.62	5.63	43.25	54.00	-10.75
5460.00	Peak	52.22	5.63	57.85	74.00	-16.15
5470.00	Peak	57.53	5.65	63.18	68.20	-5.02

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 200 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band3 :5500 MHz

:BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5460.00	Average	42.41	5.63	48.04	54.00	-5.96
5460.00	Peak	55.18	5.63	60.81	74.00	-13.19
5468.72	Peak	61.46	5.64	67.10	68.20	-1.10
5470.00	Peak	60.86	5.65	66.51	68.20	-1.69

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 201 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band3 :5700 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	_
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBµV/m	dB
5725.00	Peak	54.22	6.34	60.56	68.20	-7.64

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 202 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band3 :5700 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Fred	. Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MH:	z PK/QP/AV	•	dB	dBµV/m	dBµV/m	dB
5725.	00 Peak	60.10	6.34	66.44	68.20	-1.76
5727.	32 Peak	60.38	6.34	66.72	68.20	-1.48

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 203 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band4

:5745 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5650.00	Peak	49.04	6.04	55.08	68.20	-13.12
5700.00	Peak	61.17	6.32	67.49	105.20	-37.71
5720.00	Peak	72.74	6.33	79.07	110.80	-31.73
5725.00	Peak	73.94	6.34	80.28	122.20	-41.92

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 204 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band4

:5745 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5650.00	Peak	53.31	6.04	59.35	68.20	-8.85
5700.00	Peak	69.91	6.32	76.23	105.20	-28.97
5720.00	Peak	81.78	6.33	88.11	110.80	-22.69
5725.00	Peak	83.52	6.34	89.86	122.20	-32.34

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 205 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band4 :5825 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5850.00	Peak	64.84	6.39	71.23	122.20	-50.97
5855.00	Peak	64.39	6.38	70.77	110.80	-40.03
5875.00	Peak	53.68	6.37	60.05	105.20	-45.15
5925.00	Peak	47.74	6.42	54.16	68.20	-14.04

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 206 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n20 / Band4

:5825 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5850.00	Peak	80.08	6.39	86.47	122.20	-35.73
5855.00	Peak	77.34	6.38	83.72	110.80	-27.08
5875.00	Peak	69.70	6.37	76.07	105.20	-29.13
5925.00	Peak	51.67	6.42	58.09	68.20	-10.11

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 207 of 234


## 802.11n40 HT mode

**Proiect Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band1

:5190 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
 MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBμV/m	dB
 5150.00	Average	43.54	4.92	48.46	54.00	-5.54
5150.00	Peak	58.01	4.92	62.93	74.00	-11.07

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 208 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band1

:5190 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5150.00	Average	47.93	4.92	52.85	54.00	-1.15
5150.00	Peak	64.36	4.92	69.28	74.00	-4.72

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 209 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band2 :5310 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5350.00	Average	43.28	5.21	48.49	54.00	-5.51
5350.00	Peak	62.86	5.21	68.07	74.00	-5.93

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 210 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band2 :5310 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBμV/m	dBµV/m	dB
5350.00	Average	47.17	5.21	52.38	54.00	-1.62
5350.00	Peak	65.48	5.21	70.69	74.00	-3.31

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 211 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3 :5510 MHz

:BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBμV/m	dB
5460.00	Average	38.31	5.63	43.94	54.00	-10.06
5460.00	Peak	51.26	5.63	56.89	74.00	-17.11
5470.00	Peak	58.12	5.65	63.77	68.20	-4.43

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 212 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3

:5510 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5460.00	Average	43.15	5.63	48.78	54.00	-5.22
5460.00	Peak	55.34	5.63	60.97	74.00	-13.03
5468.64	Peak	60.93	5.64	66.57	68.20	-1.63
5470.00	Peak	61.09	5.65	66.74	68.20	-1.46

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 213 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3 :5670 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	_
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5725.00	Peak	54.34	6.34	60.68	68.20	-7.52

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 214 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band3

:5670 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



	Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
	MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
_	5725.00	Peak	60.71	6.34	67.05	68.20	-1.15

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 215 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band4 :5755 MHz

:BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dBµV	dB	dBµV/m	dBµV/m	dB
5650.00	Peak	52.79	6.04	58.83	68.20	-9.37
5700.00	Peak	66.87	6.32	73.19	105.20	-32.01
5720.00	Peak	74.69	6.33	81.02	110.80	-29.78
5725.00	Peak	75.51	6.34	81.85	122.20	-40.35

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 216 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band4 :5755 MHz

:BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBµV/m	dBµV/m	dB
5650.00	Peak	58.55	6.04	64.59	68.20	-3.61
5700.00	Peak	74.58	6.32	80.90	105.20	-24.30
5720.00	Peak	81.60	6.33	87.93	110.80	-22.87
5725.00	Peak	82.52	6.34	88.86	122.20	-33.34

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 217 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band4 :5795 MHz

:BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBµV/m	dB
5850.00	Peak	59.24	6.39	65.63	122.20	-56.57
5855.00	Peak	57.02	6.38	63.40	110.80	-47.40
5875.00	Peak	52.46	6.37	58.83	105.20	-46.37
5925.00	Peak	47.76	6.42	54.18	68.20	-14.02

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 218 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11n40 / Band4

:5795 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5850.00	Peak	68.97	6.39	75.36	122.20	-46.84
5855.00	Peak	68.62	6.38	75.00	110.80	-35.80
5875.00	Peak	64.34	6.37	70.71	105.20	-34.49
5925.00	Peak	52.19	6.42	58.61	68.20	-9.59

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 219 of 234


## 802.11ac80 VHT mode

**Proiect Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band1

:5210 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin
	Mode	Reading Level		FS	@3m	
MHz	PK/QP/AV	dΒμV	dB	dBμV/m	dBμV/m	dB
5150.00	Average	40.40	4.92	45.32	54.00	-8.68
5150.00	Peak	52.54	4.92	57.46	74.00	-16.54

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 220 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band1

:5210 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector	Spectrum	Factor	Actual	Limit	Margin	
	Mode	Reading Level		FS	@3m		
 MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB	_
5150.00	Average	47.93	4.92	52.85	54.00	-1.15	
5150.00	Peak	59.52	4.92	64.44	74.00	-9.56	

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 221 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band2

:5290 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



ıal Limit Margin
3 @3m
//m dBµV/m dB
93 54.00 -6.07
9 74.00 -9.81

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 222 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band2

:5290 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
 MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBμV/m	dB
 5350.00	Average	47.31	5.21	52.52	54.00	-1.48
5350.00	Peak	60.61	5.21	65.82	74.00	-8.18

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 223 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band3

:5530 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBµV/m	dBµV/m	dB
5460.00	Average	40.47	5.63	46.10	54.00	-7.90
5460.00	Peak	51.71	5.63	57.34	74.00	-16.66
5470.00	Peak	53.63	5.65	59.28	68.20	-8.92

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 224 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band3

:5530 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5460.00	Average	46.97	5.63	52.60	54.00	-1.40
5460.00	Peak	60.43	5.63	66.06	74.00	-7.94
5468.60	Peak	61.49	5.64	67.13	68.20	-1.07
5470.00	Peak	61.13	5.65	66.78	68.20	-1.42

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 225 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band4

:5775 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5650.00	Peak	52.94	6.04	58.98	68.20	-9.22
5700.00	Peak	61.37	6.32	67.69	105.20	-37.51
5720.00	Peak	64.93	6.33	71.26	110.80	-39.54
5725.00	Peak	65.17	6.34	71.51	122.20	-50.69

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 226 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band4

:5775 MHz :BE CH Low :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



	Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin	
_	MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB	_
	5647.40	Peak	61.16	6.02	67.18	68.20	-1.02	
	5650.00	Peak	59.13	6.04	65.17	68.20	-3.03	
	5700.00	Peak	68.23	6.32	74.55	105.20	-30.65	
	5720.00	Peak	71.07	6.33	77.40	110.80	-33.40	
	5725.00	Peak	71.62	6.34	77.96	122.20	-44.24	

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.




Page: 227 of 234

**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band4

:5775 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane Measurement Antenna Pol. :VERTICAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμV	dB	dBµV/m	dBµV/m	dB
5850.00	Peak	61.81	6.39	68.20	122.20	-54.00
5855.00	Peak	58.69	6.38	65.07	110.80	-45.73
5875.00	Peak	53.61	6.37	59.98	105.20	-45.22
5925.00	Peak	50.64	6.42	57.06	68.20	-11.14

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 228 of 234


**Project Number Operation Band Fundamental Frequency Operation Mode** EUT Pol.

:T190506W05 :802.11ac80 / Band4

:5775 MHz :BE CH High :E2 Plan

**Test Date** :2019-05-15 Temp./Humi. :20/50 Engineer :Kane

Measurement Antenna Pol. :HORIZONTAL



Freq.	Detector Mode	Spectrum Reading Level	Factor	Actual FS	Limit @3m	Margin
MHz	PK/QP/AV	dΒμ̈V	dB	dBμV/m	dBµV/m	dB
5850.00	Peak	66.66	6.39	73.05	122.20	-49.15
5855.00	Peak	65.73	6.38	72.11	110.80	-38.69
5875.00	Peak	60.45	6.37	66.82	105.20	-38.38
5925.00	Peak	53.80	6.42	60.22	68.20	-7.98

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 229 of 234

# 12 TRANSMISSION IN THE ABSENCE OF DATA

### **Standard Applicable** 12.1

According to §15.407(c)

The device shall automatically discontinue transmission in case of either absence of information to transmit or operational failure. These provisions are not intended to preclude the transmission of control or signaling information or the use of repetitive codes used by certain digital technologies to complete frame or burst intervals. Applicants shall include in their application for equipment authorization a description of how this requirement is met.

#### 12.2 Result

While the EUT is not transmitting any information, the EUT can automatically discontinue transmission and become standby mode for power saving. The EUT can detect the controlling signal of ASK message transmitting from remote device and verify whether it shall resend or discontinue transmission.



Page: 230 of 234

## 13 FREQUENCY STABILITY


## 13.1 Standard Applicable

Manufacturers of U-NII devices are responsible for ensuring frequency stability such that an emission is maintained within the band of operation under all conditions of normal operation as specified in the user's manual.

## 13.2 Measurement Procedure

- 1. The EUT was placed inside temperature chamber and powered and powered by nominal DC voltage.
- 2. Set EUT as normal operation.
- 3. Turn the EUT on and couple its output to spectrum.
- 4. Turn the EUT off and set the chamber to the highest temperature specified.
- 5. Allow sufficient time (approximately 30 min) for the temperature of the chamber to stabilize, turn the EUT and measure the operating frequency.
- 6. Repeat step with the temperature chamber set to the lowest temperature.

## 13.3 Test SET-UP



Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only. 除非另有說明,此報告結果僅對測試之樣品負責,同時此樣品僅保留90天。本報告未經本公司書面許可,不可部份複製。



Page: 231 of 234

# 13.4 Measurement Equipment Used:

EQUIPMENT TYPE	MFR	MODEL NUMBER	SERIAL NUM- BER	LAST CAL.	CAL DUE.
DC Power Supply	Agilent	E3640A	KR93300208	08/15/2018	08/14/2019
Spectrum Analyzer	Agilent	N9010A	MY53400256	11/21/2018	11/20/2019
TEMPERATURE	TEMPERA- TURE	HTC-1	EC-HY-01	04/18/2019	04/17/2020
DC Power Supply	GWINSTEK	SPS-3610	GPE880163	01/14/2019	01/13/2020
DC Block	Mini-Circuits	BLK-18-S+	31129(1)	02/26/2019	02/25/2020
Attenuator	Mini-Circuit	BW-S10W2+	1	02/26/2019	02/25/2020
Power Meter	Anritsu	ML2496A	1242004	10/23/2018	10/22/2019
Power Sensor	Anritsu	MA2411B	1207365	10/23/2018	10/22/2019
Power Sensor	Anritsu	MA2411B	1207368	10/24/2018	10/23/2019
Attenuator	Mini-Circuit	BW-S10W2+	3	02/26/2019	02/25/2020

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 232 of 234

#### 13.5 **Measurement Result**

## Startup:

Operation Mode	802.11 a	Test Date	05/21/2019
Temperature	: 24.5°C	Test By	Peter
Humidity	: 63%		

Test Temp.(°C)	Test Voltage(V)	Channel	Measured Frequency (MHz)	Spectrum Frequency (MHz)	ΔFrequency (MHz)
-30	4.8	36	5180	5,180.00558	-0.00000108
-30	3	36	5180	5,179.99708	0.00000056
25	3.6	36	5180	5,180.00010	-0.00000002
85	4.8	36	5180	5,179.99368	0.00000122
00	3	36	5180	5,180.00145	-0.00000028

## 2 Minutes:

Operation Mode	802.11 a	Test Date	05/21/2019
Temperature	: 24.5°C	Test By	Peter
Humidity	: 63%		

Test Temp.(°C)	Test Voltage(V)	Channel	Measured Frequency (MHz)	Spectrum Frequency (MHz)	ΔFrequency (MHz)
-30	4.8	36	5180	5,180.00649	-0.00000125
	3	36	5180	5,179.99678	0.00000062
25	3.6	36	5180	5,180.00958	-0.00000185
85	4.8	36	5180	5,180.00235	-0.00000045
	3	36	5180	5,180.00258	-0.00000050

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 233 of 234

## 5 Minutes:

Operation Mode	802.11 a	Test Date	05/21/2019
Temperature	: 24.5°C	Test By	Peter
Humidity	: 63%		

Test Temp.(°C)	Test Voltage(V)	Channel	Measured Frequency (MHz)	Spectrum Frequency (MHz)	ΔFrequency (MHz)
-30	4.8	36	5180	5,179.99382	0.00000119
	3	36	5180	5,180.00743	-0.00000143
25	3.6	36	5180	5,180.00548	-0.00000106
85	4.8	36	5180	5,180.00715	-0.00000138
	3	36	5180	5,180.00690	-0.00000133

## 10 Minutes:

Operation Mode	802.11 a	Test Date	05/21/2019
Temperature	: 24.5℃	Test By	Peter
Humidity	: 63%	,	

Test Temp.(°C)	Test Voltage(V)	Channel	Measured Frequency (MHz)	Spectrum Frequency (MHz)	ΔFrequency (MHz)
-30	4.8	36	5180	5,179.99439	0.00000108
	3	36	5180	5,179.99328	0.00000130
25	3.6	36	5180	5,180.00331	-0.00000064
85	4.8	36	5180	5,180.00604	-0.00000117
	3	36	5180	5,179.99286	0.00000138

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Page: 234 of 234

## 14 ANTENNA REQUIREMENT

### Standard Applicable 14.1

According to §15.203, an intentional radiator shall be designed to ensure that no antenna other than furnished by the responsible party shall be used with the device.

According to §15.407, If transmitting antennas of directional gain greater than 6 dBi are used, both the maximum conducted output power and the maximum power spectral density shall be reduced by the amount in dB that the directional gain of the antenna exceeds 6 dBi.

#### **Antenna Connected Construction** 14.2

The antenna is designed with unique RF connector and no consideration of replacement. Please see EUT photo for details.

~ End of Report ~

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.